THE

INTERNATIONAL

SCIENTIFIC SERIES



THE GETTY CENTER LIBRARY

Digitized by the Internet Archive
in 2025 with funding from
Getty Research Institute

https://archive.org/details/chemistryoflight00voge_2

THE

INTERNATIONAL SCIENTIFIC SERIES.

Each Book Complete in One Volume. Crown 8vo. cloth, 5*s*. unless otherwise described.

I. **FORMS of WATER**: in Clouds and Rivers, Ice and Glaciers. By J. TYNDALL, LL.D., F.R.S. With 25 Illustrations. Ninth Edition.

II. **PHYSICS and POLITICS**; or, Thoughts on the Application of the Principles of 'Natural Selection' and 'Inheritance' to Political Society. By WALTER BAGEHOT. Eighth Edition.

III. **FOODS.** By EDWARD SMITH, M.D., LL.B., F.R.S. With 156 Illustrations. Ninth Edition.

IV. **MIND and BODY**: the Theories of their Relation. By ALEXANDER BAIN, LL.D. With Four Illustrations. Eighth Edition.

V. **The STUDY of SOCIOLOGY.** By HERBERT SPENCER. Fourteenth Edition.

VI. **The CONSERVATION of ENERGY.** By BALFOUR STEWART, M.A., LL.D., F.R.S. With 14 Illustrations. Seventh Edition.

VII. **ANIMAL LOCOMOTION**; or, Walking, Swimming, and Flying. By J. B. PETTIGREW, M.D., F.R.S., &c. With 130 Illustrations. Third Edition.

VIII. **RESPONSIBILITY in MENTAL DISEASE.** By HENRY MAUDSLEY, M.D. Fourth Edition.

IX. **The NEW CHEMISTRY.** By Professor J. P. COOKE, of the Harvard University. With 31 Illustrations. Ninth Edition.

X. **The SCIENCE of LAW.** By Professor SHELDON AMOS. Sixth Edition.

XI. **ANIMAL MECHANISM**: a Treatise on Terrestrial and Aërial Locomotion. By Professor E. J. MAREY. With 117 Illustrations. Third Edition.

XII. **The DOCTRINE of DESCENT and DARWINISM.** By Professor OSCAR SCHMIDT (Strasburg University). With 26 Illustrations. Seventh Edition.

XIII. **The HISTORY of the CONFLICT between RELIGION and SCIENCE.** By J. W. DRAPER, M.D., LL.D. Twentieth Edition.

XIV. **FUNGI**: their Nature, Influences, Uses, &c. By M. C. COOKE, M.A., LL.D. Edited by the Rev. M. J. BERKELEY, M.A., F.L.S. With Illustrations. Fourth Edition.

XV. **The CHEMISTRY of LIGHT and PHOTOGRAPHY.** By Dr. HERMANN VOGEL. With 100 Illustrations. Fifth Edition.

London: KEGAN PAUL, TRENCH, & CO., 1 Paternoster Square.

XVI. The **LIFE** and **GROWTH** of **LANGUAGE**. By William Dwight Whitney. Sixth Edition.

XVII. **MONEY** and the **MECHANISM** of **EXCHANGE**. By W. Stanley Jevons, M.A., F.R.S. Eighth Edition.

XVIII. The **NATURE** of **LIGHT**, with a General Account of **PHYSICAL OPTICS**. By Dr. Eugene Lommel. With 188 Illustrations and a Table of Spectra in Chromo-lithography. Fourth Edition.

XIX. **ANIMAL PARASITES** and **MESSMATES**. By Monsieur Van Beneden. With 83 Illustrations. Third Edition.

XX. **FERMENTATION**. By Professor Schützenberger. With 28 Illustrations. Fourth Edition.

XXI. The **FIVE SENSES** of **MAN**. By Professor Bernstein. With 91 Illustrations. Fifth Edition.

XXII. The **THEORY** of **SOUND** in its **RELATION** to **MUSIC**. By Professor Pietro Blaserna. With numerous Illustrations. Third Edition.

XXIII. **STUDIES** in **SPECTRUM ANALYSIS**. By J. Norman Lockyer, F.R.S. With Six Photographic Illustrations of Spectra, and numerous Engravings on Wood. Fourth Edition. 6*s*. 6*d*.

XXIV. A **HISTORY** of the **GROWTH** of the **STEAM ENGINE**. By Professor R. H. Thurston. With numerous Illustrations. Fourth Edition.

XXV. **EDUCATION** as a **SCIENCE**. By Alexander Bain, LL.D. Seventh Edition.

XXVI. The **HUMAN SPECIES**. By Professor A. de Quatrefages, Membre de l'Institut. Fourth Edition.

XXVII. **MODERN CHROMATICS**. With Application to Art and Industry. By Ogden N. Rood. Second Edition. With 130 original Illustrations.

XXVIII. The **CRAYFISH**: an Introduction to the Study of Zoology. By T. H. Huxley, F.R.S. Fifth Edition. With 82 Illustrations.

XXIX. The **BRAIN** as an **ORGAN** of **MIND**. By H. Charlton Bastian, M.D. Third Edition. With 184 Illustrations.

XXX. The **ATOMIC THEORY**. By Professor A. Wurtz. Translated by E. Cleminshaw, F.C.S. Fifth Edition.

XXXI. The **NATURAL CONDITIONS** of **EXISTENCE** as they affect **Animal Life**. By Karl Semper. Third Edition. With 2 Maps and 106 Woodcuts.

London: KEGAN PAUL, TRENCH, & CO., 1 Paternoster Square.

XXXII. **GENERAL PHYSIOLOGY of MUSCLES and NERVES.** By Prof. J. ROSENTHAL. Third Edition. With 75 Illustrations.

XXXIII. **SIGHT:** an Exposition of the Principles of Monocular and Binocular Vision. By JOSEPH LE CONTE, LL.D. Second Edition. With 132 Illustrations.

XXXIV. **ILLUSIONS: a Psychological Study.** By JAMES SULLY. Third Edition.

XXXV. **VOLCANOES: what they are and what they teach.** By JOHN W. JUDD, F.R.S. Fourth Edition. With 96 Illustrations.

XXXVI. **SUICIDE: an Essay on Comparative Moral Statistics.** By Professor H. MORSELLI. Second Edition.

XXXVII. **THE BRAIN AND ITS FUNCTIONS.** By J. LUYS, Physician to the Hospice de la Salpêtrière. With numerous Illustrations. Second Edition.

XXXVIII. **MYTH AND SCIENCE: an Essay.** By TITO VIGNOLI. Third Edition.

XXXIX. **THE SUN.** By C. A. YOUNG, Ph.D., LL.D. Third Edition. With numerous Illustrations.

XL. **ANTS, BEES, and WASPS.** A Record of Observations on the Habits of the Social Hymenoptera. By Sir JOHN LUBBOCK, Bart., M.P. Ninth Edition. With 5 Chromo-lithographic Plates.

XLI. **ANIMAL INTELLIGENCE.** By GEORGE J. ROMANES, LL.D., F.R.S. Fourth Edition.

XLII. **The CONCEPTS and THEORIES of MODERN PHYSICS.** By J. B. STALLO. Third Edition.

XLIII. **DISEASES of MEMORY.** An Essay in the Positive Psychology. By TH. RIBOT. Third Edition.

XLIV. **MAN BEFORE METALS.** By N. JOLY, Correspondent de l'Institut de France. Fourth Edition. With 148 Illustrations.

XLV. **THE SCIENCE of POLITICS.** By Prof. SHELDON AMOS. Third Edition.

XLVI. **ELEMENTARY METEOROLOGY.** By ROBERT H. SCOTT. Fourth Edition.

XLVII. **THE ORGANS of SPEECH.** By GEORG HERMANN VON MEYER. With 47 Illustrations.

XLVIII. **FALLACIES:** a View of Logic from the Practical Side. Second Edition. By ALFRED SIDGWICK. Second Edition.

London: KEGAN PAUL, TRENCH, & CO., 1 Paternoster Square.

XLIX. **THE ORIGIN OF CULTIVATED PLANTS.** By ALPHONSE DE CANDOLLE. Second Edition.

L. **JELLY FISH, STAR FISH, AND SEA URCHINS.** Being a Research on Primitive Nervous Systems. By G. J. ROMANES, LL.D., F.R.S.

LI. **THE COMMON SENSE OF THE EXACT SCIENCES.** By the late WILLIAM KINGDON CLIFFORD. Second Edition. With 100 Figures.

LII. **PHYSICAL EXPRESSION:** its Modes and Principles. By FRANCIS WARNER, M.D., F.R.C.P. With 50 Illustrations.

LIII. **ANTHROPOID APES.** By ROBERT HARTMANN. With 63 Illustrations. Second Edition.

LIV. **THE MAMMALIA IN THEIR RELATION TO PRIMEVAL TIMES.** By OSCAR SCHMIDT. With 51 Woodcuts.

LV. **COMPARATIVE LITERATURE.** By H. MACAULAY POSNETT, LL.D.

LVI. **EARTHQUAKES and other EARTH MOVEMENTS.** By Prof. JOHN MILNE. With 38 Figures. Second Edition.

LVII. **MICROBES, FERMENTS, and MOULDS.** By E. L. TROUESSART. With 107 Illustrations.

LVIII. **GEOGRAPHICAL and GEOLOGICAL DISTRIBUTION of ANIMALS.** By Prof. A. HEILPRIN.

LIX. **WEATHER:** a Popular Exposition of the Nature of Weather Changes from Day to Day. By the Hon. RALPH ABERCROMBY. With 96 Figures. Second Edition.

LX. **ANIMAL MAGNETISM.** By ALFRED BINET and CHARLES FÉRÉ. Second Edition.

LXI. **MANUAL OF BRITISH DISCOMYCETES,** with descriptions of all the Species of Fungi hitherto found in Britain included in the Family, and Illustrations of the Genera. By WILLIAM PHILLIPS, F.L.S.

LXII. **INTERNATIONAL LAW.** With Materials for a Code of International Law. By Professor LEONE LEVI.

LXIII. **The GEOLOGICAL HISTORY of PLANTS.** By Sir J. WILLIAM DAWSON. With 80 Illustrations.

LXIV. **THE ORIGIN OF FLORAL STRUCTURES THROUGH INSECT AND OTHER AGENCIES.** By Prof. G. HENSLOW.

LXV. **On the SENSES, INSTINCTS, and INTELLIGENCE of ANIMALS, with special reference to INSECTS.** By Sir JOHN LUBBOCK, Bart., M.P. With 118 Illustrations. Third Edition.

LXVI. **THE PRIMITIVE FAMILY IN ITS ORIGIN AND DEVELOPMENT.** By C. N. STARCKE.

London: KEGAN PAUL, TRENCH, & CO., 1 Paternoster Square.

THE INTERNATIONAL SCIENTIFIC SERIES.

VOL. XV.

Woodbury process.

See p 188.

PHOTOGRAPH OF THE MOON.

(From RUTHERFURD'S original negative.)

THE CHEMISTRY OF LIGHT AND PHOTOGRAPHY

IN THEIR APPLICATION

TO ART, SCIENCE, AND INDUSTRY.

BY

DR. HERMANN VOGEL,

PROFESSOR IN THE ROYAL INDUSTRIAL ACADEMY OF BERLIN.

WITH 100 ILLUSTRATIONS.

FIFTH EDITION.

CONS.
SPECIAL
NH
510
V87
1888

LONDON:
KEGAN PAUL, TRENCH & CO., 1, PATERNOSTER SQUARE.
1888.

(*The rights of translation and of reproduction are reserved.*)

THE GETTY CENTER
LIBRARY

PREFACE.



Among the splendid scientific discoveries of this century, two are specially prominent—Photography and Spectrum Analysis. Both belong to the province of Optics, and at the same time to that of Chemistry. While Spectrum Analysis has, down to the present time, remained almost exclusively in the hands of scientific men as a most important means of research, Photography passed immediately into practical life, spread over almost every branch of human effort and knowledge, and now there is scarcely a single field in the universe of visible phenomena where its productive influence is not felt.

It brings us faithful pictures of remote regions, of strange forms of stratification, of fauna, and of flora; it fixes the transient appearances of solar eclipses; it is of great utility to the astronomer and geographer; it registers the movements of the barometer and thermometer; it has become connected with porcelain painting and the various forms of printing; it makes the noblest works of art accessible to those of slender means.

But it does more than this. A new science has been called into being by Photography, the Chemistry of Light; it has given new conclusions respecting the operations of the vibrating ether of light. It is true that these services, rendered by Photography to art and science, are only appreciated by the few. Men of science have in great measure neglected this subject after the first enthusiasm excited by Daguerre's discovery had passed away; but seldom is Photography mentioned in the text books of physics and chemistry.

This consideration has induced the Author to lay before the public a popular treatise of Photography and the Chemistry of Light, showing their important bearing on science, art, and industry. The Publisher has met the Author in the readiest manner, not only by providing numerous woodcuts to explain the text, but by obtaining specimens of the latest discoveries in Photography, at a considerable cost; so that the illustrations afford the reader an opportunity of seeing of what value Photography can be in connection with the printing press. The Author trusts the work may meet a friendly reception.

THE AUTHOR.

BERLIN, *January*, 1874.

TABLE OF CONTENTS.

CHAPTER		PAGE
I.	Development of our Photo-chemical Knowledge ...	1
II.	The Daguerreotype	14
III.	Paper Photography and the *Lichtpaus*, or New Talbot Process	23
IV.	The Development of Modern Photography	31
V.	The Negative Process	37
VI.	The Positive Process	46
VII.	Light as a Chemical Agent	54
VIII.	Chemical Effect of Different Sources of Light	67
IX.	On the Refraction of Light	81
X.	Photographic Optical Apparatus	87
XI.	The Chemical Effects of Light	102
	(*a*) Action of Light on the Elements	104
	(*b*) Chemical Action of Light on Salts of Silver ...	106
XII.	On the Correctness of Photographs	117
	(*a*) Influence of the Individuality of the Photographer	117
	(*b*) Influence of the Object, of the Apparatus, and of the Process	119
XIII.	Light, Shade, and Perspective	131
XIV.	The Applications of Photography	146
	§ I. Portrait Photography	146
	§ II. Landscape Photography	155
	§ III. Photogrammetry, or Surveying by Photography	162
	§ IV. Astronomical Photography	167

CHAPTER		PAGE
XIV.	The Applications of Photography (*continued*).	
	§ V. The Application of Photography to the Observation of Scientific Instruments ...	195
	§ VI. Photography and Medical Research ...	197
	§ VII. Photography and the Microscope	200
	§ VIII. Microscopic Photographs and the Photographic Pigeon Post	204
	§ IX. Pyro-Photography	207
	§ X. Magic Photography	208
	§ XI. Scamoni's Heliographic Process	210
	§ XII. Photography and Jurisprudence	212
	§ XIII. Photography, Industry, and Art	213
XV.	Photography with Chromium Compounds	215
	§ I. Combinations of Chromium	216
	§ II. Heliography with Salts of Chromium ...	219
	§ III. The Production of Photo-reliefs	224
	§ IV. Printing in Relief	229
	§ V. Pigment Printing	232
	§ VI. The Albert-type	235
	§ VII. Aniline Printing	238
	§ VIII. Photo-Lithography	241
	IX. Encaustic Photography with Salts of Chromium	249
	§ X. Photography and the Sand-blast Process ...	252
	§ XI. The Photometer	254
	§ XII. The Chemical Action of Light and the Pea-Sausage	256
XVI.	Photography with Iron, Uranium, and Copper Compounds	257
XVII.	The Change of Glass under the Influence of Light ...	261
XVIII.	Photography in Natural Colours	264
XIX.	Photography as a Subject to be taught in Art and Industrial Schools	269

CHAPTER PAGE

XX. The Latest Improvements in Photography down to 1883 277

§ I. New Developments of the *Lichtpaus* Process 277

§ II. The New Emulsion Dry-Plate Process ... 279

§ III. Platinotype 285

§ IV. Photography by Electric Light 286

§ V. Photography as a means of Scientific Investigation 289

§ VI. Book-Illustration by Photography 294

Photogravure 296

INDEX 299

THE CHEMISTRY OF LIGHT.

CHAPTER I.

DEVELOPMENT OF OUR PHOTO-CHEMICAL KNOWLEDGE.

Various Effects of Light—Physical and Chemical Changes—Bleaching Effect of Light—Action of Light upon Chloride of Silver and Lunar Caustic (Nitrate of Silver)—Chemical Ink—Pictures upon Paper prepared with Nitrate of Silver—The Researches of Wedgwood and Davy — The Camera Obscura — Niepce — Effects of Light upon Asphalt—Heliography—Its Application to the Production of Paper Money—Iodide of Silver—Discovery of the Daguerreotype.

THE light which radiates from the great central body of our planetary system produces manifold effects upon the animate and inanimate world, some of which are at once evident to the senses, and have been known for thousands of years, while others, again, are not so apparent to the eye, and have been discovered, examined, and utilized only through the observations of modern times.

The first effect which every person, however uncultivated, notices when, after the darkness of night, the sun

rises, is that bodies become visible. The rays from the source of light are thrown back (reflected) from various bodies, they reach our eyes, and produce an impression upon the retina, the result of which is the perception of material objects by the eye. But soon another effect is observed, not by the eye, but by the sense of feeling. The sun's rays not only illumine bodies upon which they fall, but heat them, as is felt when the hand is held in the rays. Both effects, the shining, or illuminating, and the warming effects of the sunbeams, differ very essentially from each other. The illuminating effect we perceive instantaneously; the heating effect is only felt after a certain time, which may be shorter or longer, as the heating power of the sun is stronger or weaker.

In addition to these two effects of sunlight, there is a third, which generally requires a still longer period to make itself noticed, and which cannot be directly perceived either by the eye or by the sense of feeling, but only by the peculiar changes which light produces in the material world. These are the chemical effects of light.

If we take a piece of wood, and bend or saw it, we change its form; if we rub it, it becomes warm—we change its temperature, but it still remains wood. These changes, which do not affect the substance or matter (*Stoff*) of a body, we term physical.

But if we set fire to a piece of wood, strong-smelling gases ascend, ashes are deposited, and a black residue remains, which is totally different from the wood. By this process a new substance—charcoal—has been produced. *Material* changes of this kind we term chemical changes;—and such chemical changes are, in an especial

manner, produced by heat. If, for instance, we heat a bright iron wire red hot, it undergoes apparently only a physical (not a material) change. But, if we allow it to cool, we find the bright rod has become dull and black; that it has acquired a brittle, black surface, which easily breaks away on bending the rod, and differs entirely from the bright, tough, flexible iron. Here again a chemical change, that is to say, a change of substance, has taken place; the iron has been converted into another body, into iron scale, because it has combined with a component part of the surrounding air—with oxygen.

Chemical changes of this kind are not only produced by heat but also by light.

It has long been known that when the colours with which fabrics are dyed are not the so-called fast colours, they fade in the light, that is, become paler. In this case the colouring matter changes into a colourless or differently coloured body; and that this is the effect of light is evident from the fact that those parts of the material in question which are covered up from the light —beneath the folds, for example—remain unchanged. This effect of light upon colour has been long turned to practical use in the bleaching of linen. The unbleached fabric is spread out in the sunlight, and repeatedly moistened with water; and thus, through the combined effect of light and moisture, the dark colouring substance becomes gradually soluble, and can then be removed from the linen by boiling it in alkaline lye.

It was formerly believed that the changes we have just described were caused by the heat which is produced in bodies by the sun's rays. That this is an erroneous

view is evident from the fact that fabrics dyed in colours which are not fast can be exposed for months together in the temperature of a hot oven without any bleaching effect; and further, that wax, which the sunlight likewise bleaches, becomes darker, rather than paler, through heat.

As we remarked before, the bleaching effect of sunlight is a slow process, and this circumstance renders the phenomenon less striking. A sudden and rapid occurrence surprises us, and stirs us up to inquire and to reflect.

In the mines of Freiberg is occasionally found a vitreous dull-shining silver ore, which, on account of its appearance, is called horn silver (chloride of silver).

This horn silver consists of silver and chlorine in chemical combination, and can be artificially produced by passing chlorine gas over metallic silver. This horn silver in its original position is completely colourless, but as soon as it is exposed to the daylight it assumes, in a few minutes, a violet tint. This effect of light has long excited the astonishment of men of science.

In another substance containing silver this phenomenon is still more apparent. Silver, placed in nitric acid, is dissolved with effervescence, and if the solution is evaporated, a solid mass of crystals is obtained. This is not silver, but a combination of this body with nitric acid. This nitrate of silver is totally different from ordinary silver; it is easily soluble in water; it has a bitter, disagreeable taste; it fuses readily and destroys organic matter; and it is therefore used as a corrosive agent, under the name of lunar caustic.

It has been long known that the fingers which have

grasped lunar caustic, skin which has been cauterized by it, or anything sprinkled with a solution of it, quickly assume a dark colour. This can be at once observed by moistening a small piece of paper with a silver solution, allowing it to dry, and then placing it in the light.

These properties were soon made use of to produce a so-called indelible ink, which is nothing more than a solution of one part of nitrate of silver in four parts of water, mixed with a thick solution of gum. Written characters traced with it upon linen cloth are pale; but, when dried in the sunlight, quickly become dark brown, and are not injured by washing. Ink of this kind is much used in hospitals for marking linen. A quill, not a steel pen, must be used, as steel decomposes the nitrate of silver. It is not unusual to print the characters by means of wooden type.

From the discovery of the blackening of paper saturated with lunar caustic to the invention of photography there was but a step; yet it was long before any one thought of producing pictures by the help of light alone, and still longer before these attempts were crowned with success.

Wedgwood, the son of the celebrated manufacturer of porcelain who produced the popular Wedgwood ware, and Davy, the celebrated chemist, made the first attempts in the year 1802. They placed flat bodies, such as the leaves of plants, upon paper prepared with nitrate of silver. Light was thus kept from the parts of the paper covered by the objects, these parts remained white, whilst the uncovered portions of the paper were blackened by the light; and thus was produced a white outline, or

"white silhouette," of the superimposed objects upon a black ground. (See Figs. 1 and 2.)

Fig. 1.

Fig. 2.

Wedgwood produced in this manner copies of drawings upon glass, in white lines upon a black ground; and this process became the basis, in modern times, of a mode of treatment which attained the highest importance, coming under the name of the *lichtpaus* process.

Unfortunately these pictures were not durable. They had to be kept in the dark, and could only be exhibited in a subdued light. If they remained long exposed to the light, the white parts also became black; and thus the picture disappeared. No means were then known to make the pictures durable, that is to say, to make them unalterable by light, or, as we now say, to *fix* them. But the first step towards the discovery of photography was made; and the idea of producing pictures of objects without the help of the draughtsman became, after these first attempts, so extremely attractive that, from that time, both in England and in France, a large number of

persons occupied themselves with the subject in private with the greatest enthusiasm.

It is clear that by the process of Wedgwood and Davy only flat bodies could be copied, and, notwithstanding all the improvements of which the process was still susceptible, it admitted of only a limited application.

But Wedgwood had already conceived the idea of the possibility of producing pictures of any bodies whatsoever by the action of light on sensitized paper. He tried to effect this by the aid of an interesting optical instrument which has the property of forming flat images of solid objects. This instrument is the camera obscura.



Fig. 3.

If a small hole be made in the window shutter of a completely darkened room on a sunny day, a clear image of the landscape will be seen on the opposite wall of the room.

Let *a* be a poplar, *o* the hole, and *w* the back wall of the room, then from each point of the poplar rays of light will travel towards the hole, and beyond that in a straight line to the wall. It is now clear that to the point *a'* light can only arrive from the point *a* of the

poplar, which is situated on the extension of the line $a'o$. Therefore this point of the wall can only reflect light, which in its colour and position corresponds to the point a. The same remark applies to the points f and g, and the result accordingly is that on the wall an inverted image of the tree is visible. This was first observed by Porta, the celebrated Italian physicist of the 16th century, whose house, we are told by contemporaries, was seldom free from visitors in search of knowledge. An improved instrument was soon obtained by using instead of the room a small box (Fig. 4) which had a movable semi-transparent screen in place of the solid wall. On this screen



Fig. 4.

the image of an object in front of the box is clearly visible, if a minute hole is made in the front side, which is best if composed of a thin tin plate.*

These images appear still more beautiful if, instead of a hole, a glass lens, or, as it is called, a burning-glass, is substituted. This lens, or "burning-glass," at a certain distance, which is equal to that of its focus, casts a distinct image of objects—which is much better defined and clearer than that which is produced by a hole.

* To prevent the access of light the head must be covered with a cloth.

In this improved form the instrument was employed by Wedgwood and Davy. Their idea was to fix on sensitized paper the image produced upon the screen. They fastened a piece of paper saturated with a silver salt upon the place of the image, and left it there for several hours—unfortunately without result. The image was not bright enough to make a visible impression upon the sensitized paper, or the paper was not sufficiently sensitive. It now became necessary to find a more sensitive preparation to catch the indistinct image; and this was achieved by a Frenchman—Nicophore Nièpce. He had recourse to a very peculiar substance, the sensitiveness of which to light was before unknown to any one—asphalt, or the bitumen of Judæa. This black mineral pitch, which is found near the Dead Sea, the Caspian, and many other places, is soluble in ethereal oils—such as oil of turpentine, oil of lavender—as well as in petroleum, ether, etc. If a solution of this substance is poured upon a metal plate, and allowed to cover the surface, a thin fluid coating adheres to it, which soon dries and leaves behind a thin brown film of asphalt. This film of asphalt does not become darker in the light, but it loses by light its property of solubility in ethereal oils.

If such a plate, therefore, is put in the place of the image of the camera obscura, the asphalt coating will remain soluble on all the dark places (shadows) of the image, whilst the light spots will become insoluble. The eye, it is true, does not perceive these changes; the plate, after being exposed to the influence of light, appears the same as before the exposure. But if oil of lavender is poured over the coating of asphalt, it dissolves

all the spots that had remained unchanged, and leaves behind all those that had been changed by light, that is, had been rendered insoluble. Thus, after several hours exposure in the camera obscura, and subsequent treatment with ethereal oils, Nièpce succeeded, in fact, in obtaining a picture. This picture was very imperfect it is true, but interesting as a first attempt to fix the images of the camera, and still more interesting as evidence that there are bodies which lose their solubility in the sunlight. This fact was again made use of long after the death of Nièpce, and it led to one of the finest applications of photography, that of heliography, or the combination of photography with copper-plate printing, which Nièpce himself, to all appearance, had already known.

A copper-plate print is produced thus:—A smooth plate of copper is engraved with the burin (or graving tool); that is to say, the lines which should appear black in the picture are cut deeply in the plate. In producing impressions, ink is first rubbed into these cuts, and then a sheet of paper is placed upon the plate and subjected to the action of a roller press, whereby the ink is transferred to the paper and produces the copper-plate impression. Nièpce endeavoured to utilize light in producing these engraved copper plates in place of the laborious process of cutting. To effect this he covered the copper plate with asphalt, as before stated, and exposed it to the light beneath a drawing on paper. In this case the black lines of the drawing kept back the light; and, accordingly, in these places the asphalt coating remained soluble; under the white paper, on the contrary, it became insoluble. Therefore, when lavender oil was afterwards

poured over the plate, the parts of the asphalt which had become insoluble adhered to the plate, whilst the soluble parts were dissolved and removed; and the plate in those places was laid bare. Thus a film of asphalt was obtained on the plate in which the original drawing appeared as if engraved.

If a corrosive acid is now poured on such a plate, it can only act on the metal in those places where it is not protected by the asphalt; and in such places his metal plate was in fact eaten into. Thus an incised drawing upon a metal plate was produced by the corrosive action of the acid, and a plate was obtained which, after cleaning, could be used for printing like an engraved copper plate. Copper-plate prints of this kind have been found amongst the papers left by Nièpce, which he called "heliographs," and showed to his friends as far back as 1826. This method, in an improved form, is still in use at the present day, especially in the printing of paper money, when it is requisite to produce a number of engraved plates which are all to be absolutely alike, so that one piece of paper money may perfectly correspond to another, and may therefore be distinguished from counterfeits. In this way the arms and the inscription on the face of the Prussian ten-thaler notes are printed off from heliographic plates. Thousands of people carry photographic impressions in their pocket-books, without knowing it. Nor is there any occasion to fear that these notes can be imitated easily by the help of photography or heliography. We shall show later on, that the ground tint, the paper itself, and the colour of the inscription present well-devised obstacles to all such imitations, and make them very difficult, if not impossible.

Nièpce's impressions were undoubtedly very imperfect, and therefore remained unnoticed. He himself gave them up, and again entered upon a series of experiments to fix the charming images of the camera obscura. In 1829 Daguerre joined him; and both carried on experiments in common until 1833, when Nièpce died without having obtained the reward of his long-continued efforts. Daguerre went on with the experiments; and he would not, perhaps, have got further than Nièpce if a fortunate accident had not worked in his favour.

He made experiments with iodide of silver plates, which he produced by exposing silver plates to the vapour of iodine, a peculiar and very volatile chemical element. Under this treatment, the silver plate assumes a pale yellow colour, which is peculiar to the compound of iodine and silver. These plates of iodide of silver are sensitive to light, they take a brown colour when exposed to it, and an image is produced upon them when they are exposed to the action of light in the camera. A very long exposure to light, however, is necessary to this end; and the thought could scarcely have arisen of taking the likeness of any person in this manner, since he would have been obliged to remain motionless for hours.

One day Daguerre placed aside as useless, in a closet in which were some chemical substances, several plates that had been exposed too short a time to the light, and therefore as yet showed no image. After some time he happened to look at the plates, and was not a little astonished to see an image upon them. He immediately divined that this must have arisen through the operation on the plates of some chemical substance which was

lying in the closet. He therefore proceeded to take out of the closet one chemical after the other, and placed there plates which had been exposed to the light, when, after remaining there some hours, images were again produced upon them. At length he had removed in succession all the chemical substances from the closet; and still images were produced upon the plates. He was now on the point of believing the closet to be bewitched, when he discovered on the floor a dish containing mercury, which he had hitherto overlooked. He conceived the notion that the vapour from this substance—for mercury gives off vapour even at an ordinary temperature—must have been the magic power which produced the image. To test the accuracy of this supposition, he again took a plate that had been exposed to light for a short time in the camera obscura, and on which no image was yet visible. He exposed this plate to the vapour of mercury, and, to his intense delight, an image appeared, and the world was enriched by a most beautiful discovery.

CHAPTER II.

THE DAGUERREOTYPE.

Its Publication and extended Use—Method—Improvements—Discovery of the Portrait Lens—Æsthetic Effects of the Daguerreotype.

MANY persons at the present day, who have before their eyes the grand productions of paper photography, such, for example, as life-size portraits, view doubtless with pity, or even contempt, the little pictures called daguerreotypes, from their inventor. The appearance of these pictures is no doubt injured by the ugly mirror-like surface which prevents a clear view of them. No such objections were felt in the year 1839, when Daguerre's discovery was first spread abroad by report. Pictures were said to be produced without a draughtsman by the operation of the sun's rays alone. That was of itself wonderful; but it was still more wonderful that, by the mysterious operation of light, every substance impressed its own image on the plate. How many extravagant hopes, how many evil prognostications, were associated with the report of this mysterious invention?

It was prophesied that painting would come to an end, and that artists would die of starvation. Every one

hoped that he could himself prepare images of any objects which he desired.

A friend is leaving home: in an instant his image is permanently retained at the moment of departure. A joyous company is assembled: a picture is taken of it at once as a souvenir. All objects were to be thus retained as pictures by the chemical action of light: the landscape glowing with the magical effects of sunset, the favourite spot in the garden, the daily life of the streets—men, animals, everything.

Then came sceptics who declared the whole thing impossible. These persons were reduced to silence by the testimony of Humboldt, Biot, Arago, the three celebrated scientific men to whom Daguerre disclosed his secret in 1838. The excitement grew. Through the influence of Arago an application was made to secure to Daguerre a yearly pension of 6000 francs, provided he made public his discovery. The French Chamber of Deputies agreed; and, after a long and tiresome delay, the discovery was at length disclosed to the expectant world.

It was at a memorable public *séance* of the French Academy of Sciences in the Palais Mazarin, on the 19th of August, 1839, that Daguerre, in the presence of all the great authorities in art, science, and diplomacy, who were then in Paris, illustrated his process by experiment.

Arago declared that "France had adopted this discovery, and was proud to hand it as a present to the whole world;" and henceforth, unhindered by the quackery of mystery, and unfettered by the right of patent,*

* It was only in England that the process was patented, before its publication on the 15th of July, 1839.

the discovery of Daguerre made the round of the civilized world.

Daguerre quickly gathered round him a number of pupils from all quarters of the globe; and they transplanted the process to their homes, and became in their turn centres of activity, which daily added to the number of disciples of the art.

Sachse, a dealer in art still living in Berlin, was initiated into Daguerre's discovery on the 22nd of April, 1839, and was appointed Daguerre's agent in Germany. On the 22nd of September, four weeks after the publication of the discovery, Sachse had already produced the first picture at Berlin. These pictures were gazed at as wonders, and each copy was paid for at the rate of from £1 to £2; while original impressions of Daguerre fetched as much as 120 francs. On the 30th of September Sachse made experiments in the Park of Charlottenburg, in the presence of King Friedrich Wilhelm the Fourth. In October the earliest Daguerre apparatuses were sold in Berlin. The first set of apparatus was purchased by Beuth for the Royal Academy of Industry at Berlin, and is still to be seen there. After the introduction of the apparatus, it was in the power of every one to carry out the system; and a great number of daguerreotypists started into existence. Men of science, too, cultivated (more than they do now) the new art: among others, the physicists, Professors Karsten, Moser, Nörrenberg, Von Ettinghausen—nay, even ladies, as Frau Professor Mitscherlich.

The first objects photographed by Sachse were architectural views, statuary, and paintings, which for two years found a ready sale as curiosities. It was in 1840

that he first represented groups of living persons, and in this way photography became especially an art of portraiture. It made the taking of portraits its principal means of support, and in two years there were daguerreotypists in all the capitals of Europe.

In America a painter, Professor Morse, afterwards the inventor of the Morse telegraph, was the first to prepare daguerreotypes; and his coadjutor was Professor Draper.

Let us now consider more closely the process employed in producing daguerreotype plates. A silver plate, or in the place of it a silver-plated copper plate, serves to receive the image. It is rubbed smooth by means of tripoli and olive oil; and then receives its highest polish with rouge and water and cotton-wool. It is only a perfectly polished plate that can be used for the process. This burnished plate is placed with its polished side downward upon an open square box, the bottom of which is strewn down with a thin layer of iodine. This iodine evaporates, its vapours come into contact with the silver, and instantly combine with it. By this means the plate first assumes a yellow straw-colour, next red, then violet, and lastly blue. The plate, protected from the light, is then placed in the camera obscura, where the image on the ground-glass slide is visible, and "exposed" for a certain time. It is afterwards brought back into the dark, and put into a second box, upon the metal floor of which there is mercury. This mercury is slightly warmed by means of a spirit lamp. At first no trace of the image is visible on the plate. This does not appear until the mercury vapour is condensed on those parts of the plate which have been affected by the light;

and this condensation is in proportion to the change which the light has caused. During this process the mercury is condensed into very minute white globules, which can be very well discerned under the microscope. This operation is called the development of the picture.

After the development the remaining iodide of silver, which is still sensitive to light, must be removed to render the image durable, that is, "to fix it." This is effected by using a solution of hypo-sulphite of soda, which dissolves the iodide of silver. Nothing more is required after this than to wash with water and dry, and the daguerreotype is completed. Sometimes, in order to protect the picture, it was usual to gild it. A solution of chloride of gold was poured over, and then it was warmed; a thin film of gold was deposited, which contributed essentially to the durability of the pictures. A picture of this nature, however, is easily injured, and requires the protection of frame and glass.

Daguerre's first pictures needed an exposure of 20 minutes—too long for taking portraits. But soon after it was found that bromine, a rare substance, having many points of resemblance with iodine, employed in combination with the latter, produced much more sensitive plates, which required far less time, perhaps not more than from one to two minutes, for exposure.

Many of us, perhaps, still remember the early period of photography, when persons were obliged to sit in the full sunlight, and allow the dazzling rays to fall directly upon the face—a torture which is clearly marked and visible on the portraits still preserved of these photographic victims, in the blackened shadows, the distorted muscles, and the half-closed eyes. These caricatures

could certainly not bear any comparison with a good drawing from life, nor probably would portrait-photography have ever succeeded if it had not become possible to obtain good results in a moderated light. This was attained by the invention of a new lens—the double objective portrait lens of Professor Petzval, of Vienna.

This new lens was distinguished by the fact that it produced a much brighter picture than the old lens of Daguerre, so that it was now possible to take less dazzlingly illuminated objects. This lens was invented by Petzval in 1841. Voigtländer ground the lens according to his directions, and soon one of Voigtländer's lenses became indispensable to every daguerreotypist. By employing bromide of iodine and Voigtländer's lens, the exposure was reduced to seconds.

The daguerreotype art had therewith reached its zenith. However delicate the pictures so produced appeared, it was found, after the first enthusiasm had gone and had given place to a cold spirit of criticism, that much still remained to be desired.

First, the glare of the pictures made it difficult to look at them. Then there were several marked deviations from nature: yellow objects often produced little or no effect, and appeared black; on the other hand, blue objects, which appear dark to the eye, frequently, though not always, came out white.

This is still the case in photography, only now the attempt is made to diminish this defect by subsequent treatment of the plate (by re-touching the negative).

But still a well-grounded æsthetic objection was brought against these pictures.

It was indisputable that the daguerreotype greatly

surpassed painting in the wonderful clearness of detail, and the fabulous truthfulness with which it reproduced the outlines of objects. The daguerreotype plate gives more than the artist, but for that very reason it gives too much. It reproduces the subordinate objects as faithfully as the principal object in the picture.

Let us take the simplest case—a portrait. A painter, when he paints a portrait, does not by any means paint all that he sees in nature. The original wears, perhaps, a shabby coat, which shows a good many creases, perhaps a spot of grease, or a patch; but this does not disturb the painter in the least, for he leaves out these accidental details. In the same spirit, if the original is seated before an old whitewashed wall, the artist by no means put such a wall into his picture, for he can leave out all that is displeasing, or add, on the contrary, what he wishes.

It is different in photography. In taking portraits, all those minor accessories which disturb the picture are reproduced as faithfully as the principal object in it—the individual himself. Another point must be added to this. The different elements admitted by the painter into his picture are by no means made equally prominent. The head is the chief consideration in every portrait. The painter accordingly gives his best skill and care to the painting of the head in the most careful manner. At the very least he puts the head in the strongest light, and leaves the rest of the picture in a half-shade. But in a photograph it is by no means the head which is generally the most prominent—frequently it is a chair, or part of a background; and this detracts considerably from the effect of the picture. Finally, the expression of

the face is an important point in a picture; and this varies with the mood of the sitter. A photograph gives the expression which the original had at the moment the picture was taken. Now, the expression varies, and is affected by a slight annoyance, a vexatious circumstance, *ennui*, or even by the motionless attitude which has to be observed during the process; and hence the portrait often looks strange and unnatural.

It is quite otherwise with painting. The painter has longer sittings of the original than the photographer; he soon learns to distinguish the accidental frame of mind from the characteristic expression of the face, and thus he is in a position to produce a portrait much more closely corresponding with the character of the original than that of the photographer can ever be. This naturally applies only to paintings of masters of the first order. In the portraits of the dauber, none of these advantages are found; and this large class disappeared, like bats before the light, when the art of sun-painting suddenly rose upon the world. Many of these themselves adopted the new art and attained to greater results than they could have done as painters.

The artist of merit has no cause to fear photography. On the contrary, it proves advantageous to him by the fabulous fidelity of its drawing—through it he learns to reproduce the outline of things correctly—nor can it be disputed that, since the invention of photography, a decidedly closer study of nature and a greater truthfulness are visible in the works of our ablest painters.

We shall see further on, how even photography appropriated the æsthetic principles according to which painters proceed in preparing their portraits, and how

thereby a certain artistic stamp was given to these productions, which raised them far above those of the early period. But this result was only possible when the technical part of photography had been brought to perfection, and a material better adapted to artistic work than an unyielding silver plate had been introduced.

CHAPTER III.

PAPER PHOTOGRAPHY AND THE *LICHTPAUS*, OR NEW TALBOT PROCESS.

Talbot's Paper Photographs — *Lichtpaus* Paper — Leaf-prints—*Lichtpaus* Process and its Application.

In the same year that Daguerre published his process for the production of images on silver plates, Fox Talbot gave to the world a process for preparing drawings on paper by the help of light. Talbot was an English gentleman of fortune, who, like many Englishmen of leisure and means, employed his time in scientific observations. He plunged paper into a solution of common salt, dried it, and then put it into a solution of silver. In this way he obtained a paper which was much more sensitive to light than that employed by Wedgwood. He employed this paper in copying the leaves of plants. Talbot himself says, "Nothing gives more beautiful copies of leaves, flowers, etc., than this paper, especially under the summer sun; the light works through the leaves, and copies even the minutest veins."

This is no exaggeration. In the possession of the author there are prints of this kind, made by Talbot

himself, which show excellently the structure of the leaves.

The pictures copied in this way in the sunlight are naturally not durable, because the paper still contains salts of silver, and is therefore sensitive to light. But Talbot offered the means of fixing the pictures—he plunged them in a hot solution of common salt; in this

Fig. 5.

way the greater part of the silver salts was removed, and the pictures did not blacken to any considerable extent in the light.

The celebrated Sir John Herschel carried out this fixing process even more successfully by plunging the pictures into a solution of hypo-sulphite of soda. This

salt, which dissolves all the salts of silver, was at that time very expensive, costing six shillings per pound. The production of this salt soon kept pace with the increasing demands of photography, and now it is offered for sale by the ton, and at as low a rate as sixpence the pound.

By this means the production of a durable sun-picture on paper, which Wedgwood had in vain attempted, was rendered possible. This method gave, indeed, only pictures of flat objects which could be easily pressed on paper; for instance, leaves of plants, patterns of stuffs, etc. The process has lately been resumed, after it had almost been forgotten. Charming ornaments of leaves, various plants, and flowers have been produced; and these copies are proportionally more beautiful than the earlier ones, because a much finer and more even-surfaced paper than that of Mr. Talbot has recently passed into trade, under the name of *lichtpaus papier.** We give on the accompanying page a faithful imitation of one of these leaf-prints which have become popular in America.

Since the sale of sensitive paper has rendered the production of these leaf-prints very easy, we give here the mode of producing them for our fair readers, who will be able in this manner, like their sisters in America, to make ornamental pictures for the adornment of lamp shades, portfolios, and similar things.

The leaves—such as ferns and the like—are suitably chosen, pressed between blotting-paper and dried, then gummed on one side and grouped gracefully by the fair artist upon a glass plate, in a small frame (Fig. 6). As

* This paper is produced by Mr. Romain Talbot, 11, Karlstrasse, Berlin.

soon as the whole is dry, the print can be at once commenced.*

A small piece of sensitized paper is placed on the leaves, the two wooden lids, *h h*, are laid upon it, and fastened down by means of two little cross-bar pieces of



Fig. 6.

wood, *x x*, and then the whole is exposed to the light, the glass side uppermost. The sheet of paper very soon assumes a brown colour, where it is not covered by the leaves, and ultimately it receives a decided bronze tint. The light also penetrates partially through the leaves,



Fig. 7.

and colours the paper lying under them brown. It is easy to discern how far the paper under the leaves is

* These wooden frames, called printing frames, dishes, and fixing salt, are also manufactured by Mr. Talbot, at Berlin. There is now even a small plaything of this kind on sale, known by the name of the "sun-copying machine."

coloured if one of the cross-bars, *x*, and the half cover, *h*, are removed, and the paper is lifted up.

As soon as the impression is dark enough—it is quite a matter of taste whether the shade be dark or light—the paper is taken out and placed in a dark closet. Several pictures can, in like manner, be taken one after the other, and all of them can be afterwards fixed, that is, made permanent in the light, in one operation.

To this end the picture is placed in a flat dish (Fig. 8) containing water, for about five minutes, and then in a second dish in which is a solution of one part of hypo-sulphite of soda in five parts of water. The moment the print is dipped in this it becomes of a yellowish brown.



Fig. 8.

After remaining ten minutes in the fixing solution—several can be immersed in succession—it is taken out and placed in fresh water (most conveniently in a saucer). This operation of placing in fresh water is repeated from four to six times, the picture being left in the water three minutes each time.

Afterwards the pictures are placed on blotting-paper and suffered to dry; they can then be pasted upon card-board, thick paper, linen, glass, or wood.

To many persons this process will appear only an agreeable pastime, but latterly it has gained an increasing importance as an aid in copying drawings, maps, plans, copper-plate impressions, and so forth.

This work of copying, which used to cost the artisan and artist many hours of time and labour, and yet was after all inaccurate, can be accomplished with the least possible trouble by the help of the process described above.

Let the reader imagine a drawing placed on a piece of sensitized paper, and, after being firmly pressed by a glass plate, exposed to the light. The light penetrates through all the white spots of the drawing, and colours brown those parts of the paper lying under them; whilst the black lines of the drawing keep back the light, and thus the underlying paper remains white in these places. Therefore, if sufficient time is given for the operation of the light, a white copy on a dark brown ground is obtained in this manner, which is fixed and washed exactly like the leaf-prints described above. This copy is reversed with reference to the original, like an object and its reflection in a mirror; in other respects it is a faithful representation, stroke for stroke.

We give in Plate II. the copy of a woodcut struck off according to this method. This copy is but small, but the largest as well as the smallest drawing can be copied equally well; and copies of this kind, from drawings more than four feet square, are made in technical offices, in mines, and in machine manufactories.

Large printing frames are used for this purpose, resembling in their construction the small frames above described; and large wooden dishes, covered with a coating of asphalt, are employed for fixing and washing the prints. This operation is called in practice the *lichtpaus* process. The black copy is called a negative picture, but a second white copy can be prepared from this by placing

the negative upon sensitized paper; then the light shines through all the white lines, and colours the paper lying under them of a dark hue, whilst it remains white under the dark places of the negative. In this manner a picture called a positive is produced, which perfectly resembles the original. The washing and fixing are carried out

Fig. 9.

just as with the negative. Fig. 9 represents a positive of this kind taken from the negative, Fig. 5.

Thus the geographer is in a position to prepare quickly faithful copies of his sketches and maps, the engineer is able to copy the drawings of machines which are to serve for the workmen, and the student can copy illustrations of natural history which are to assist him in his studies.

In the process of copying, the sensitive paper must closely touch the original picture; it must therefore be placed on the face of the picture.

This process has already done good service in military operations, where it was important to make quickly a copy of some map of which there was only one impression. If an attempt had been made to draw a copy of the map, it would have required several days to carry out, nor would the copy have been as correct as the print.

It is remarkable that this process, so important for industry, has only quite recently been known in its full value, although the experiments of Talbot have been before the world for more than thirty years. The explanation of this fact is, no doubt, to be found in the circumstance that the paper prints were then far less distinct than now, being often rendered worthless by spots and stains. Another reason is that the preparation of the paper requires especial care, and therefore frequently fails in the hands of the inexperienced; that is, of those who are not professional photographers. Further, the papers prepared according to the old method soon spoiled, and had on that account to be used immediately after their preparation.

These disadvantages have been removed by the invention of Romain Talbot's *lichtpaus* paper, which is sold ready prepared, and can be kept for months; and by this means the process can be easily made available by every professional man and amateur.

CHAPTER IV.

THE DEVELOPMENT OF MODERN PHOTOGRAPHY.

Talbot's Paper Negatives—Photography as an Art for Multiplying Copies—Services of Nièpce de St. Victor—White of Egg Negatives—Gun-cotton in Photography—Collodion—Archer's Negative Process—White of Egg Paper—Carte de Visite—Photographic Album.

THE reader has learnt in the previous chapter what a negative is, and how by its means photographic copies of flat objects can be obtained.

Talbot, the inventor of this paper process, carried out further researches, in the endeavour to represent on paper, by the help of the camera obscura, objects which cannot be pressed upon sensitized paper; for example, a person or a landscape.

He attained this object two years after Daguerre's discovery, by means of paper prepared with iodide of silver.

He dipped paper in a solution of nitrate of silver, and then in a solution of iodide of potassium. He thus obtained a slightly sensitive paper, but one that could always be rendered very sensitive, by plunging it into a solution of gallate of silver.*

* The nature of this peculiar process is explained further on.

When this paper was exposed to the light in the camera obscura, a picture was not at once formed—this was only clearly developed after lying some time in the dark, or by subsequent treatment with gallate of silver —but it came out as a negative, and not as a positive. Thus, for example, in taking a portrait, the shirt appeared black, also the face; while the black coat, on the contrary, came out white.

The picture was fixed by plunging it in a solution of hypo-sulphite of soda.

The negative thus obtained is a picture on a plane surface of a solid object, and Talbot prepared positive pictures from negatives of this kind.

He placed the negative upon a piece of sensitive paper prepared with chloride of silver, as described in the last chapter, and allowed the light to act upon it. This shone through the white places of the negative, and imparted a dark colour to those parts of the sensitive paper lying under them, while the dark places of the negative protected the paper lying under them from the effects of the light. Thus he obtained a positive picture from a negative. He could repeat the process as often as he pleased, and therefore was in a position to prepare, by the aid of light, many positives from a single negative. Photography was thus classed among the arts that multiply copies, and this circumstance exercised an important result on its future development.

Daguerre's method only gave a single picture at a time; if more were required, the person had to sit several times. In Talbot's method a single sitting sufficed to produce hundreds of pictures.

It must be admitted that the earlier pictures of the

Talbot process were not remarkably engaging. Every roughness of the paper and each small speck of dirt were imprinted on the positive, which could not be compared in point of delicacy with the fine daguerreotypes ; but the method was soon improved.

Nièpce de St. Victor, nephew of Nicophore Nièpce the friend of Daguerre, conceived the happy idea of substituting glass for paper in the preparation of the negative. He coated glass plates with a solution of albumen in which iodide of potassium was dissolved.

A solution of this kind can be easily prepared by beating up white of egg to the consistency of snow, and allowing it to settle. The glass plates, after being coated with this solution, were dried, and then dipped into a solution of nitrate of silver. Iodide of silver was formed in this manner—the coating turned yellow, and became very sensitive to light.

Nièpce put these glass plates in the place of the image in the camera obscura, and suffered the light to act upon it.

No change was at first visible, but became clearly perceptible when the picture was immersed in a solution of gallic acid. Thus Nièpce obtained a negative on glass without the blemishes which appeared on the paper negatives.

He prepared prints from this negative by exactly the same process that had been employed by Fox Talbot, and he obtained from the fine negative a correspondingly fine positive, which was much better calculated to bear a comparison with the productions of Daguerre.

Nièpce invented his method in 1847. It excited much attention, but had its drawbacks : the preparation of the

albumen and the treatment with salts of silver and gallic acid was a dirty process. Therefore the method appeared to those who had been accustomed to the daguerreotype, dirty and unpleasant, and many were deterred from trying it.

On the other hand, the advantages of the new process in multiplying prints were so evident that it could not be overlooked; therefore, even those who had an objection to soiling their fingers nevertheless zealously devoted themselves to the work.

The readiness with which albumen decomposes was, however, a great disadvantage in the new process. They sought to avoid this by adopting a more durable substance.

This was afforded by the discovery of gun-cotton made by Schönbein and Böttcher in 1847. Schönbein found that ordinary cotton-wool dipped in a mixture of nitric and sulphuric acids assumes explosive properties similar to those of gunpowder. It was conceived that this substance would be an important substitute for gunpowder, but it was soon found that its explosive property was very unequal, being sometimes too strong and at other times too weak. On the other hand, another very useful property of this substance was observed—its solubility in a mixture of alcohol and ether. This solution leaves behind it a transparent membrane forming an excellent sticking-plaster for wounds. Thus the same substance that was destined to be a substitute for gunpowder, as a destructive agent for producing wounds, became actually a remedy for the latter. This solution of gun-cotton was called collodion.

The thought occurred to several photographic ex-

perimenters to try this substance instead of the white of egg, as a coating for glass plates; but the attempts did not at first lead to any satisfactory results. At length Archer published in England a full description of a collodion negative process surpassing in the beauty of its results, in simplicity and certainty, Nièpce's white of egg process.

Archer coated glass plates with collodion, in which an iodide had been dissolved; he immersed this in a solution of nitrate of silver, and thus obtained a membrane of collodion impregnated with sensitive iodide of silver, which he then exposed in the camera.

The invisible change produced by the light became visible on pouring gallic acid, or the still more powerful chemical agent, pyrogallic acid, over the plate; or, instead of this, a solution of proto-sulphate of iron.

Very delicate, clear negatives were obtained by this process, which yielded much more beautiful paper prints than the original paper negatives of Talbot. A very essential improvement was subsequently made in the preparation of photographic paper by coating it with white of egg, according to the process of Nièpce de St. Victor. This gave it a brilliant surface, and a warmer and more beautiful tone to the prints upon it, giving the pictures a brighter appearance than those produced upon the ordinary paper.

Thus Talbot's process, which at first seemed hardly worth notice compared with that of Daguerre, was gradually so perfected by successive improvements, that it ultimately took precedence of Daguerre's. After 1853, paper pictures from collodion negatives came more and more into vogue, whilst the demand for daguerreotypes

fell off, and the production of the latter soon ceased altogether, except in some few places in America.

The collodion process is now the one universally employed. It acquired an immense impetus through the introduction of cartes de visite. These small portraits, which are intended to be given away, and therefore had to be produced in large numbers, were invented in 1858 by Disderi, the court photographer of the Emperor Napoleon, and obtained so great a success that they were immediately introduced into all circles, and soon became a necessity for everybody. The moderate price at which these portraits were sold made them attractive to the smallest purses, and the general public crowded to the ateliers, the number of which increased daily.

The old-fashioned album, the favourite souvenir of young people, was now superseded by the carte de visite, and the portraits of friends were substituted for their written words. A photographic album is now found in every home; and in Berlin alone there are at present more than ten photographic album manufactories, from whence they are exported to all parts of the world.

CHAPTER V.

THE NEGATIVE PROCESS.

The Dark Room—Chemically Inactive Light—Cleaning the Plate—Application of Collodion—Sensitizing—The Camera—The Arrangement of the Object—The Exposure to Light—The Development—Intensifying—Fixing—Varnishing.

In the previous chapters we have dwelt on the development of photography, and we are now able to feel at home in the studio of a photographer. His whole business depends on the chemical action of light,—and yet the scene of his principal activity is not the illuminated studio, but a dungeon, in which the deepest night prevails, and which is called the dark room. The sensitized plate, which has to be exposed to the light, and to respond to its most delicate operations, must be prepared in darkness, in the dark room. This space, surrounded by bottles and pots, and crammed with instruments, is the narrow world of the photographer, out of which he issues only for a few minutes into the light of his studio, to return directly with his exposed plate, and to subject this to various chemical operations.

Many persons believe that the opening and shutting

of the cap—the cover of the lens of the apparatus, falsely called the machine—is the chief work of the photographer. Nay, it is related of a certain queen, that she thinks she is photographing, when she has all the necessary apparatus brought and prepared, and then, when all is ready for the result, opens and shuts the cover of the lens—a work that a child of five could do equally well. But this operation is only one in a great chain of twenty-eight operations, which each plate must undergo to produce even a negative, while at least eight further operations are required to prepare a positive from this negative.

Let us look a little closer at these operations. The appearance of a dark room is by no means inviting. Even where the greatest order prevails, drops of silver solution scattered about produce black spots here and there. To this must be added a permanent odour of ether from the evaporation of the collodion, and an unavoidable dampness from the necessary washing of the plates,—and all this is seen in the hazy light of a gas or petroleum lamp provided with a yellow shade, or of a small window fitted with a glass of a similar colour.

The remark must here be made at the outset, that the dark room of the photographer is not really completely dark. The daylight only must be excluded from certain operations; but the yellow light of the lamp is innocuous.

From this we learn the important distinction between light chemically active, and light chemically inactive. The light of the sun and of the blue heavens, the electric and magnesium light, are chemically very active, the light from gas or petroleum very slightly so;

whilst the yellow light of a spirit lamp, whose wick has been rubbed with common salt, is entirely inactive. The active light of day, furthermore, can be rendered inoperative if allowed to pass through a yellow or, better still, a reddish-yellow glass. The light, therefore, that falls through the yellow window of a dark room is chemically inactive, or in so slight a degree active that it no longer causes any disturbing effect. It is remarkable that yellow light, which affects our eyes so powerfully, should have no action on the photographic plate. Up to the present time no satisfactory explanation of this fact has been given. It has its disadvantages in practical photography; for example, a yellow garment, a yellow complexion, yellow spots—such as freckles—appear almost black in the picture. Nevertheless, these disadvantages can be obviated by retouching the negative as described at a future page. On the other hand, this property of yellow light has also its advantages for the photographer. It permits him to prepare the sensitive plates in a light which does not injure them, and yet enables him to control the work. If the plates were sensitive to all kinds of light, it would be necessary to prepare them in absolute darkness, which would be very inconvenient.

The first operation required in preparing a sensitive plate—an operation which requires great care—is the cleaning of the glass. The plates, after being cut by the diamond, are placed some hours in nitric acid, which destroys all impurities adhering to the surface. The acid is removed by washing, and the plate is then dried with a clean cloth. To the uninitiated it would then appear perfectly clean, but the photographer subjects it to further polishing, by rubbing with a few drops

of spirits of wine; or, still better, of ammonia. The slightest touch with the finger or rub of the sleeve, the smallest drop of saliva which might chance to escape from the mouth in coughing, would spoil the polished surface; nay, even the atmospheric air produces with time the same effect. If a cleaned plate is left only twenty-four hours in the air, it gradually condenses vapours on its surface, and another cleansing is rendered necessary.

The cleaned glass is then coated with collodion. The collodion itself is, as we know, a solution of gun-cotton in a mixture of alcohol and ether, in which certain iodides and bromides—for instance, iodide of potassium and bromide of cadmium—have been dissolved. This solution must also be prepared with the greatest attention to cleanliness; thus the purity of the materials employed is of the greatest importance. The solution must be allowed to stand a long time, and carefully poured off from any sediment. The coating of a plate with collodion requires a certain manual dexterity, and only succeeds with those who have witnessed the process and after some practice.

It is usual to hold the plate horizontally by one corner and to pour over the centre of it a pool of the thick fluid, and then to allow this to flow to all of the four corners by a gentle inclination of the plate, ultimately pouring off the superfluous fluid at one of the corners.

A considerable part of the fluid originally poured upon it remains, and adheres to the plate.

Whilst pouring off the excess of collodion streaks are liable to be formed, which would spoil the picture; to avoid this the plate, whilst being drained, must be constantly kept in motion until the last drop has run off.

The fluid stiffens into a soft, moist, spongy film. At this moment the plate must at once be immersed in the solution of nitrate of silver (called the silver bath).

And now a peculiar action of the fluids takes place, for the ether in the collodion film repels like fat the aqueous solution of silver, and a steady movement of the plate in the bath is necessary in order to make the solution adhere to the film.

This mechanical operation is accompanied simultaneously by a chemical change. The iodides and bromides in the film undergo a double decomposition with the nitrate of silver of the bath, with formation of iodide and bromide of silver and nitrates of the metals previously combined with the iodine and bromine. The iodide and bromide of silver colour the film yellow; and now the plate is ready to receive the picture to be painted by the light.

All these operations must precede the taking the photograph, and they are begun, in fact, at the moment when the person enters the studio, and with proper management the plate is prepared before the arrangement of the object is concluded.

This arrangement is a labour of itself; and it is of a genuinely artistic nature. The points to which the photographer has to attend include a natural and yet graceful attitude of the original; the choice of the side which presents the most advantageous aspect; the picturesque arrangement of the dress; the removal of inappropriate objects which ought not to appear in the picture; the addition of those that are suitable, such as a table, a cabinet, or a background; lastly, an appropriate direction of the light. Only a few minutes can be devoted

to these arrangements, for people dislike long delays or experiments; and the plate itself only remains sensitive a short time, for it is wet with the adhering solution of silver, which soon dries up, and the plate is then useless.

When the exposure has been accomplished—during which the person being photographed must remain perfectly motionless—the sensitive plate is brought back into the dark chamber.

For the purpose of transporting the plate, which must of course be guarded very carefully from the daylight, the photographer employs a flat case or frame (Fig. 10), called the dark slide. At the back of this slide is a door D opening upon hinges, and in front there is a sliding shutter H. In the corners are fixed four silver wires *d, d, d, d,* upon which the plate rests with its prepared side downwards, being held steadily in its place by a spring *f f,* fastened to the door D. The plate is carried in the dark slide to the camera and substituted for the movable ground-glass screen upon which the image of the object has been previously focused. After the exposure the dark slide is removed from the camera and taken back to the dark room.

And now follows one of the most important operations, the development of the picture. Upon the plate there is as yet no trace of a picture visible. The action of the light produces a peculiar change of the iodide of silver which forms the important constituent of the film; this iodide acquires through the light the property of attracting silver, if this is precipitated on the film; this precipitate is produced by the following operation. If a silver solution is mixed with a very dilute solution of proto-sulphate of iron, there results by slow degrees a

precipitate of metallic silver—not, however, as a shining mass, but as a grey powder. Now, a small quantity of the nitrate of silver solution from the bath always adheres to the film. If therefore a solution of proto-sulphate of iron is poured upon it, a silver precipitate is formed, and the picture suddenly makes its appearance, owing to the silver adhering to those parts affected by the light.

The features of a portrait that are first visible are the lightest—the shirt, then the face, and lastly the black



Fig. 10.

coat. The negative thus obtained, however, is by no means completed by this operation.

The picture is usually too transparent to answer for the production of paper prints; for the preparation of such a print depends upon the light shining through the transparent places of the negative, and colouring dark the paper beneath, while it fails to penetrate the parts which have to remain white. The opaque and transparent parts of the negative must be in sufficient contrast with each other to produce this effect.

The negative must, therefore, be more strongly defined; and this is produced by repeating the developing process. A mixture of solutions of green vitriol and of nitrate of silver is poured upon the picture, a silver precipitate is again formed on it, which adheres only to the dark parts of the negative, giving them a greater density. If the plate is not perfectly clean, silver is precipitated, in the processes of developing and intensifying, upon the dirt stains and produces spots. After the further development of the picture, or the so-called intensifying process, has been completed, it is only necessary to remove the iodide of silver, which diminishes the transparency of the clear parts of the plate. For this purpose a solution of hypo-sulphite of soda is poured on the plate. This salt has the property of dissolving salts of silver, which are insoluble in water, so that the iodide of silver vanishes under the influence of this solution. This is the fixing process. Lastly, the plate is washed and dried.

If it be borne in mind that all these different operations are performed on a film liable to be injured by the slightest touch, it is not to be wondered at that the inexperienced beginner destroys so many coatings before he can prepare a perfect one.

Even when dried, the picture is very liable to injury; and therefore photographers, in order to protect it, cover it with a varnish, that is, with a solution of a resin, such as shellac or sandarach, in spirits of wine. The fragile glass negative is therewith brought to completion.

This sketch of the operations which a photographer is obliged to carry out in order to produce a negative, is sufficient to show that photography is a more difficult art than some persons imagine, and that it requires something more than the opening and shutting of a lid.

The chief requisite for the success of these operations is routine; accuracy is only attained in practising each part of the process. Faults that are made in any single operation are, as a general rule, irremediable; and therefore it is absolutely essential to avoid them.

CHAPTER VI.

THE POSITIVE PROCESS.

Character of the Negative—Departure from Nature—Retouching the Negative—Preparation of Sensitive Paper—Printing—Toning with Chloride of Gold—Fixing—Cause of Fading—Quantity of Silver in the Picture—Vignetting.

In the preceding chapter we have become acquainted with the preparation of a negative. However interesting such a negative might be, nevertheless, it would not satisfy the purchaser of a portrait, since it shows everything reversed. The white face is black, and the black coat, white. No one would hang up on his wall a picture representing him as a Moor. It is therefore necessary to obtain a positive impression from this negative. We have already learnt how this is effected in the chapter on the *lichtpaus* process. It is the old Talbot method that is here employed. But we must still mention certain operations which have become very important in modern photography.

The camera, the negative process, and the photographer who knows how to manipulate intelligently, no doubt produce a negative which, laid over sensitive paper and exposed to the light, yields a positive; but although

this positive is very faithful in the delineation of figures —that is, of their outline—it yet presents marked departures from nature. Thus the relations of light and shade are by no means correctly given. In general the light parts appear too light, the dark parts too dark—as, for example, the folds in a dress, the skin, and, moreover, the shadows under the eyes and chin. When photographers knew nothing of art, these defects were taken as a matter of course. People protested that photography was correct because nature, through photography, was herself the artist. But in this conclusion the co-operation of the photographer was overlooked.

No doubt nature, that is, the object to be taken, makes the impression upon the plate, by the light radiating from it; but an impression of light is not a picture—it is indeed, of itself, invisible; nay, more, the strength of the impression of light is entirely at the discretion of the photographer, who can make it weak or intense by a shorter or longer exposure. There is no rule which determines the length of time a photograph has to be exposed to the light.

The fact is that nature, probably speaking, only determines the outline of the picture, while the relations of light and shade depend partly on nature, and partly on the will of the photographer.

The impression made by the light must be developed to be visible, and finally the developed picture must be intensified. By this means the photographer can at his option increase, and even exaggerate, the contrasts of light and shade.

If the negative is carefully compared with the original, we shall find that many dark parts have not appeared at

all, because the exposure was too short for them to produce an impression upon the plate; others have appeared, but too faintly. On the other hand, very light parts—for instance, the shirt-collar—are too apparent, and the needlework upon it is invisible because the time of exposure was too long. In the case of long exposures it is often remarked that bright parts differing little in colour are entirely confused and form a single white patch.

Moreover, the accessories which a painter would undoubtedly omit, such as warts, pockmarks, little hairs, are all as clearly defined as the principal features; and thus the negative is neither a correct nor an agreeable repetition of the reality, but produces in the positive a picture which shows considerable departure from nature, and is often inaccurate by giving too much prominence to accessories.

In the first period of photography these departures were overlooked. Every one was content to possess a portrait which at least showed the outlines correctly; and what was defective in the negative it was sought to remedy by retouching the positive. But this made the pictures dear; and as it began to be the custom to order pictures by the dozen, the endeavour was made to evade this labour, which had to be applied to each individual picture, by carrying it out in the negative.

A single retouched negative gave any number of corrected prints which did not require to be retouched, and thus retouching negatives became the first and most important operation in producing a faithful and agreeable picture. The essential characteristic of this operation consists in entirely covering many parts. For example, the freckles and warts which are white in the negative

Print from untouched Negative.

Print from retouched Negative.

EFFECT OF RETOUCHING NEGATIVES.

See pp. 49, 237.

are entirely removed by a pencil, or by spots of Indian ink. Other parts—for example, the ill-defined details of the hair—are brought out by pencil strokes. Many hard shadows, such as the wrinkles in the face, are softened off by slight touches of Indian ink. It must be constantly borne in mind during this operation that all the dark lines which the painter draws on the negative will appear light in the positive.

It is requisite, therefore, for successful retouching, to know how to use the pencil and brush so as to produce the desired effect in the positive. The best draughtsman or painter is therefore far from being qualified for retouching a negative.

It is to be remarked that the negative retouch may, under certain circumstances, go too far. By covering every wrinkle an old face can be made young; an ugly original can be beautified by cutting away a hump on the back, or other abnormal growths; and these tricks are often put into requisition for the vanity of sitters, and are dearly paid for.

Plate VI. represents two portraits of the same person, one from a retouched negative, the other from a negative that had not been retouched. The spots on the skin and the dark shadows, on the picture which is not retouched, are clearly to be seen, while in the retouched one they are not visible.

In many cases retouching is employed simply to satisfy human vanity, but this is by no means always the case.

As already explained, photography does not always represent the natural colours correctly. Yellow often becomes black, and blue, white. For this reason photo-

graphs of paintings frequently fail to give the various tones of the original. This fault may be in some degree corrected by retouching the negative, and it is owing to this alone that photographs of oil paintings have attained their present perfection. We will treat of this subject in a future chapter. Let us consider the preparation of a positive picture.

The first operation is the preparation of the sensitive paper. A piece of paper coated with white of egg and moistened with a solution of common salt is laid in a dish on a solution of nitrate of silver, and allowed to remain for about a minute. The solution is absorbed by the floating paper, and chloride of silver is formed by double decomposition of the nitrate of silver with the common salt.



Fig. 11.

The wet paper is but slightly sensitive; it becomes fully sensitive only after being dried. The dry paper, saturated with chloride and nitrate of silver, is then pressed upon the negative in the printing frame (Fig. 11), which is similar to the one described. Then the whole is exposed to the light. The same process ensues which we have described in the chapter on *lichtpaus* paper; the light shines through the clear places of the negative and colours the paper lying under them dark, the paper under the dark places of the negative remains white, while it assumes a slight colour under the half-tones. In this manner a faithful positive copy of the

negative is produced, presenting a beautiful violet-brown tint. We know from the description of the *lichtpaus* process, that this print would not remain unaltered in the light for long, because the paper is still sensitive to light. The salts of silver contained in it must be removed if the impression is to be made lasting. To this end a solution of hypo-sulphite of soda is employed. If the prints be immersed in this solution, they become durable in the light; but, unfortunately, they suffer a peculiar change of colour, assuming an ugly brown tint. This tint is of no consequence in technical and scientific pictures, but detracts greatly from portraits and landscapes; and in order to give these a more agreeable tint, before fixing them, they are immersed in a dilute solution of chloride of gold. This process is called toning.

In this operation gold is precipitated on the picture, giving it a bluish shade; and now the tone of the picture is not essentially altered by hypo-sulphite of soda.

The picture thus produced consists partly of gold, partly of silver, in a finely divided state, and only requires to be thoroughly washed in order to become perfectly permanent. If this washing is omitted, small particles of hypo-sulphite remain behind, which decompose and form on the picture yellow sulphide of silver. This accounts for the circumstance that the pictures of an earlier period, when from ignorance of this fact this thorough washing was neglected, so often became faded and yellow.

It is surprising what a small amount of silver and gold is required to give an intense colour to a whole sheet of paper. For in a sheet of perfectly blackened paper 44 × 47 centimetres there is only 0·15 gramme

of silver, and in a photograph of the same size only 0·075 gramme; in a carte de visite but 0·002 gramme.

It must be here remarked that prints bleach a little in the fixing process; and hence the photographer usually lets the prints become darker than they are to remain. Thus even the printing process requires a practised eye, simple as it may appear.

In certain cases tricks of art are employed to produce agreeable effects, and among these is that of vignetting. Our readers are no doubt well acquainted with portraits on a white ground, the outlines of which gradually become confounded with the ground tint of the picture. This effect is produced in a very simple manner by placing what is called a mask over the copying frame. This mask is a piece of metal or cardboard (Fig. 12) in which an oval hole *b* is cut. This is placed on the printing frame *K K*, so that the part of the negative which is to be printed lies perpendicularly under it. This part is



Fig. 12.

then acted upon by the broad perpendicular bundles of light *S S*, and intensely coloured, while the marginal parts lying under the mask are affected only by the narrow slanting pencils *S' S'*, and therefore are coloured less intensely in proportion to their distance from the hole of the mask. Thus a gently vanishing margin is

produced, looking very artistic, and yet only the result of a very simple trick of art.

The picture produced in the manner described above only requires some preparation to be an elegant drawing-room ornament. It is cut in a regular shape, square or oval, and fastened with clean paste to white cardboard; after drying, any slight blemishes are removed with the paint brush, and finally its surface is rendered glossy by two polished steel rollers.

Certain sizes have been adopted by the public, such as the "carte de visite" and "cabinet" sizes. The former is rather larger than an ordinary visiting card. The latter is two and a-half times as large.

The carte de visite, introduced at Paris by Disderi in 1858, speedily secured admirers, and has spread over the whole earth. Even Chinese photographers have adopted the carte de visite form.

The carte de visite, and the cabinet size—which was first introduced in England, and is a great favourite in America—are not confined to portraits, but also employed for landscapes and photographs taken from oil paintings. Millions of these pictures are sold every year, and a properly arranged album for preserving them is found in almost every family.

Photography admits of such small pictures because of its fine details, but it is by no means confined to them. Surfaces on which life-size portraits may be taken can be employed. The production of the latter necessitates a peculiar process, called the enlarging process, which will be treated of at a future page.

CHAPTER VII.

LIGHT AS A CHEMICAL AGENT.

Theory of Photography—Nature of Light—Undulatory Theory—Action of Light on Realgar—Chemical Decomposition by Light—Colours and Tones—Their Vibrations—Refraction—Dispersion—The Spectrum—Lines of the Spectrum—Invisible Rays—Photographs of Moonlit Landscapes—Abnormal Photographic Effect of Colours—Photography of the Invisible.

"GREY is all theory, and green life's golden tree," says Goethe. This saying has often been misunderstood and misused, especially by those too lazy to think; but, faithful to its true meaning, we have first treated of a multitude of facts from life—that is, from the history and practice of photography,—and now we proceed to describe, by the help of science, how and why, not the golden but the silver tree of photography grows, blooms, and bears such splendid fruit.

Two sciences join hand to accomplish the wonders of photography. One is Optics, a division of Physics, and the other Chemistry. We have already shown that they alone are inadequate to fulfil the requirements of photography. Æsthetical claims have to be considered; and thus photography unites in itself the provinces of natural

science and of the fine arts which seem remote and incapable of union. We shall consider first the principles of optics—that is, light—as the force which occasions the chemical changes in photography. We shall see that its chemical operations have not only become the basis of our art, but that they have played, and still play, a much more important part in the development of our planet.

We are aware of the existence of sun, moon, and planets. We know their distance; nay more, we know their elements, though we are separated from them by millions of miles.

We are indebted for all this knowledge to light. What is light? A wave motion of ether. And what is ether? An infinitely delicate fluid, which fills all the space of the universe, and which, like all fluids, may be set in undulation. If we throw a stone into water, waves are produced—that is, circles or rings of hills and valleys, are formed, which appear to widen out from a centre, and as they extend become gradually less, until they finally disappear. If several stones are thrown at the same time into the water, each of them forms its own system of waves.

Fig. 13.

These intersect each other in the most intricate manner; and, although an apparent confusion of rings takes place, it is wonderful that none of them disturbs the other, and that each circle widens out regularly from its own centre, where the stone fell into the water.

If a handful of sand, which contains many thousand grains, is thrown into water, and if the attention be

directed to the undulations of a single grain, it will be remarked that this one, without being affected by the countless other waves, widens out in a regular circle.

These undulations are one of the most remarkable movements in nature, taking place not only in water, but in the air, where they occasion the propagation of sound.

The peculiar feature of the undulatory movement consists in the fluid appearing to advance without really doing so. If, sitting on the side of a sheet of water, we see an undulation approach, it appears exactly as if the particles of water were approaching us from the origin of the movement.

It is easy to prove that this is an error by throwing sawdust or a piece of wood into the water. It dances up and down upon the ripples without moving from the spot. Indeed, the undulation is itself only an up and down motion of the particles of the water, and this movement is communicated further and further to the neighbouring particles.

Exactly in the same manner light spreads in undulations from a luminous body through the ether of space in all directions. The direction of the undulation we call a ray of light. We perceive it as soon as it reaches our eye, because the vibrating ether strikes our retina.

Now, we know that the undulations of sound are able to set other bodies in motion. If the *A* string of a violin is struck, the *A* string of a piano standing near sounds distinctly with it. Nay, even if the damper of a piano is raised and any note be sung, instantly the string of

the piano sounds which has the same tone. The same thing happens with a glass bell of the same tone. There are people even who can break a glass by a shrill tone of their voice. The glass is so shaken by the violent undulations communicated to it by the air, that it falls to pieces. Under such circumstances, it need not surprise us that the undulations of light agitate bodies so forcibly that they fall to pieces.

Realgar offers the most remarkable example of this kind. This is a beautiful mineral of a ruby red colour, in the form of splendid crystals composed of sulphur and arsenic. If a crystal of this kind be exposed for months to the light, it falls into powder; and in this way many very fine pieces of this beautiful mineral have been lost in the mineralogical museum of Berlin.

This is only a mechanical, and not a chemical, operation of light; but it gives an insight into its chemical action. Heat occasions chemical decomposition by expanding bodies, and thereby removing their atoms so far apart that the chemical power which unites them loses effect, and the component parts separate. Thus oxide of mercury is by heat resolved into its constituent parts, mercury and oxygen.

Decomposition is effected by light when the atoms of a body are agitated by its undulations, that is to say, are made to vibrate; and if these vibrations are unequal, a separation of the parts takes place, and the body falls to pieces.

Light waves are not a fiction. Not only has their existence been ascertained, but their size has been determined. The latter is extremely minute, but nevertheless is susceptible of measurement.

The waves of sound and the waves of light have therefore a certain analogy; and as there are different notes in music, so are there different colours in light. The number of notes is great. The simplest piano now has nine octaves, and there are other tones below and above these. But the number of colours is small; only seven of them can be distinguished—red, orange, yellow, green, blue, dark blue, and violet,—the well-known colours of the rainbow. The painter, indeed, contents himself with three ground tints—yellow, blue, and red. All the others are the result of their mixture; and the large scale of colour of the painter consists not of simple tones of colour, but of what may be called chords of colour.

The deep tones of music are caused by few undulations, the higher tones by more. For example, an $\bar{a}$ string makes 420 vibrations in a second, the a an octave lower makes 210, the great A 105.

In light, red is the colour which gives the fewest vibrations; it is the lowest tone in colours, and violet is the highest, giving vibrations nearly twice as rapid as red. With regard to tones, we know that they all spread with equal rapidity in the air; if this were not the case, a piece of music would be heard in the distance as a most disagreeable discord.

It is the same in the kingdom of light—the colours, without exception, are propagated through the ether with equal rapidity, the red as fast as the violet. But, whilst sound passes over only 1100 feet in the second, light traverses 190,000 miles in the same time, and the deepest colour-tone—red—makes in a second 420 billion of vibrations; that is to say, a million times

a million as many as the tone which is marked in music with a bar over the ā,* that is,



The small number of the colour-tones compared with the large number of musical tones is very striking. But the fact is, that, besides the seven visible colours, there exist invisible tones, which are both deeper and higher than the visible colours.

These invisible colour-tones are partly disclosed by the thermometer, which reveals the lower tones, and partly by substances sensitive to light. For it is remarkable that the colour-tones, which are higher than the violet, though invisible, have a powerful chemical effect.

We name the invisible tones of colour above violet, ultra-violet, and those below red, ultra-red.

In the common white light all the tones of colour are found together, and in combination they produce the effect of whiteness; but if we wish to examine the tones of colour separately, we must part them, and this may be done by the help of a prism.

Any polished crown-glass prism causes flames seen through it to appear like a rainbow containing the primitive colours we have named above. This separation of the colours in the prism takes place by refraction.

If a ray of light passes from one transparent medium

* We may here remark that the tone ā is not everywhere the same. The ā of the Berlin Opera is the highest; it has 437 vibrations,—the Italian Opera at Paris only, on the contrary, 424 vibrations. We have adopted for the sake of simplicity a round number, 420.

to another, it is deflected from its rectilinear direction, and this deflection is named refraction.

For example, if the ray *a n* (Fig. 14) strikes a surface of water, it does not continue in its original direction *a n*, but in the direction *n b*. If through the point *n*, where the ray strikes the water, a perpendicular line *d f* be drawn, the rule is that when a ray passes from a thinner medium (for example, air) into a denser one, it approaches the perpendicular, for *n b* is evidently nearer to the *d f* than *n a*. On the other hand, when a ray passes from a denser to a thinner medium,—for instance, from glass into air,—then the ray *n b* departs from the perpendicular *n d*; that is, the angle which the ray makes with the perpendicular after refraction is greater than the angle which it makes with it before.



Fig. 14.

Now, it is a remarkable fact that light of different colours is refracted unequally.

If a bundle of rays of white sunlight is suffered to fall on a piece of glass, the violet rays are deflected more than the blue rays, the blue more than the green, yellow, and red; and the result of this is that the white bundle is decomposed into a rainbow-coloured fan, violet, indigo, blue, green, yellow, orange, and red.

This phenomenon is the cause of the rainbow. If a ray *a* falls on a drop of water (Fig. 15), it is refracted and at the same time divided into a coloured fan, which is reflected from the back of the drop, suffers again refraction and dispersion at *b*, and issues as a broad bundle of colour. In open daylight this cannot be clearly

seen, because our eyes are dazzled by the bright light. In order to observe the pure colours of the spectrum, it is best to produce it in a darkened room, in which the light is allowed to enter only through a small slit (*b* Fig. 16).

When a prism *S* is placed behind the slit, a pure spectrum appears upon the opposite wall. If the slit is sufficiently narrow, a series of dark lines may be observed within the spectrum, at right angles to it.



Fig. 15.

These lines were first seen by Wollaston, and studied more exactly by the celebrated optician Frauenhofer, and called after him Frauenhofer's lines.

The lines are always found in the same position, so that they can be considered as natural music lines, upon which the scale of colour is written; and as the music lines serve for the recognition of the musical notes, so do the lines of the spectrum indicate fixed points in the scale of colour.



Fig. 16.

If we were to speak of the green of the spectrum, this would be a very vague designation; whereas by mentioning a line of the spectrum in the green, the part of spectrum is at once characterized. For this purpose Frauenhofer

gave the most characteristic lines names, the letters of the alphabet; a certain line in the red he called *A*, another in the yellow *D*, one in the violet *H*, and *H'*. As the number of lines reaches several thousand, these letters do not suffice to indicate them all. (See Fig. 17.)

The lines thus named are found in sunlight; the light of other stars commonly shows other lines. The light from artificial sources does not show dark, but bright lines; a flame coloured yellow with common salt shows, for example, a very characteristic line in the yellow; a burning magnesium wire shows several blue and green lines.

The situation of these lines agrees exactly with that of certain dark lines in the spectrum. For example, the yellow line in a flame coloured with common salt exactly coincides with the line *D* in the spectrum. The green lines in a flame of magnesium coincide exactly with lines *E* and *b* in the spectrum.



Fig. 17.

This remarkable coincidence led to the surmise that the lines in the sun's solar spectrum might owe their existence to the same substances that produced the coinciding bright lines in flames. Kirchhoff converted this surmise into a certainty, and was thus able to determine from the lines in the solar spectrum the substances present in the sun, and thus to demonstrate the chemical composition of a star distant more than 20 millions of miles (spectrum analysis).

But the spectrum contains still other wonders, which cannot be discerned by the human eye, but by the photographic plate.

If a sensitive plate be exposed to the action of the spectrum, it is observed that the red and yellow rays have scarcely any action, whilst that of the green is but very weak. Light blue produces more effect, dark indigo and violet the most; and in the space where no rays can be perceived by our eyes, a distinct action is produced, and extends beyond the violet for a space almost as long as the whole visible spectrum.

From this fact the existence of the ultra-violet rays was ascertained. The retina of our eye and the photographic plate possess an entirely different sensitiveness. Our eye is affected most powerfully by yellow and green light. These colours appear to us the brightest, while the photographic plate is not at all affected by them; on the other hand, indigo and violet rays, which appear dark to our eye, and even rays which to our eyes are invisible, produce a powerful action on the plate.

It is natural, therefore, that photography should represent many objects in a false light. Further back we called attention to the fact that photography is much less sensitive than the human eye to feebly lighted objects. This is most clearly seen in the fact that the eye can easily perceive objects by moonlight, which is 200,000 times weaker than that of the sun; whereas the photographic plate is not able to produce any picture of a moonlit landscape. The photographic landscapes by moonlight sometimes offered for sale have been taken in the daylight and copied very darkly, so that they produce the effect of moonlight. These pictures are very popular at Venice.

This small sensitiveness of the photographic plate to feeble light explains the reason why shadows are generally too dark in photographs. To these defects must be added the false action of light,—blue generally appears light, yellow and red, black. Yellow freckles appear therefore in a picture as black spots, and a blue coat becomes perfectly white. Blue (and therefore dark) flowers on a yellow ground produce, in photography, light flowers on a dark ground. Red and also fair golden hair becomes black. Even a very slight yellow shade has an unfavourable effect. A photograph from a drawing is often blemished by little iron-mould specks in the paper invisible to the eye. These specks frequently appear as black points. There are faces with little yellow specks that do not strike the eye, but which come out very dark in photography. A few years ago a lady was photographed at Berlin, whose face had never presented specks in a photograph. To the surprise of the photographer, on taking her portrait specks appeared that were invisible in the original. A day later the lady sickened of the small-pox, and the specks at first invisible to the eye, became then quite apparent. Photography in this case had detected before the human eye the pock-marks, which were, doubtlessly, slightly yellow.

In the photographs of paintings, such abnormal action of colour becomes still more evident, and can only be removed by appropriate retouching.

It is proper to observe, however, that by no means all shades of blue become light in photography. For example, indigo forms an exception, appearing as dark as in nature; this is shown in the photographs of the uniforms of Prussian soldiers. The reason of this is, that

indigo contains a considerable amount of red. On the other hand, cobalt blue and ultramarine produce almost the effect of white. Again, vermilion becomes dark, also English red; whereas Turkey red, which contains blue, becomes very light. Chrome yellow becomes much darker than Naples yellow; Schweinfurt's green becomes lighter than cinnabar green. No one of our pigments is a perfectly pure spectrum colour, but consists always of a mixture of different colours, and therefore is essentially modified in photography.

If the effect of the colours of the spectrum on photographic plates is more narrowly examined, it is observed that the indigo produces the greatest action. Nevertheless, the differently sensitized photographic plates offer somewhat various results in this respect. Chloride of silver is most sensitive to violet, but non-sensitive to blue. Bromide of silver is sensitive even to green, and iodide of silver only to violet and indigo. Mixtures of iodide and bromide of silver are sensitive both to blue and green. The author succeeded, in the end of 1873, in making photographic plates sensitive even to those colours that were before considered to be inoperative, *i.e.*, yellow, orange, and red. He found that if certain coloured substances that absorb green light were added to bromide of silver, which is by itself but slightly sensitive to green, the sensitiveness of this bromide to green is considerably increased. In like manner, the addition of coloured substances absorbing yellow or red light makes bromide of silver sensitive to yellow and red light. After this discovery, we may hope that the difficulties attending the taking of coloured objects may be soon overcome.

Mention has often been made of the photography of the invisible. The cases already recorded of the photographs of invisible pock-marks belong to this. But the photography of invisible quinine writing is especially understood by the term, photography of the invisible. If a writing is made on paper with a concentrated solution of di-sulphate of quinine, the result is scarcely visible. If this is photographed, it appears black and plainly visible in the picture. The di-sulphate of quinine has the property of lowering the tone of violet, of ultra-violet and blue rays; that is, of converting them into rays of less refractive power and of less chemical effect; therefore the light reflected from quinine produces little or no photographic effect, and the written characters become black.

This property of the di-sulphate of quinine serves also to make ultra-violet rays visible. If a piece of paper which has been moistened with a solution of sulphate of quinine is held in the spectrum, the originally invisible ultra-violet part is seen to shine with a bluish green light.

Other substances produce this effect, such as glass coloured with uranium and fluor-spar from Devonshire, and therefore this property has received the name of fluorescence.

CHAPTER VIII.

CHEMICAL EFFECT OF DIFFERENT SOURCES OF LIGHT.

Artificial Light—Magnesium Light—Lime Light—Electric Light—Illumination of Subterranean Places by Reflected Sunlight—Chemical Intensity of the Light of the Sun and of the Blue Sky—Breathing of Plants under the Influence of Light—Effect of Light in the History of the Development of the Earth and in the Economy of Nature.

From the facts explained in the foregoing chapter, it follows that chemical effects are chiefly produced by the ultra-violet, violet, and blue rays. It is therefore evident that the chemical action of any light will be proportional to the amount of these rays it contains.

Lamplight (gas or petroleum) is very poor in such rays, and therefore acts but feebly on the photographic plate; photographers are thus enabled to prepare their sensitive plates in a subdued lamplight.

This is also frequently done in the day by allowing the light to pass through yellow glass.

The white Bengal light, the flames of the blue Bengal light, and those of burning sulphur, produce a much more powerful chemical effect. The latter possesses only a small illuminating power, because it contains few yellow

and red rays; but, on the other hand, it is rich in blue and violet. Photographs have been actually taken by help of these flames.

But the chemical action of the foregoing lights is greatly surpassed by the effect of the lime, the magnesium, and electric lights. The magnesium light is very simply produced by the burning of magnesium wire.



Fig. 18.

Magnesium is a metal which forms the chief component part of magnesia. Magnesia is nothing but magnesium rust; that is, a combination of magnesium with oxygen.

If magnesium wire is burned, it combines with the oxygen of the air, producing a brilliant light and forming the oxide of magnesium. This light is very convenient in its application. An ounce of magnesium

wire, sufficient to take fifteen to thirty photographs, can be easily carried in the pocket. The general use of the light is impeded by the price of the metal (sixpence per gramme) and by the smoke which it emits. The author has repeatedly employed it with success in taking the sculptures in the sepulchral monuments of Egypt. When burning the magnesium wire, Solomon's lamp is used (Fig. 18). This consists of a reel *K*, upon which the wire is coiled, a clockwork apparatus *G*, which conducts the wire from the reel between two rollers to the tube *R*, at the end (*f*) of which the wire is burned. The concave mirror *O* reflects the light in parallel rays.



Fig. 19.

By means of the handle *H*, the lamp with parallel rays can be turned in any direction, and the clockwork can be instantly stopped by the key *m*.

The magnesium light is surpassed in power by Drummond's lime light. This is produced by a gas or spirit flame, into which oxygen gas is blown. The oxygen gas is produced by the action of heat on chlorate of potassium, a salt rich in that element. On heating this salt, oxygen is given off as a gas, and is collected in an india-rubber bag *K*. (See Fig. 19.)

This bag is closed by means of a stopcock *h*, and when

used is placed between two boards *b b*, a weight being placed on the upper one. By the pressure of this weight the oxygen gas is forced through the cock *h*, and the india-rubber pipe *n*, into the lamp *D*. To this is attached a burner *H F*, terminating in a jet *I*. The coal gas which serves for combustion enters through the cock *L*, which is connected with a gas tube.

The combustion takes place at the jet *I*. Without oxygen the coal gas burns with a bright soot-producing flame; but as soon as the oxygen is turned on, the flame becomes smaller and blue in colour, and burns with an intense heat.

Fig. 20.

Its illuminating power is small, but as soon as the flame has sufficiently heated the lime cylinder *A B*, a dazzling white light is produced, which has a very intense effect in photography, and has been used with success by Monckhoven and Harnecker for enlarging photographs.

The same apparatus serves for the production of what are called dissolving views.

The electric light, produced by help of a galvanic battery, has a still more powerful effect than the lime light.

If a piece of gas carbon *k* (Fig. 20) and a piece of zinc are dipped together into an acid (dilute nitric or sulphuric acid), electricity is developed, which produces a spark on bringing together the two ends of the zinc and coal above the fluid; this spark is, however, very feeble. But if several vessels containing zinc cylinders and pieces of carbon are employed, the spark becomes very intense; and, as we are able to increase to any extent the number

of these elements, we are able to produce a cone of light of any degree of brilliancy, exceeding all other artificial light.

In arranging electric batteries of this kind, the zinc of one element is connected with the carbon of the second, and the zinc of this with the carbon of the third element. (See Fig. 22.)



Fig. 21.

If the two wires from Z and C are brought together, a spark of light is produced by the electric stream burning the wire.

The light is generally produced between cones of carbon placed in front of a concave mirror H (Fig. 23). SS' is a self-acting apparatus to regulate distance between the carbon points KK. The



Fig. 22.

upper point is connected with the wire K by the stand F, the lower one with the wire Z of the electric battery. Thirty-six cells similar to those of Fig. 21 suffice to produce the electric light.

The preparation of the battery makes the application

of the light inconvenient. In other respects this light surpasses all others in photographic effect.

Nadar has made with it many excellent pictures of the catacombs of Paris. It has also been used to take



Fig. 23.

portraits. But the employment of such a dazzling artificial light is attended with the drawback of occasioning harshly defined shadows, which disfigure the portrait.

This difficulty has been overcome by placing another electric light of less power on the shaded side; but it is difficult under this dazzling light, as in direct sunlight, to prevent contraction of the features.

It thus appears that all these artificial lights can only serve as auxiliaries for photographic purposes, for they are, moreover, very expensive. Accordingly, their use will be confined to places that cannot be lighted in any other way. The writer has used sunlight with great advantage in taking photographs of Egyptian sepulchres. He



Fig. 24.

brought the light through subterranean passages by means of reflection.

Let the reader imagine a mirror *a* set up in the open air, reflecting the sun's rays through the entrance *T* (Fig. 24), into the subterranean vault *G*. In this vault they are received by a second mirror *b*, which throws the rays on the surface of wall *W*, of which a photograph has to be taken. It is true that nothing but a spot of light is thus produced; but if, during the exposure of the photographic plate, this spot be moved over the part of wall *W*,

of which a photograph is to be taken, all parts of the object receive successively enough light to produce photographic effects. The movement of the spot of light over the wall is effected by moving the mirror *b*.

Braun of Dornach, by help of the same method, was able at a later date to reproduce the very dark frescoes of Raphael and Michael Angelo in the Sistine Chapel and in the galleries of the Vatican, with excellent results.

Sunlight remains the most important source of light for photographic purposes. The brightness of this light is, however, subject to great variations. Even the eye recognizes that the sun is much brighter at noon than in the morning and evening. According to the measurements of Bouguer, this difference is so considerable, that the sun at an elevation of 50° above the horizon is 1200 times brighter than at sunrise. The eye, moreover, perceives a decided difference of colour between the sun on the horizon and the sun at the zenith. The latter appears white, the former of a reddish hue; and, on examination with the spectroscope, it is found that in the setting sun the reddish rays predominate, while the blue and violet are in part wanting.

For this reason the chemical action of sunlight is very feeble in the morning and the evening; it increases as the sun rises above the horizon, and it attains its greatest intensity about noon.

The cause of the red hue of the morning and evening sun is found in the fact that the particles of the air partly reflect the blue rays—for which reason the air (that is, the sky) appears blue—whereas they transmit the yellow and red rays more easily.

If *E* (Fig. 25) is the earth surrounded by the atmo-

sphere A, S the sun at the moment of sunrise, S''' the sun at the moment of sunset for the place O, and S' the sun at noon, it is apparent that the sun's rays at sunrise and sunset have to travel much further through the atmosphere—namely, the distance between a and O—than when the sun is in the zenith S'. But in proportion as the stratum of atmosphere through which the sun must pass to arrive at the spectator is thicker, the weaker becomes the light. It follows from this that on high mountains the chemical action of the rays of light must



Fig. 25.

be more intense, and this has been proved by experiments on the Alps to be the case.

But not only are chemical effects produced by direct sunlight; the light of the blue sky, which is nothing but reflected sunlight, is likewise chemically active, and powerfully so, through its blue colour.

It has been already stated that the blue colour of the sky proceeds from the fact that the particles of the air reflect blue light. The quantity of this reflected light varies with the hour of the day, being strongest when the sun is highest (that is, at noon), and diminishes in proportion as the sun approaches the horizon. Photo-

graphers therefore prefer the middle of the day, *i.e.*, between 10 a.m. and 2 p.m., for taking portraits, for which the light of the blue sky only is used. During these hours the chemical effect of this light remains almost the same; afterwards it begins to diminish—quickly in winter, more slowly in summer. Thus the chemical power of light, according to Bunsen, expressed in degrees, is at Berlin:—

	12 o'clock.	1 o'clock.	2 o'clock.	3 o'clock.	4 o'clock.	5 o'clock.	6 o'clock.	7 o'clock.	8 o'clock.
June 21	38°	38	38	37	35	30	24	14	6
Dec. 21	20°	18	15	9	0	0			

It appears from this example how extraordinarily weak is the chemical action in winter (thus about noon on the 21st December only half as powerful as at noon on the 21st June); moreover, how small is the amount of chemical light which is diffused by the blue sky on the 21st December, on account of the shortness of the day. Therefore a longer exposure is necessary in winter than in summer, and, the printing process being slower, a longer time is required in winter to print the same number of pictures.

Now, the intensity of the blue sky light depends on the position of the sun, and the latter varies, not only according to the different seasons, but also at the very same seasons on different parts of the earth.

If circles be drawn round the earth from pole to pole, we obtain what are called meridians (*m m* Fig. 26). At all places situated on the same meridian it is noon at the same time, but the height of the sun varies very much according to the distance of the place from the equator.

If circles be drawn round the earth parallel to the equator, they form the so-called lines of latitude. If the sun is perpendicular at noon at a particular place on the equator, at 10° of north latitude it is 10° lower; that is, the height of the sun (or the distance of the sun from the horizon expressed in angular measurement) is 80°. At 10° further north, the position of the sun, at the same time, is only 70°; and at the pole, which is 90° from the equator, the height of the sun = 0; that is, the sun is on the horizon.

Fig. 26.

The chemical action of the blue sky light varies greatly, corresponding to the different positions of the sun at the same time. Thus, for example—

At Cairo, on the 21st Sept.,	the	strength	of light at noon	= 105°
At Heidelberg	„	„	„	= 57°
In Iceland	„	„	„	= 27°

Therefore, the more southerly a place is, the richer it is in the amount of light available to the photographer. Accordingly, the American photographers are better off than those of Germany and England.

These differences in the chemical intensity of light are also essentially modified by the state of the weather. If the sky is covered with grey clouds, the chemical intensity of the light is considerably less than with a perfectly clear sky. On the other hand, white clouds increase the power of the light very decidedly. In the autumn the chemical intensity of light is much greater than in spring, perhaps in consequence of the greater transparency of the air. According to Roscoe, it is in August and Sep-

tember more than one and a half times as great as in March or April.

These variations in the chemical intensity of light are very important to the life of plants. The green leaves of plants inhale carbonic acid and exhale oxygen under the influence of light. This breathing process does not take place without the presence of light. The green colour of leaves and the variegated colours of flowers only exist under the operation of light. In the dark, plants only develop sickly blossoms, like the well-known white sprouts of potatoes kept in cellars.

The necessity of light for the life of plants is also seen in the effort made by plants kept in darkened rooms to reach the apertures which admit light. Hence a plant develops with an energy proportional to the intensity of the light. The greater fruitfulness of the tropics is to be ascribed, not only to the higher temperature, but also to the greater chemical intensity of the light. Recent observations have established that the yellow and red rays, and not the blue and violet, produce the greatest chemical effect on the leaves of plants.

We have now arrived at the knowledge of the importance of light for the economy of nature. Atmospheric air is a mixture of two gases, oxygen and nitrogen. Nitrogen is a perfectly innocuous kind of air, serving to dilute the oxygen; for the latter, though essential to life, is injurious if undiluted.

In breathing, part of the oxygen is absorbed in the lungs: it forms, with the organic constituent parts of the body, carbonic acid and water. The carbonic acid and water are exhaled by us and dispersed again in the air.

It is easy to prove by an experiment that a consider-

able amount of carbonic acid is contained in the air we exhale. Carbonic acid forms with lime-water an insoluble precipitate, carbonate of lime. If now we blow the exhaled air through a glass tube into perfectly clear lime-water, the latter becomes milky by the formation of carbonate of lime. Hence, by breathing, the amount of oxygen in the air is continually diminished and converted into carbonic acid. The same result is produced on a larger scale by the process of combustion. In this process a combination of wood or coal with oxygen takes place, and the result is again, principally, carbonic acid.

It might be supposed from this fact, that, in the course of time, the amount of oxygen in the air must diminish, while that of carbonic acid would increase. This actually takes place in closed spaces. Leblanc found that, after a lecture in one of the lecture-rooms of the Sorbonne at Paris, the air had lost one per cent. of its oxygen.

In the open air no such a diminution of oxygen and increase of carbonic acid gas can be detected, and the reason of this is that the carbonic acid formed by combustion and the exhalations of animals is again decomposed by plants under the influence of light.

Plants absorb the carbonic acid, retaining the carbon and liberating the oxygen; by which means the latter, lost by combustion and exhalation, is made again available.

There was a time when the atmosphere was much richer in carbonic acid gas than now. When the incandescent and fluid masses that once formed our earth gradually solidified, when the aqueous vapours were condensed as seas, the atmosphere contained almost all the carbon of the earth, combined with oxygen, as carbonic

acid gas. The air was therefore at that time infinitely richer in carbonic acid than now. When at length the earth had cooled sufficiently for vegetation to be developed, gigantic plants shot forth from the warm ground under the influence of the sunlight. They flourished luxuriantly in an atmosphere so rich in carbonic acid, the carbon of the carbonic acid passed over into the form of wood, and thus for thousands of years the carbonic acid in the atmosphere was continuously diminished. Revolutions of the earth's surface succeeded; whole tracts were buried under sand and clay; their forests decomposed, and were changed into coal. A fresh vegetation sprouted forth from the newly formed soil, and again absorbed, under the influence of light, the carbonic acid of the atmosphere, to be once more engulfed. Thus the carbon from the carbonic acid of the atmosphere was stored as coal in the depths of the earth; and thus the atmosphere, by the chemical effect of light, became continually richer in oxygen, until at length, after countless ages, it attained that wealth of oxygen which made the existence of man possible.

We see, therefore, that the chemical influence of light has played an important part in the development of our planet, and that it continues to do so in the economy of nature.

CHAPTER IX.

ON THE REFRACTION OF LIGHT.

Simple Refraction—Index of Refraction—Refraction in Glass Plates—Prisms and Lenses—Production of Images by Lenses.

We have already pointed out (p. 60) that when a ray of light passes the border of two transparent media of unequal density, a change of direction takes place which is called refraction.

If a small coin is placed in an opaque cup, and the eye be kept in such a position that the edge of the vessel just conceals the coin, it becomes visible on pouring water into the cup, and this takes place by the refraction which the rays experience in passing from the water to the air. (See Fig. 27.)



Fig. 27.

The angle which the rays make, before and after the refraction, is called the deflection.

This deflection increases in proportion to the obliqueness with which the rays fall upon the surface of the water.

In order to determine exactly the degree of the refraction, let a line be conceived to be drawn at right angle

to the surface through the point of immersion n of the ray $n\ l$ (Fig. 28). This line is called the normal, and the angle i which the ray forms with this normal is called the angle of incidence, while the angle r which the refracted ray forms with the same normal is called the angle of refraction.



Fig. 28.

The ratio of the magnitude of the angle of incidence to the angle of refraction is peculiar. If a circle be described with centre n, and from the points a and b perpendicular lines $a\ d$ and $b\ f$ are let fall on the normal, these lines are what mathematicians call the sines of the angles. Thus $a\ d$ is the sine of i, and $b\ f$ the sine of r. The ratio of the sine of the angle of incidence to the sine of the angle of refraction is constant.

This ratio is, when light leaves air for water, 4 to 3; that is, the sine $b\ f$ is $\frac{3}{4}$ times as great as the sine $a\ d$, or the sine $a\ d$ is $\frac{4}{3}$ times as great as $b\ f$. Light is still more refracted on entering glass. In this case the ratio of the sines is as 3 to 2. This ratio of the sines of the two angles is called the index of refraction.



Fig. 29.

If a ray of light $n\ l$ falls upon a smooth sheet of glass (Fig. 29), it experiences a similar refraction; it continues in the direction $n\ n$, and the sine of the angle of refraction at n in the glass becomes two-thirds of the sine of the angle of incidence.

On issuing from the other side of the sheet of glass,

another refraction takes place; but in this case the sine of the angle of refraction at n' in the air becomes one and a half times that of the angle in the glass, and as the angle at n is equal to the angle at n', the angle of emergence of $r\ n'$ is of the same magnitude as the angle of incidence of $n\ l$; that is, the ray continues, after refraction, in its original direction. At all events, it only experiences a shifting parallel with itself. Therefore we see objects through our windows in the same direction in which they are really situated.

The result is entirely different when the spectator looks through a triangular glass (Fig. 30). If the eye is at o, and an object at a, and a triangular prism be held close to the eye, the object does not appear to be at a, but in the direction of a'. The incident ray $a\ d$ suffers a deflection at the first face of the glass, taking the direction $d\ c$; at the refraction on the second face it takes another, $o\ c$. Both deflections are in the same direction.

Fig. 30.



Fig. 31.

The greater the magnitude of the angle x which the two faces of the prism, through which the ray passes, make with each other, the greater is this deflection. Thus

the deflection by the prism *b* (Fig. 31) is greater than by the prism *c*, and by the prism *a* it is greater than by *b*; because the angle of refraction *x* is greater in *b* than in *c*, and in *a* it is greater than in *b*.

If a glass structure be erected, consisting of separate prisms of varying angles (Fig. 32), and if a bundle of parallel rays be conceived to fall upon it, the ray *a* will



Fig. 32.

be more strongly deflected than *b*, which falls on a prism having a smaller angle; and the latter, again, will be more deflected than ray *c*, and the result may be that all the rays unite in one point *f*.



Fig. 33.

If instead of the separate prisms we substitute a solid symmetrical mass of glass, we obtain the section of a burning glass, or, as the opticians say, a lens, which has the property of uniting all parallel incident rays in one point. (See Fig. 33.)

Every lens is contained between two curved faces. The connecting line running through the centre of the two surfaces is named the axis of the lens, and the point *E* (Fig. 33), where the parallel incident rays unite, is the focus, while its distance from the lens is the focal length. But not only are parallel rays united in one point by the refraction of a lens of this kind, the same thing occurs with the divergent rays which issue from any luminous point. The point in which such rays are united is called the conjugate focus of the luminous point.



Fig. 34.

A luminous point *S*, for example, sends a cone of rays to the lens. After refraction these are united at *R*. If *S* be brought near to the lens, *R* removes further; if *S* be brought so near that its distance from the lens is twice the focal length, then the converging point *R* is equally distant from the lens.



Fig. 35.

If instead of the luminous point an object (for example an arrow *B A*) is placed before the lens, from each individual point of the object a cone of light proceeds to

the lens, and all the rays of one and the same cone converge in one point, the rays from *A* in *a*, and those issuing from *B* in *b*; and the result is that a perfect miniature and inverted image of the arrow is produced.

If the arrow be moved nearer to the lens, its image is removed farther from the lens and becomes larger. For example, if the little arrow *a b* is placed before the lens, it produces the enlarged picture *A B*.

But if the arrow be removed farther from the lens, its image approaches the lens, and becomes continually smaller. Accordingly, a lens is able to project enlarged or diminished images of an object, the size of the image varying with the distance of the object from the lens.

CHAPTER X.

PHOTOGRAPHIC OPTICAL APPARATUS.

Construction of the Camera Obscura—Telescopic Images—The Magic Lantern—Enlarging Apparatus—The Stereoscope.

We have just shown that a lens is able to produce enlarged or diminished pictures of objects according to their distance. On this depends the property of the



Fig. 36.

camera obscura, the most important photographic instrument, to project plane pictures of solid objects. We have already described (see p. 7) its simplest form. It is a dark chamber having a small hole in the

shutter. This arrangement produces indistinct and weak pictures. But if a lens is placed in the hole of the shutter *o* (Fig. 36), a brighter and more distinct image is cast on the wall than that of a simple hole. It is evident that in this case the distance of the wall from the lens must correspond to the distance of the object. Now, as this varies, the dark chamber has been converted into a small box (Fig. 37), the back part of which is movable, and contains a ground-glass slide *g*. If the back of the camera *o* is moved to and fro, it is easy to find the exact situation of the image of an object placed before the lens *l*. In order to determine this distance with the necessary accuracy, photographic lenses are supplied with a rackwork motion *r* in the frame of the lens; but this addition is by no means necessary.



Fig. 37.

In order to be able to see the image on the ground-glass slide *g*, all foreign light which would blind the eye must be kept off, and for this a dark cloth is thrown over the head, forming what is called the focussing cloth.

The operation of seeking the image is named in photography focussing. It follows from what has been said that the image appears inverted on the ground-glass slide. Though the process of focussing appears simple at first sight, it is really rendered difficult by the fact that objects at different distances from the lens form images that likewise vary in distance from the ground-glass slide. For example, if a head be placed opposite a

camera, the nose is nearer to the lens than the hairs behind the head; and the result is that the image of the nose in the camera is farther from the lens than the hairs of the back or side of the head. Accordingly, the whole head never presents the same degree of sharpness or definite accuracy. Photographers are satisfied with obtaining the main points with definite clearness, such as the face, and they bestow less care on the subordinate parts.

If the situation of the object be rather remote (for example, a landscape, whose nearest features in the foreground are distant about fifty times the focal length), the images of the various objects, whatever their distance may be, appear all in the same focus.

The same thing occurs in the case of stars. Photographic cameras are well adapted to project images of stars, only they are very small if the focus of the lens is short. Accordingly, telescopic lenses are preferred in such cases. The production of images in this case depends on the same principle as the production of images by other lenses. If we imagine a telescopic lens *o o* (Fig. 38), and an arrow *A B* placed before it at a great distance, a very diminished image *b a* would be formed. Thus, the image of



Fig. 38.

the sun at a distance of 90 millions of miles, when cast by a lens of six feet focal length, is only eight lines in diameter. If it is wished to obtain the photograph of such an image, the tube *R*, on which the lens *L* is fixed, must be arranged as a photographic camera. (See Fig. 39.) A movable ground-glass screen *n* is used to focus the image, to be exchanged for a photographic plate during the exposure. This is the method adopted by Warren de la Rue, Rutherford, and others engaged in eclipse expeditions, and also by the author in the expedition to Aden in 1868.



Fig. 39.

The images taken by a photographer are usually smaller than nature. But he is also able to produce images that are larger than the originals. Every lens gives, as described at p. 86, images of the same object, varying in size according to distance. If the object is nearer than twice the focal distance, an enlarged image is produced, but if it is more remote, the image is smaller. The latter is the commoner case. The production of enlarged images direct from nature is attended with difficulties. The larger the image, the larger is the surface over which the light from the objects is spread, and, accordingly, the smaller will be the amount of light over each part of the image. But, in proportion as an image is deficient in light, the longer the exposure must be to produce a photographic impression. A man would find it difficult

to endure such a long sitting, therefore this method is only employed for drawings and the like.

Enlarged pictures of other objects are produced by the help of an apparatus resembling the magic lantern. The magic lantern serves for the production of enlarged images by means of lenses. Instead of a simple lens, a system of lenses *n n o o* (Fig. 40) is employed for enlarging, which gives more sharply defined images. The object is painted or photographed on glass plates, which are placed in the slide *a a*, and brightly illumined by the lamp *L*. The concave mirror *H* and the lens *m m* are employed to concentrate the lamplight on the object that has to be enlarged. The images obtained vary in size with the distance of the screen from the lens.



Fig. 40.

This instrument was formerly nothing but a plaything, but it has latterly become an important auxiliary in instruction. Photographs of microscopic preparations, of animals, plants, minerals, landscapes, national types and architecture, may be in this manner more faithfully represented than by maps, which are in general very imperfectly designed.

In America this application of the magic lantern is universal. Every educational establishment of any size

possesses one such instrument, and often more. In Germany, though so useful, it has been hitherto left in the hands of showmen connected with the annual fairs, who employ them for what are called dissolving views. These dissolving views are produced by the help of two magic lanterns placed side by side, both of which project their images on the same screen. If one of these lenses be covered up, one of the pictures disappears and the other alone remains visible. Meanwhile, if another picture be substituted for the one withdrawn, and the lid again taken off, a combination of two images is obtained. If the one lens be only gradually, not suddenly, closed, the corresponding image also fades gradually away.

Professor Czarmak, at Leipsic, has latterly introduced the representation of enlarged images by the magic lantern as a useful auxiliary in his lectures; and he obtained so great a success with it, that he prepared the way for its general introduction into schools.

We take this occasion to remark that wonderful pictures on glass have been lately produced from photographs by means of a new printing process. These glass pictures are now for sale, and are specially designed for the magic lantern. Their price is so moderate, and the objects they represent are so interesting—landscapes from all parts of the earth—that it is within the reach of every family to obtain a collection of the most beautiful and interesting views. At domestic entertainments by the family fireside, such pictures united with a magic lantern become an important means of instruction and enjoyment to both young and old.

A petroleum lamp is not sufficient for the representation of such images on a large scale. For this purpose

more powerful sources of light must be employed, such as the lime light or the electric light (see p. 72). To obtain photographs of such enlarged images, a sheet of sensitized paper is stretched over the place and instead of the screen.

To produce life-size photographs, the magic lantern is not used, but the so-called solar camera, a section of which is represented in Fig. 41, and a view of its exterior Fig. 42.



Fig. 41.

Sunlight is made to fall on a large lens *B*, which concentrates it on the small negative *N*; close to which is the objective *O*, which projects an enlarged image on the screen *R*. The image will be obviously a negative one. If a sensitized piece of paper be stretched at *R*, this paper becomes brown at all places where the negative is clear (transparent), and it remains white in all places where the negative is black (opaque); there-

fore the resulting picture will be positive. The whole apparatus is enclosed in a light-tight wooden box, which can be shifted by means of a rackwork motion, so that it can always be turned towards the sun.

In conclusion, we have to describe a most beautiful



Fig. 42.

optic-photographic apparatus, which enables us to see images not only as plane objects, but as solid bodies. This is the stereoscope.

Our readers know already that this instrument is intended to exhibit double pictures, the two halves of



Positive.



Negative.

P. 94.

NEW TALBOTTYPE OR LICHTPAUS PROCESS.

which at the first glance seem to be absolutely alike, and which when viewed through the instrument form one picture, which appears no longer plane but solid.

The two pictures which are seemingly alike are, in fact, different. If we look at a cube with the right eye, we see rather more of the right side; if we look with the left eye, we see something more of the left side, taking for granted that the head is not moved. The pictures of the right and of the left eyes are combined with each other and give the impression of solidity.

If we close one eye, the impression of solidity is far weaker; the objects appear plane or flat. This may not be readily credited, because men do not often seek an explanation of what they see, but look at objects much too hastily. But it can be easily ascertained that such is the fact if a bottle be placed before a wall, or in front of an upright book. If we then look at them with both eyes, we readily perceive the distance of the bottle from the wall or book, but directly we close one eye the bottle and the book appear to be almost contiguous, and it is only by moving the head on one side that we clearly distinguish the distance between them.

Accordingly, the use of both eyes is necessary for a perception of solidity. It is only in this manner that we come to the conviction that space has not only height and breadth, but also depth. One-eyed persons only receive this impression by turning the head on one side. If objects are very remote, the difference between the views which the right eye and the left eye have of them is very inconsiderable; and, accordingly, such remote objects appear flat and without solidity, and it is only when we change our position and observe them from

different sides that we become acquainted with their solidity. This is therefore purely an affair of experience. Every person will recognize a distant house as a solid object, because we know from experience that a house is solid; but that we actually see it as a flat surface is proved by the deception produced by theatrical decorations, where the remote background, if properly painted, often produces an extremely natural effect; but we perceive this background to be flat directly we move the head on one side. When this is done, a solid object presents a different appearance, but a flat surface remains unchanged.

Wheatstone was impressed by the fact that the solid impression made by an object is caused by the combination of the different views of it by the right and left eye. Accordingly, he tried to substitute for a single picture a view of the right side of an object for the right eye, and of the left side for the left eye. He obtained in this manner a perfectly solid impression, though the double picture occasioning it is no solid at all. Some people indeed are able to see stereoscopic pictures as solids without using an instrument. But most persons require an apparatus which renders it possible for both eyes to see in the same place the two separate pictures. This apparatus is the stereoscope (Fig. 43). Its most essential features are, the two pictures on the slide and the partition in the interior of



Fig. 43.

the box which prevents the right eye seeing the picture on the left, and vice versâ; and further, the lid, which is generally provided with a mirror which can be either shut or opened, so as to exclude or let the light into the box; and, lastly, the two lenses at the top.

These lenses are represented in the diagram (Fig. 44); they are two halves of one lens, and work in the same manner. We are indebted to Brewster for the construction of this instrument.

Fig. 44.

We have shown at a previous page that a lens gives a diminished image of a remote object, and an enlarged inverted image of a near object. This image is objective, that is, it can be rendered visible on the ground glass screen of a camera. Nevertheless, this phenomenon only takes place when the object is more remote than the focus. The case is different when the object is nearer to the lens. Let an ordinary magnifying or burning-glass be held near some writing, and it will be seen upright, and not inverted. The image appears also enlarged, but on the same side as the object, and the accompanying diagram illustrates the manner in which it originates. Thus F represents the focus of the lens, A B an object within the focal distance, and a b its image, as it appears to the eye upon the other side of the lens. As may be seen in the diagram, the rays issuing from A B do not actually unite to form an image, but their directions



Fig. 45.

prolonged through the lens (the dotted lines of the figure), unite to form the image *a b*, and there the magnified image will be seen. The eye seeks the objects seen in the direction of the rays which fall upon it, as may be seen, for example, in a mirror, where we see the mirrored objects behind.

In order to give a clear illustration of the different way in which a lens represents near and distant objects, we introduce the diagram of p. 85 again, which shows the production of an inverted and enlarged image *B A* representing the arrow *a b* situated without the focus.



Fig. 46.

A lens employed to see objects enlarged within the focus is named a microscope, or magnifying glass. The lenses of a stereoscope are such magnifying glasses. They present us with a rather enlarged upright image of the object seen, but they produce likewise the effect of a prism. As may be seen from Fig. 44, the two lenses consist properly of only two half lenses, which are placed in a reversed position.



Fig. 47.

We pointed out at a previous page that an eye *o* sees an object *a* through a prism in the direction *o a'*, that is, shifted towards the angle of the prism. The same thing happens with stereoscopic glasses. We see

the image, not in the original direction, but reflected towards the angle of refraction, that is, towards the centre of the instrument.

The two corresponding points a a', which belong to the right and left images, appear therefore in common to both eyes at a''—that is, at the same place—and consequently our two eyes see only one image instead of two.



Fig. 48.

Now, every one who wishes to see an object (for instance, writing) clearly and distinctly holds it at a definite distance from his eye. This distance is the distance of clear vision. In the case of good eyesight it is eight inches; with far-sighted persons it is more, and with short-sighted persons less. In the case of stereoscopic vision, the image appears remoter or nearer, according as it is removed from or approached towards the two lenses. If the image is near the lenses, it appears when viewed through them nearer and smaller. In the opposite case it appears farther and larger. But every one wishes to see the image at the distance of clear vision, therefore stereoscopes must have movable lenses, in order that persons may adapt the position of the object to the eye; that is, that they may vary the distance of object and lens until the image appears clearest. If such focussing arrangements are absent, the instrument is only adapted for eyes of average power of vision, and requires an effort in eyes of a different calibre. Persons are often met with whose eyes are not of equal strength, one being short and the other long-sighted. There can be no satisfactory stereoscope for such persons; for if the distance

of the lenses is adapted for one eye, it does not suit the other.

Nevertheless, such persons can obtain a tolerable stereoscopic effect if they hold a suitable eyeglass before one eye.

A great hindrance to viewing stereoscopic pictures on paper is the shape of the Brewster stereoscopic box, which is closed all round and only open at the top. This aperture only admits an insufficient amount of light to the picture, which is commonly left in the shade on one side.

This defect has been removed in the American stereoscope, which dispenses with any box. Lenses are fitted in a frame *g g* (Fig. 49), which may be held by a handle;



Fig. 49.

the partition *b* serves to separate the field of view of the two lenses. The object is placed on the cross-board *d d*, and this board can be easily slid to and fro, so that the proper position of the image with reference to the eye may be found.

But the American stereoscope is only suitable for paper pictures. The beautiful transparent stereoscope pictures on glass can only be viewed with Brewster's

stereoscope, as they must be seen by transmitted light, and all front light excluded, or the effect will be destroyed.

We have named the stereoscope an optic-photographic apparatus. But we remark that double pictures drawn by the hand can also be viewed through it. It is evident that the preparation of such pictures only succeeds in very simple subjects. It would be very difficult to represent stereoscopically a complicated object; for example, a man, a landscape, or a machine. Photography, which can produce with the greatest ease pictures of the most complicated objects from any point preferred, rendered this possible. It is only since the invention of photography that the stereoscope, which was formerly a philosophical instrument, has become a favourite instrument with the public. Notwithstanding their small form, the pictures of these instruments make a clearer and more intelligible impression than single pictures of the same object in a larger form. A single picture of a machine, or of complicated architecture (for example, the choir of the Cologne Cathedral), is often a hopeless maze of details. But in the stereoscope the confused masses are directly defined; they become distinct in perspective, and the eye perceives with great clearness the interior structure. In this respect the stereoscopic pictures are of equal value to the magic lantern in imparting instruction.

CHAPTER XI.

THE CHEMICAL EFFECTS OF LIGHT.

Physical and Chemical Processes—Moser's Experiments—Action of Light upon the Elements—Phosphorus, Oxygen, and Chlorine—Action of Light upon Salts of Silver—Chloride, Bromide, and Iodide of Silver—Theory of the Developing Process—Dry Plates—Theory of the Positive Process.

In the previous chapter we have become acquainted with the part which light plays in the processes of photography. We will now enter the domain of chemistry, in order to explain the phenomena which occur when substances sensitive to light are exposed to its action.

All bodies in nature are perpetually subject to change. The sun, moon, and stars change place; wood and sugar can be powdered; lead can be melted, and thus its state of aggregation altered. In such cases the matter is not changed. Wood may be rubbed or sawn into the finest dust, yet it remains wood; lead remains lead, notwithstanding the melting. Changes of this kind, that leave the matter of bodies unchanged, are styled physical changes.

But, beyond the physical changes, there exist others of a different nature. If a piece of wood be heated in flame, it burns and loses its character as wood. It

becomes changed partly into combustible gases, partly into ashes. A rod of iron, heated to redness in the air, becomes dull and coated with a black crust, which falls off in flakes when struck by a hammer. In this case the substance of the iron is totally changed. Changes of this kind are styled chemical changes.

Now, light is able to produce both chemical and physical changes. We have already stated that the red mineral, realgar, falls into a yellow powder when exposed to light. This is a physical change, for the yellow powder is still realgar, and if it is fused it forms, on cooling, compact red masses, which are again changed on exposure to the light. The number of physical changes of this kind occasioned by light is not great, but the phenomena are in themselves remarkable.

Moser has remarked that light has a certain action on almost all surfaces. He covered smoothly polished surfaces of silver, ivory, and glass with perforated screens, and exposed them to the light. After this he breathed upon them, or exposed them to the action of the vapour of mercury, and found that the vapour was condensed most powerfully where the light had reached the surface. Accordingly, Moser established the proposition: Light reacts on all bodies, and its action can be made visible by the greater condensation of vapours on the parts exposed to light.

The chemical changes effected by light are far more numerous than the physical, and their study is the special province of photo-chemistry.

Before passing to the more complicated phenomena of photography, we must make the reader acquainted with the simpler phenomena of the action of light.

(a) *Action of Light on the Elements.*

The chemist understands by the term elements simple undecomposable bodies. Thus water, which the ancients named an element, is no element in the chemical sense of the term, for it can be easily decomposed into two components of a gaseous nature—oxygen and hydrogen. Air, also an element of the ancients, is no element viewed in the light of chemistry, for it is a mixture of two gases—oxygen and nitrogen. But these two substances, oxygen and nitrogen, are undecomposable bodies, or elements. The chemical elements contain amongst their number all the known metals, also sulphur, phosphorus, chlorine (a greenish, strong-smelling gas); further, the less known substance bromine (a brown, unpleasantly smelling fluid); and iodine (a black, volatile solid). Each of these elements can combine with others to produce bodies with new properties. Metallic iron combines with the gaseous oxygen, and produces the red iron rust. Sulphur unites with oxygen, and produces the pungent, strong-smelling sulphurous acid. Iodine and chlorine combine with metals forming the iodides and chlorides, amongst which are iodide and chloride of silver.

It is remarkable that many elements present themselves in quite different forms, so that it might be supposed they were different substances. The yellow, inflammable, poisonous phosphorus, soluble in ether, and formerly used in the manufacture of matches, is changed by heating in a closed vessel into a reddish substance difficult to kindle, not poisonous, and insoluble. This is, however, phosphorus, and passes by melting into the state of common phosphorus.

It is an interesting fact that this transformation of yellow into red phosphorus is effected not only by heat, but also by light. If yellow phosphorus be exposed for a long time to the light, it becomes red.

The oxygen of the air is also susceptible of similar changes. Ordinary oxygen is a colourless and inodorous gas. By the action of electricity, however, it is easily changed into another kind of gas, distinguished by a peculiar smell—the so-called sulphurous smell of lightning. This new gas, ozone, has a much more oxidizing or rusting effect than common oxygen.

Ozone is also formed by the action of light. If oil of turpentine be poured into a large bottle containing air, and agitated violently in the sunlight, ozone is formed.

Equally peculiar are the changes experienced in sunlight by two other elements not so well known, chlorine and bromine, which have only been carefully observed latterly.

Chlorine is a yellowish-green gas, with a disagreeable smell, distinguished by its properties of bleaching coloured stuffs and destroying infectious matter. Bromine is a substance very similar to chlorine, but in a fluid not in a gaseous state at ordinary temperatures, though it can be easily vaporized, and then appears as a brownish-red gas.

Both chlorine and bromine gas show a peculiar relation to light, even in combination.

Chlorine gas behaves in a peculiar manner with hydrogen—a gas which forms one of the constituents of water, from which it can be easily obtained by the action of zinc and sulphuric acid. The zinc attracts the oxygen

of the water, forming, with the sulphuric acid, sulphate of zinc, while the hydrogen escapes in the form of gas.

If this combustible gas is mixed with chlorine, and the mixture is exposed to the sunlight, an explosion takes place. This accompanies the chemical combination of chlorine and hydrogen to form a new body—*hydrochloric acid*—having no resemblance to chlorine or to hydrogen. This acid is of a sour taste, very soluble in water, does not bleach like chlorine, and is not combustible.

Another body—iodine—is very closely related to chlorine and bromine. It is a solid, appearing in the form of shining black crystals, and giving when heated a wonderful violet vapour.

(*b*) *Chemical Action of Light on Salts of Silver.*

Iodine, bromine, and chlorine unite with metals, forming the iodides, bromides, and chlorides of the metals. Kitchen salt is one of the commonest combinations of this kind, consisting of chlorine and sodium. Sodium is a metal not employed in the industrial arts, which possesses the property of powerfully attracting the oxygen of the air, or rusting, so that it has to be protected by being kept under naphtha. The chlorides, bromides, and iodides of the metals all show a nature analogous to salt. Chloride, bromide, and iodide of silver are particularly interesting to us. These three salts may be obtained by the direct action of chlorine, bromine, and iodine on silver; but a more rapid method is to dissolve in water chloride, bromide, or iodide of sodium, and to add to them a solution of a salt of silver. For silver can also form salts.

If a silver coin is thrown into nitric acid, it is dissolved, forming nitrate of silver; and this is obtained on evaporating the solution as a white soluble salt, which when fused is called lunar caustic.

If a solution of this substance be mixed with a solution of chloride of sodium, a white curdy precipitate of chloride of silver is formed by double decomposition. Chloride of sodium and nitrate of silver produce chloride of silver and nitrate of sodium.

Bromide or iodide of silver may be produced exactly in the same manner if bromide or iodide of sodium be added to a solution of silver.

Bromide, chloride, and iodide of silver are thus separated as precipitates, because they are all three insoluble in water. After being washed and dried, all three salts appear in the form of powders, the chloride being white, the bromide yellowish white, and the iodide yellow. All three are very stable bodies, not decomposed by heat, and insoluble in water, alcohol, or ether; they are, however, dissolved by solutions of hypo-sulphite of soda or cyanide of potassium, by combining with these bodies to form new chemical compounds which are soluble in water.

These three stable compounds—chloride, bromide, and iodide of silver—show a marked sensitiveness to light, and this sensitiveness is the basis of modern photography.

By the light of a gas lamp in a dark room the chloride of silver appears perfectly white, but it quickly takes a violet tint in the daylight. It is often said that it becomes black; this, however, is not the case. This change of colour is the result of a chemical decomposition. The chlorine is in part set free, and may be detected by

its odour if large quantities of chloride of silver be employed. The violet powder which remains behind was formerly thought to be metallic silver.

Metallic silver does, it is true, under certain circumstances, present itself in the form of a grey or violet powder. The violet-coloured body formed on exposing chloride of silver to light is not, however, metallic silver; it is only a combination of silver with chlorine, which contains half as much chlorine as chloride of silver. Silver and chlorine form two compounds—one white and rich in chlorine, the other violet and with little chlorine, named subchloride of silver. In the same manner, silver forms two compounds with bromine—one light yellow, rich in bromine, named bromide of silver; and a yellowish-grey compound, less rich in bromine, named subbromide of silver. Further, analogous to these there exist a yellow iodide of silver, and a green subiodide of silver, less rich in iodide. Subbromide and subiodide of silver are produced exactly in the same manner as the subchloride, by the operation of light. The chemist says, therefore, that bromide, chloride, and iodide of silver are reduced by the action of light to the corresponding subchloride, subbromide, and subiodide.

The change of colour by which this chemical change is accompanied is most striking with chloride of silver, less with bromide of silver, and least so with the iodide.

It would appear from this that chloride of silver is the most useful to photography. But this is not the case. We have previously seen, whilst discussing the practical part of photography, that plates of iodide of silver and not of chloride of silver are exposed in the camera. The

image thus produced is nearly invisible, but becomes visible through a subsequent process, named the developing process.

In daguerreotypes the exposed plate of iodide of silver was exposed to the vapour of mercury. In this case the vapour was condensed in fine globules on the exposed places, in proportion to the change caused by the light. In the present treatment with collodion, the plate is washed over with a solution of green vitriol. This mixes with the adhering solution of silver, and precipitates from it a fine black silver powder, which adheres to the exposed places of the plate.

Therefore, in both cases we have a finely pulverized body, which is attracted and retained by the exposed places—a mysterious process, as interesting as it is practically important.

From this it appears that it is by no means the colouring of the silver salts which renders the image visible, but the subsequent developing process.

If an experiment be made with chloride, bromide, and iodide of silver simultaneously, by exposing and developing them, it is found that chloride of silver gives the feeblest picture under the developer, bromide of silver a stronger one, and iodide of silver the strongest. Therefore, the very body which was most strongly coloured by light is the least coloured under the developer, and the body which is least coloured by the light, viz., iodide of silver, is the most coloured under the developer.

The developing process is of immense importance. If it were attempted to produce a picture by exposure in the camera without developing, an exposure of hours would be required before the impression could be seen. The

developing process permits, under favourable circumstances, the impression to become visible after an exposure of only one-hundredth of a second.

Pure iodide of silver was formerly used in photography, but a mixture of iodide and bromide of silver is now preferred. This change was made because it was soon perceived that iodide of silver is very sensitive to *strong* light, but by no means so to weak light. For example, in taking a portrait, iodide of silver gives the light parts in a few seconds with great clearness, such as the shirt and the face; whereas the darker parts, such as the shadows, the dark coat, etc., are very feebly given. But, if some bromide of silver is mixed with the iodide, the coating of combined iodide and bromide of silver gives a weaker but still intense picture of the clear parts, while it gives a much better impression of the dark parts than iodide of silver alone.

The mixture of iodide and bromide of silver is effected in practice by adding to the collodion a salt containing iodine and a salt containing bromine; for example, iodide of potassium and bromide of cadmium. Both are decomposed in the silver bath. Iodide of potassium and nitrate of silver produce iodide of silver and nitrate of potash, and in the same way bromide of cadmium and nitrate of silver produce bromide of silver and nitrate of cadmium.

A considerable quantity of the solution of silver remains also adhering mechanically to the collodion coating. This adhering solution of silver is by no means a matter of secondary importance; on the contrary, while developing, it affords the necessary material from which the fine silver powder is precipitated.

If the developer (for example, a solution of green vitriol) is mixed with a solution of silver, the silver is precipitated in the form of a fine powder. For green vitriol—protosulphate of iron—readily absorbs oxygen, and is changed thereby into persulphate of iron. Accordingly, if a body containing oxygen (for example, nitrate of silver) is mixed with green vitriol, the latter withdraws at once the oxygen from the silver salt, and sets free the silver. Other bodies that readily combine with oxygen operate in like manner; namely, certain organic substances, such as pyrogallic acid and others. It was formerly thought that green vitriol reduced the iodide of silver affected by light; and this erroneous opinion is actually found in some of the most recent works on chemistry. It can be easily proved that this view is false. For, if a plate is exposed and the nitrate of silver adhering to it is washed away, and then the developer poured upon it, no picture appears, proving that green vitriol alone is without action on exposed iodide of silver. But if a solution of silver is added, a picture appears immediately.

The solution of silver adhering to the plate plays, however, another part. If a plate is washed before it is exposed—that is, if all the nitrate of silver which adheres to it is removed, and it is then exposed—it will be remarked that it is far less sensitive than when the nitrate of silver is present.

This is explained by the peculiar property of many bodies sensitive to light.

There are bodies which in isolation are either not at all, or only very slightly, sensitive to light, but which become so in the presence of substances which are able

to unite with one of the constituents liberated during exposure to light. For example, chloride of iron is not sensitive to light; but chloride of iron dissolved in ether is sensitive, because the liberated chlorine unites at once chemically with the ether.

The same remark applies to iodide of silver. This is, by itself alone, sensitive to light, but only slightly; in presence of a body which can combine with iodine, it is quickly decomposed in the light. Now, nitrate of silver, which reacts with iodine with the greatest ease, satisfies this condition; and this explains the greater sensitiveness of iodide of silver in the presence of nitrate of silver.

It follows from this fact, which was first accurately determined by the author, that other bodies which unite easily with iodine also increase the sensitiveness of iodide of silver.

Among these bodies may be enumerated extract of coffee or tea, morphine, and tannin. Such bodies enable photographers to prepare what are called dry plates. The plates, which are prepared in a silver bath, only remain moist for a short time; the adhering solution of silver dries up, and then dissolves the iodide of silver, so that the plate is actually eaten into. It is not therefore possible to keep a supply of such plates for any length of time, which would be very useful in travelling.

But dry plates which may be kept without spoiling can be prepared by washing away the nitrate of silver adhering to the moist plate, and then coating the plate with a solution of a substance having affinity for iodine; for example, with tannin or morphine. Such coatings can dry up without injury to the film of iodide of silver, and in this manner a durable dry plate is obtained. The

sensitiveness of the plates is considerably less than that of moist plates, but this is of no detriment in the case of objects well illuminated. The development of dry plates of this kind is commonly effected with pyrogallic acid. This substance is obtained by dry distillation of the gall-nut. It has a powerfully reducing action; that is, it precipitates metallic silver from silver solutions, exactly as green vitriol does.

But pyrogallic acid alone is not able to bring out an image on an exposed dry plate, because another substance is necessary to yield the silver. This substance, viz., a solution of silver, is found on the plates themselves when they are wet. But in the case of dry plates, the silver salt has been washed off; therefore mixed solutions of pyrogallic acid and nitrate of silver must be employed as developer. Finely divided silver is precipitated, adheres to the exposed places, and thus brings out the image. Nevertheless, dry plates do not give such beautiful and secure results as moist plates.

We have now given an illustration of the photochemical phenomena in the production of a camera picture. The essential part of this process—the negative process—consists in the developing of an invisible impression made by light by a subsequent operation.

But all pictures are by no means prepared in this way. We have already seen, on the contrary, that the pictures on paper are occasioned by the production of a visible impression of light, a piece of sensitized paper being exposed until it is coloured dark. In this case no developing is required. The picture is exposed to the light till it has received the necessary intensity.

The process is in this case quite simple. The paper

contains chloride of silver and nitrate of silver. The former is quickly, the latter slowly, reduced by the light to metallic silver, which is separated as a brown powder. Chloride of silver alone would only be reduced to sub-chloride of silver; but in the presence of paper-fibre the process of reduction is carried further, and metallic silver is formed. The chlorine set free by the light combines immediately with the silver of the nitrate of silver, and produces chloride of silver again. This is then decomposed by the light, and a fresh quantity of brown metallic silver is separated. And this process is repeated as long as nitrate of silver is present, and as long as the light operates.

Pure chloride of silver alone gives but a faint impression, but in presence of nitrate of silver it yields a very vivid image. The picture, in the form in which it is produced by the light, is not durable—it would turn brown through the further operation of light on the white places; and to prevent this, the sensitive salts of silver still adhering to the paper must be removed. The nitrate of silver is removed easily by washing with water, for it is soluble in water; but the chloride of silver must be removed by plunging in a solution of hypo-sulphite of soda. This salt reacts with chloride of silver, forming chloride of sodium and hypo-sulphite of silver, and the latter combines with the hypo-sulphite of soda to form a double salt, remarkable for its peculiar sweet taste, which is soluble in water, and can be removed by washing.

If a fresh print is plunged in hypo-sulphite of soda, it suddenly changes its beautiful violet colour—it becomes a yellowish brown; this tint is not liked.

It does not interfere with the effect in technical and scientific pictures, but is a great drawback in portraits and landscapes; so the positive prints are subjected to a further treatment, styled the toning process. They are immersed in a very dilute solution of chloride of gold. Metallic silver has more affinity for chlorine than has gold; hence it combines with the chlorine, forming chloride of silver, while the gold is precipitated, giving a blue colour to the picture. And this blue, mixed with the brown of the picture, gives a pleasant tone, which does not change in the fixing-bath; that is, in hypo-sulphite of soda.

Accordingly, every paper photograph consists of silver and gold, in the proportion of about four parts of silver to one of gold; the quantity of both substances being very small. In a picture of 44×47 centimetres, or 17 inches by 22, only one-thirteenth of a gramme, or about one grain, of metallic silver is contained. Its value is about one German pfennig,* and the value of the silver in a carte de visite is about one-thirtieth of a pfennig. The question may here arise, how it happens that photographers charge so high for their pictures? A sufficient reply is found in the fact that the price is not determined by the value of the materials, but by the labour which has been necessary to produce the pictures. It must be remembered that a photographer has to make twenty-eight operations to produce a negative, and eight to produce a positive; that a picture is often a failure; that for the one pfennig's-worth of silver in preparing a sheet, four-pennyworth of salts of silver must be employed, and that at the utmost only one-third of this

* About half an English farthing.

silver can be recovered from the washings. Nor should it be forgotten that the paper itself is valued at threepence, that cardboard of the same value is required for the mounting, and that further outlay is needed for the hire of premises and assistants—all which circumstances certainly justify the price demanded.

If it is borne in mind that thirty-three times as much silver must be employed as that which actually remains when the picture is finished, it will be seen that the amount of silver consumed annually in photography must be enormous. It is valued at about £1,350,000.

CHAPTER XII.

ON THE CORRECTNESS OF PHOTOGRAPHS.

Influence of the Individuality of the Photographer—Different Branches of Photography—Influence of Lenses, of the Length of Exposure, of Colours and Models—The Characteristic Feature in the Picture—Deviation from Truth in Photography—Difference between Photography and Art.

(*a*) *Influence of the Individuality of the Photographer.*

In the previous chapters we have become acquainted with the development, theory, and practice of photography. We have mentioned cursorily various practical applications; for example, the *lichtpaus* process. It is our present purpose to give our special attention to one point which is of great import in judging of the value of a photograph.

Most persons have a fancy that the application of photography is always uniform, whatever may be the object to be taken, and, therefore, that a photographer who can take a portrait must be able to take equally well a machine, a landscape, or an oil-painting. This results from the erroneous notion that the picture makes itself when the photographer removes and replaces the cap of the lens. But our readers know already that the picture does not make itself, but that it must be first

developed, intensified, fixed, and printed. In all these operations there is no precise measure or rule how long the photographer should expose to the light, develop, intensify, print, or tone his picture; it rests entirely upon his discretion. He is able at pleasure to bring out more or less of the details of a picture by abridging or prolonging the exposure, to make a picture more or less brilliant by intensifying, more or less dark by regulating the printing and toning. He must direct his judgment as to the correctness of his picture by nature and by nature alone. He must know nature, and compare his picture with it. Nor is this easy. Nature appears positive to him, but in the picture she at first appears negative; and if he compares the two, he must be able to convert the picture in his mind into a positive, which it is afterwards to become. More experience and study are required to do this than is generally supposed.

If two printed proofs are presented to a man who is ignorant of the art of printing, one of the sheets in question being well and the other ill printed, if the defects be not too glaring, this person will not be able to detect any difference between the proofs. The practised eye of the printer, however, immediately detects that in one proof the type is too thick or thin, or that the letters are faint or uneven. In like manner, a practised eye is needed to judge a photograph—an eye not only able to observe the finest details of the picture, but also the peculiarities of the original. The unprofessional man often uses the expression, "I have no eye for it,"—that is, "I am not accustomed to see such things,"—and it is in this manner that we first discover how imperfectly we use this, the most perfect of our senses.

A man born blind, and who recovers his sight by an operation, cannot at first distinguish a cube from a sphere, or a cat from a dog. He is not accustomed to see such things, and must first learn to see.

We, also, though in possession of sound eyes, are blind to all things that we are not accustomed to see; and this fact is most apparent in art, as also in photography, so closely related to it.

If photographers principally engaged in taking portraits are not able to produce a good landscape, the reason of this is that they have no eye for landscapes; that they consider a picture to be good after too short an exposure, or when imperfectly developed and intensified, or when badly printed. It proceeds from their not knowing the influence exercised by the position and intensity of the sun or clouds, without speaking of other points of less importance.

Thus every class of subjects requires a special study, although the mere manipulation remains in all cases the same. There are photographers whose proper province is portraiture, and others devoted to landscapes, to the reproduction of oil-paintings, etc.

(*b*) *Influence of the Object, of the Apparatus, and of the Process.*

The remark is frequently made by admirers of photography, that this newly invented art gives a perfectly truthful representation of objects, understanding by the term truthful a perfect agreement with reality. Photography can, in fact, when properly applied, produce truer pictures than any other art; but it is not absolutely true. And, as it is not so, it is important to become acquainted

with some of the many sources of inaccuracy. I shall treat here especially of optical errors.

The lenses which are employed in photography do not always give absolutely true pictures. Suppose, for example, that an image of a square is formed by a simple lens; the sides of the image will often be curved, as in the accompanying diagrams, though not so markedly. A picture taken with such a lens, in which straight lines come out as curves, is evidently inaccurate. The inaccuracy may not be perceived by many, but it exists. It may per



Fig. 50.

haps be expected that this defect disappears in the case of what are called correct lenses, but let the attempt be made to obtain a picture with these correct lenses of lofty buildings taken from a low position. The lines that ought to be perpendicular commonly converge upwards. This is caused by the photographer being obliged to direct his camera upwards, in order to be able to take in a view of the whole building, and thus the perpendicular lines are represented as convergent. To avoid this defect, lenses have been made with a very large field of view. These are called pantoscopic; but they reproduce distant objects

apparently on a very small scale, and objects near at hand on a very large scale—peculiarities unnoticed by unprofessional persons, but detected by close observers of nature.

A remarkable phenomenon, exciting the wonder of the uninitiated, is the distortion of spheres in photography. Let the reader imagine a row of cannon balls: these will always appear spherical to the eye, and an artist would always draw them as spheres; but if they are taken



Fig. 51.

with a lens with a large field of view, the outside balls no longer appear circular but elliptical.

To explain this phenomenon, we must attend once more to the mode in which the picture is produced. Let it be conceived that there are three balls *A B C* in front of a camera *K*, with the lens *o* (Fig. 51). Each ball projects a cone of rays on the optical centre of the lens, and an inverted cone is formed within the camera, and cuts the surface of the picture, if its axis falls obliquely upon

it, in the form of an ellipse, such as *A* and *C*. It is only when the axis of the cone of rays is perpendicular to the surface of the picture *S S*, as at *B*, that the image appears a circle. This defect, however, only occurs when the field of view of the lens is very large, and the balls are situated very near its border.

A photographer once brought to the author the picture of a castle having a row of statues in front of it, which he had taken with a lens having a large field. Curiously enough, the heads and bodies of the statues towards the margin of the picture became broader and broader; and the slim Apollo of Belvedere, which unfortunately stood on the very margin, had such full-blown cheeks and so protuberant a paunch, that he looked like Dr. Luther.

But, quite independently of these considerations, there is another point that must materially affect the accuracy of photographic representation. Photography generally gives the light parts too light, and exaggerates the dark shadows. This is a natural fault, which it is very difficult to avoid. It is seen in the most apparent manner in taking objects lighted by a brilliant sunlight; for example, a statue. If the exposure is short, a detailed picture is obtained of the light side, but the shady side is a black blotch. If the exposure is long, the shady side is full of detail, but the light side exposed too much, and so deeply coloured that the details are wanting in it. Hence photographers, in order to obtain correct pictures, are obliged to avoid strong contrasts of light and shade in their models far more than would be thought desirable by artists. The latter often exclaim when they see the illumination of a model, and are surprised when

the picture is correct. And, no doubt, in the case of landscapes and architecture, the results are not always satisfactory.

The author once took a photograph of the interior of a laboratory which had a vaulted roof. All was excellent. The tables, furnaces, retorts, lamps, etc., were all seen, only the vaulted ceiling was quite dark. New attempts were made, with exposures of 20, 30, and 40 minutes. At length a trace of the vault appeared; but now the objects near the window were suffering from too much exposure; that is, they had become as white as if they had been snowed over. This circumstance, that photography exaggerates the dark parts, appears again in very simple matters, such as the reproduction of copper-plate engravings. A photographer once reproduced a painting of Kaulbach's "Battle of the Huns." He produced a charming photograph, but the city in the background appeared too thick and black, and not soft enough. The customer refused the photograph and demanded another. The photographer made another attempt, giving a longer exposure, and now the distance appeared softened down; but, unfortunately, the objects close at hand, which had to appear black and clear, turned out grey. In the end, the photographer escaped from the difficulty by retouching the negative. These are quite ordinary examples to show how difficult it is to reproduce an object correctly.

But we come now to the worst point, the colours. Photography gives the cold colours—blue, violet, and green—too light, and the warm colours too dark. Take as an instance the photographs on sale of "A Sunset on the Ganges," by Hildebrandt. It represents a red glowing sun with clouds of chrome yellow on an ultramarine

sky. But what becomes of all this in the photograph? A black round disc between black thunderclouds. It looks like an eclipse at Aden. The difficulty of representing nature is still more patent when the photographer attempts to grapple with higher artistic themes. Let us take an example. There exists a pretty *genre* picture called "A Mother's Love." A young mother sits reading in an armchair; her little darling embraces her suddenly from behind, and, delightfully surprised, she drops her hand with the book, turns to look at her little pet, and offers him her cheek to kiss.

A photographer was inspired with the idea of producing a similar picture with the help of a living model, He found a comely maiden, who agreed to personate the mother, and a good-looking boy was also found. An armchair for the mother, a chair, and other suitable furniture were easily procured. The next point was the grouping. The pseudo-mother was very accommodating to the requirements of the photographer, and even assumed a look which, for want of a better, might pass as the expression of a mother's love. But the boy was not of the same mind. He was by no means attracted by the pseudo-mother—he protested against coming near her, and a good cuff was needed to make him take up the requisite position. Time was thus lost. The mother began to feel uncomfortable in the irksome position, straining her neck. The photograph was taken at last, and turned out sharp and without spot or blemish. The models were dismissed to their great satisfaction. What was the result? The boy was embracing his mother with a face bearing evidence of the cuff he had received, and with a look as if he would have liked to murder her;

and she regards him with an expression that seems to say, "Charles, you are very unmannerly," and appears greatly annoyed that her pleasant reading has been interrupted. Can it be said that a picture of this kind correctly expresses the intention of the artist? Does the picture thus produced correspond accurately to its name, "A Mother's Love"? The untruthfulness of such a picture will be evident to every one.

Thousands of pictures of this class are offered for sale. About ten years ago errors of this kind were committed by the thousand in stereoscopic views, and if they meet with approval this must be referred exclusively to the bad taste of the public. It may, however, be said in this case it is not the photographer who is guilty, but the unwilling models.

Nevertheless, it is this very circumstance that throws such immense difficulties in the way of taking good photographic portraits. Many persons by no means wish that their characters should be correctly given. The rascal wishes to appear an honourable man in his picture; tottering old men desire to seem young, foppish, and lively; the maid-servant plays the fine lady, the tradesman's daughter would be a court lady, the crossing-sweeper a gentleman. Thus the picture serves them only as a means of flattering their personal vanity; and, in order to appear very noble and distinguished, they put on a Sunday dress, often borrowed and a very bad fit. They practise at home, moreover, before their looking-glass, in the presence of papa, mamma, wife, or lover, attitudes impossible in an artistic point of view. Even cultivated persons are not exempt from these absurdities. Thorwaldsen relates of Byron, who gave him a *séance*:

"He sat down opposite to me, but assumed, immediately I commenced, a perfectly different expression. I called his attention to this. 'That is the true expression of my face,' replied Byron. 'Indeed,' I rejoined, and then made his portrait exactly as I wished. All persons declared my bust to be an excellent likeness. But Lord Byron exclaimed, 'The bust does not resemble me; I look much more unhappy.' The fact was that at that time he wished to look intensely miserable," adds Thorwaldsen. The photographer is even in a worse case. If Byron had come to a photographer and had presented his face of misery to the camera, what could the photographer have done? He is unfortunately dependent on the model, and many models leave him in the lurch at the critical moment, often not intentionally, but from nervousness or inadvertence. Much depends here on the influence of the photographer, who must know how to control his sitters with courtesy; many portraits, however, fail without any fault on his part. The author has often witnessed how persons of his acquaintance, at the moment of being taken, assume quite a strange expression without being in the least aware of it.

There are still more characteristic cases of photographic inaccuracy which cannot be attributed to the models. Let us suppose that a photographer, stimulated by the beautiful pictures of Claude, Schirmer, and Hildebrandt, wished to photograph a sunset. He evidently can only expose his plate for a moment to the dazzling bright sun. What sort of picture is the result? A round white blotch and some shining clouds are all that appear clearly. All objects in the landscape—trees, houses, and men—have had too short an exposure, and

form a black mass. There, where the eye clearly distinguishes road, village, forest, and meadow, it sees in the photograph nothing but a dark patch without any outline. Is such a picture true? Even the most fanatical enthusiast of photography will not dare maintain this.

Cases where violent contrasts of light and shade make the production of a correct picture quite impossible, are countless in number. Let any one examine the majority of the photographs of the white Königsdenkmaal in the Thiergarten at Berlin. The monument is excellently given, but the background of trees is a confused black mass, without details, without shades of tone; the architecture and other features are there, all except the splendid foliage that delights the eye at that spot. Still more numerous are the photographs of rooms, in which the dark corners, quite discernible to the eye, present nothing but pitch-black night.

There are other cases besides these of photographic incorrectness. Suppose we are looking at a mountain landscape. A small village, enclosed on both sides by woody hills, occupies the centre, its houses extending along the declivities and scattered picturesquely among the trees. A ridge of finely broken mountains in the background, their summits shining in the setting sun, completes the wonderful picture, whose effect is only injured by one object—a ruinous pigsty close to the spectator, with a dung-heap beside it. An artist, who wished to paint this scene, would certainly have no scruple about altogether leaving out the pigsty, or leaving it so indistinct and dark that it would not injure the landscape. But what is the photographer to do? He cannot pull down the offending object. He seeks

another position; but there the greater part of the landscape is concealed by trees. He ends by admitting the pigsty, and what kind of picture is the result? On account of its vicinity, the pigsty appears of colossal size in the picture. On the other hand, the landscape, which is the principal thing, appears small and inconsiderable. A still more fatal adjunct is found in the dung-heap occupying almost one-fourth of the picture. As the most brightly lighted part of the photograph, it immediately attracts the eye of the beholder; it diverts his glance from other important points. The photograph obtained does not appear to be a picture of the landscape, as intended, but a view of the pigsty. The accessory has become the principal point. The picture is untrue. It is untrue, not because the objects it represents were not present in nature, but because the accessories are presented too glaringly and too large, while the principal features appear too small, indistinct, and inconsiderable.

This brings us to a weak point in photography. It represents accessories and principal features as equally defined. The plate is indifferent to everything, while the genuine artist, in reproducing a view of nature, gives prominence to what is characteristic, and entirely keeps under or softens off accessories. He can dispose and manage his picture with artistic freedom, and he has a perfect right to do so, because, by his giving prominence to what is characteristic, and dropping what is accessory, he is truer than photography, which gives equal prominence to both, and often more to what is accessory. Reynolds says of the portrait of a lady in which an apple-tree was most carefully painted on the background: "That is the picture of an apple-tree and not of a lady."

Similar remarks might be made on seeing many photographs. It is a cardinal error in their case, that they give a stronger tone to accessories than to essentials. They present a conglomerate of furniture, and it is only after careful inspection that a man is detected among it whose portrait should form the picture. In another case a quilted white blouse is seen, and it is only after some time that a girl's head is perceived rising above it. A park is seen in a landscape, with fountains and other adornments, and it is only after some time that a black coat is seen confounded with an equally dark bush.

It may perhaps excite surprise that the writer ascribes greater truth to painting than to photography, which is generally regarded as the truest of all methods of producing pictures. It must be self-evident that this remark can be made only of the works of masters. One of the great services of photography is that it has rendered impossible those daubs of inferior artists formerly offered for sale in every street. But the perfect picture of the photographer is not self-created. He must test, weigh, consider, and remove the difficulties which oppose the production of a true picture. If his picture is to be true, he must take care that the characteristic is made prominent and the accessories subordinate. The photographer attains this end, on the one hand, by appropriate management of the original; on the other, by a proper treatment of the negative. To do this he must of course be able to detect what is characteristic and what accessory in his original. The sensitive plate of iodide of silver cannot do this. It receives the impression of all that it has before it, according to unchangeable laws.

Therefore, whoever wishes to be successful in photo-

graphy must first become familiar with the object that he wishes to take, that he may know what he has to do. The photographer will not, indeed, be able to control his matter like the painter, for the disinclination of models and optical and chemical difficulties often frustrate his best endeavours; and hence there must always be a difference between photography and a work of art. This difference may be briefly summed up by saying that photography gives a more faithful picture of the form, and art a more faithful picture of the character.

CHAPTER XIII.

LIGHT, SHADE, AND PERSPECTIVE.

The Difference between the Picture and Reality—Effect of Shade—Perspective Foreshortenings—Effect of the Position of the Spectator—Influence of Distance—Influence of the Height of the Eye.

In the previous chapter, while treating of the incorrectness of photographs, we tacitly assumed that it is possible to give a true picture of an object, if not by photography, yet by the hand of a skilful artist.



Fig. 52.

We will now see how far this assumption is admissible.

Let the simplest case be taken; for example, a cube or a cylinder. Let these be drawn, and figures will be obtained nearly identical with those marked X and S in the diagram. Now, these figures are flat like the paper, while the originals are solids. It may be said that picture and solid agree; but it is not so. Let a blind man be questioned, who knows the bodies by touch only. Now, the cube can be moulded in marble or plaster, and then the deception—for such it is—can be carried to

great lengths. The wood of the cube or of the cylinder can be imitated by painting. The eye will readily pronounce such imitation to be wood. The blind man, who feels both, will say: The form agrees, but not the mass — one cube, that of wood, feels warm; the other, that of stone, cold.

The principles that apply to these two objects apply to all objects and their representations. No one of them is a perfectly true copy of the object. When the surface representation makes on our eye the impression of a solid object, this is an illusion by which our eye suffers itself to be deceived.

If two rectangles *A* and *B* are drawn on paper, both appear as plane figures. But directly one of them *B* is shaded with thinner or thicker lines, the rectangle no longer appears flat, but cylindrical. Thus, by imitating the gradation of light and shade, we have produced a deception for our eye. This division of light and shade is one of the most important means of producing an appearance of solidity.



Fig. 53.

But there is another and a more important means of deception—perspective.

If we observe the cube (Fig. 52), the faces of which are equal, we perceive that these faces appear of very different length. The surface turned towards our eye appears a square, while the others are shortened in a marked degree, the surface appearing quite irregular, the parallel lines running together and converging to one point *o*, called the vanishing point. The same thing

happens with all other bodies: a human arm hanging down or a standing column *S* (Fig. 52) appear at their full length, but the lying column *L*, and the arm extended towards us, appear foreshortened. Their dimensions are contracted; in short, we see, instead of the shaft of a column, only its circular base *b*, and this, again, appears sometimes round, when its full surface is turned towards us, at others an ellipse, which it is not in fact, and in this case the parallel sides of the column converge. The track of a railroad viewed in perspective presents the same features. The fact that we do not feel this deception—for such it is—to be one, results from habit.

We know from experience that the arm extended towards us is longer than it appears, in perspective, to our eye, and also that the rails which appear to run together are parallel. We are continually correcting the errors of our sense of sight. The eye gives us a false representation of objects, and the painter takes advantage of this circumstance. He represents the lying column *L b*, and the sides of the cube, as falsely as we see them—that is, "foreshortened" in their dimensions, with their parallel lines converging—and every one is deceived by this.

It is the task of the artist as of the photographer to represent perspective correctly; that is, as it appears to our eye. If this is not the case, the picture appears incorrect.

Perspective teaches us the laws of foreshortening.

Our eye is a camera obscura with a simple landscape lens. It is known from optics, that the image of any point lies on the straight line drawn from the point to the optical centre of the objective, at the place where this

line, named the principal radius, cuts the plane of the image—the ground-glass screen of the camera or the retina of our eye. The image of a straight line is the place where the rays from each point of the line, passing through the optical centre, cut the ground-glass screen. Now, these rays form a plane, and this plane cuts the flat screen in a straight line. Therefore the image of a straight line is to our eyes another straight line, and the image of a plane triangle another plane triangle. If the flat figure is parallel to the retina, by well-known stereometric laws the image is like the original. Let the reader imagine a glass slab placed perpendicular to



Fig. 54.

the axis of his eye; then the rays or pencils of light issuing from this object *a b c d* will cut it so as to form a figure *a' b' c' d'* (Fig. 54). If such a figure is drawn for a given point of intersection, this drawing, if brought to a proper position and distance from the eye, will produce on it exactly the same impression as the object itself. This is the secret of the solid appearance of plane pictures properly constructed. A picture made in the manner just described is named a drawing in perspective. It is evident that such a drawing must be viewed under the same conditions as those in which it was designed.

If *A B C D* (Fig. 55) is the outline of a house, *B* the picture, *O* the point of intersection of the rays, and *a b c d*

the image of the points *A B C D*, the eye must be brought exactly to the point of intersection *O* if the representation in perspective *a b c d* is to produce the same impression as the object.



Fig. 55.

If the picture is brought nearer to the eye (for example, to *B'*), it is evident that the rays will intersect at a very different angle from those issuing from the object *A B C D;* accordingly, they cannot produce a correct impression. The same thing would be the case if the picture were removed farther from the eye (*e.g.* to *B''*). Therefore every drawing in perspective must be viewed from the point of intersection of the rays adopted as the basis of its construction, if it is to produce a correct impression.

Now, photography is a drawing in perspective whose point of sight is in the objective. Accordingly the inspecting eye must be brought to the same distance as the objective; that is, to the focal distance. If this is not done, the impression is untrue.

We have lenses with a focal distance of only four inches, and even less; and at such a distance it is impossible to see a drawing with the unaided eye. To do this it must be held at the distance of at least eight inches, and that is the reason why photography in such cases produces an untrue impression. This is often the case with views taken with lenses of great aperture.

There are other abnormal appearances which accompany portrait taking. Thus, the same object gives an

entirely different picture according as it is viewed from a greater or less distance. Let the reader conceive a pillar with the outline *A B C D*, let it be viewed from *P;* in this case the faces *A B* and *C D* will be perfectly seen. Now let the spectator approach nearer to the object; for example, to *O*. From this position nothing is any longer seen of the faces; the entire character of the picture becomes changed. If instead of a pillar a human face



Fig. 56.

be thought of, it is evident that the cheeks will contract if we approach the object, and the face appear too narrow in proportion to its height.

The accuracy of this conclusion is proved by the following illustrations. The two representations (Fig. 57) of the head of Apollo were taken at the distance of 47 and 112 inches.* The bust was placed perfectly upright, also the photographic apparatus, and the directing line was most carefully arranged.

The contrast is obvious. The whole figure appears in I. slimmer, the chest almost contracted; on the other hand, the same model II. appears with full cheeks and square shoulders. That this slimness is by no means a

* In order to secure a correct reproduction of both, they were reproduced upon wood by a process of photographic wood engraving. The reproduction does not give the same impression as the original, but it is sufficiently intelligible to the careful observer.

mere deception of the eye may ascertained by measurement.*



Fig. 57.

The distances between the eye and the point on the

* In the original photograph, where the two busts stand out from a black background, this difference is still more marked.

chest marked by a cross are exactly equal in both busts —the greatest breadth of chest, including the arms, amounts in I. to 56 millimetres, and in II. to 59 millimetres. Quite independently of this glaring difference, there are other marked distinctions between the two heads which strike a careful observer. Let a line *a a* be drawn across the top of the hair—in II. it is horizontal, in I. it inclines to the right.

Next let attention be directed to the pedestal. The curves in I. are strongly inclined, and in II. are quite horizontal.

Let the ends of the arms *A A* be next considered. In I. the side surface is scarcely seen, and in II. it is very apparent. In like manner, it is clearly seen that the back pedestal at *u* stands out more in II. than in I. In II. the head stands more between the shoulders (let the angle of the neck be observed at *W*); in I. it rises up more; therefore the whole form appears in I. to raise up the head. In II. the head appears somewhat bent forward; and yet the figure was immovable, the lenses employed free from flaw, the direction and height were the same in both. Nothing was different but the distance.

The author, besides taking these two heads, has taken two others at the distance of 60 and 80 inches; and if the four heads thus taken are placed beside each other, it is seen how with the increase of distance the form becomes fuller and more thickset; how the hair sinks more and more; how the ellipses of the pedestal become flatter; how the chest increases in width, and the stumps of the arms stand out.

Thus, therefore, we see very different views of the

same object at different distances; just as the same portrait placed in different lights expresses an entirely different character.

It may be objected that these are small matters, and that it is indifferent whether the statue looks a little too thin or too stout. To many this may appear unimportant in the case of Apollo—most persons do not know in the least how he looks. But it is a different matter in the photography of portraits, when the personality of the customer himself is in question. Persons quite untutored in art have a very quick eye for their own physiognomy—a line, a wrinkle, an outline, a curl, are in this case criticized, and differences that would not be at all remarked in the picture of Apollo become very striking. It is therefore the duty of the photographer to attend to the effects of distance.

Now, many persons would perhaps wish to know which distance is the best; which gives the most correct picture.

We might reply that this depends on the individuality of the person. Painters in general recommend for the drawing of an object a distance that is twice its own length; accordingly, for a man six feet in height, a distance of about twelve feet; for his bust, about five feet. The painter, however, has here greater freedom; he can add, omit, and alter at his pleasure. In photography this is only partially possible.

The appearance of hollow bodies is as much altered by distance as that of solids.

If *A B C D* (Fig. 58) is the inside of a box, we should see the side *A B* much more foreshortened from the distance *P* than from *O'* or *N;* therefore, its picture

taken at short distances will show it wider in proportion to its height than if taken from a more distant point. The



Fig. 58.

same thing occurs if we imagine *A C* to be the trunk, and *C D* the lap or the feet of a seated person. In that case the lap appears much larger in relation to the trunk, and the feet of a standing person appear longer from the shorter distance. Let the reader observe, for instance, the foot

Fig. 59.



Fig. 60.

of the Apollo in I. (Fig. 57), which is much more prominent than in II. Lastly, let *C D* (Fig 58), be supposed to be the carpet or ground; this will appear wider—that is,

rising higher—seen from *N*. Therefore, if the same person is taken from different positions, *P* and *O'*, so that the height of the body remains the same in both pictures, in that one taken at the shorter distance the prominent parts—lap, hands, and feet—appear wider, and the ground or chair more inclined (Fig 59) than in the picture taken from *P*.

Fig. 61.

Very important changes result from an alteration in the height of the spectator's eye.

If a standing person is looked up to, so that the head of the spectator is lower than the head of the object, the latter appears thrown back. If the head of the spectator is on a level with the head of the object, the latter appears perpendicular; if the spectator is higher, the head of the object appears inclined forward.

The three accompanying diagrams, taken from photo-

Fig. 62.

graphs, will make this evident. The first shows the view taken on the same level, the second taken from above, the third from below.

Similar differences occur in viewing a landscape from

a high and from a low position, as may be seen from the three woodcuts on next page. The dotted horizontal line shows the height of the eyes of the spectator (his horizon). The first picture gives a view as a person sitting on the ground would see it; the milestone on the left appears unusually high, towering to the sky, and the men appear taller, but the ground looks contracted

Fig. 63.

(foreshortened). The second picture gives the view as seen by a man standing erect: in this case the ground widens out, rising higher, and the milestone appears

Fig. 64.

Fig. 65.



Fig. 66.

lower. In the third picture, which gives the view from twice the height of the man, the figures and the mile-stone appear small and contracted. They appear persons who are smaller than the spectator, while the ground widens out and rises considerably in the picture. These examples show how important is the choice of position both in photography and painting, and how an incorrect choice produces quite an abnormal picture. The photographer is unfortunately often obliged to take a position that does not give a favourable view, for example, of lofty buildings in narrow streets (the Rathhaus in Berlin, St. Stephen's at Vienna), or among mountains, where often the trunk of a tree, which does not offend the eye of the spectator, destroys the picture of the photographer, and forces upon him the choice of a less picturesque but unincumbered locality.

CHAPTER XIV.

THE APPLICATIONS OF PHOTOGRAPHY.

We have by this time learnt the difficulties of obtaining a correct photographic picture; and the reader is now capable of examining the various problems attempted by photography.

We shall carry this examination only so far as is necesssary for the comprehension of the subject, and is of general interest to every one.

Section I.—Portrait Photography.

Popularity of Portraiture—Æsthetical Defects—Dependence of Success on the Person to be taken—Effect of Dress—Effect of Colours—Pictures of Children and Groups—Effect of the Size of the Picture—Life-size Pictures—Instantaneous Pictures—Photographic Copies of Photographs.

Scarcely any other branch of photography has enjoyed so much popularity as that of portrait-taking. Most persons understand by the term photography only the art of portraiture, and few only are aware that it can be used for any other purpose. The photographic portrait owes its popularity to its extraordinary cheapness, to the rapidity of execution, and to its relatively greater resemblance when compared with drawings from nature. Photography, with all its imperfections, can reckon, on

account of these circumstances, on greater support than the drawing of an artist; and the more so as a false belief exists that photography is invariably accurate, which is by no means the case, as we have already seen.

Photographic portraiture having driven the trade of portrait-painting out of the field, the genuine artist only is able to hold his own against it. This branch—portraiture—more than any other depends on the good taste of the operator—on his power of giving a natural or at least apparently natural position to the sitter, concealing as far as possible all personal imperfections. He must by clever manipulation of the light be able to give prominence to the essential points and leave indistinct those parts which would injure the effect of the picture. To this end the photographer is able to include the surroundings of the person, be they a chamber or a landscape, or to exclude them by screens.

In the first period of photography the pictures were commonly crammed with accessories, and incredible errors were committed with relation to position and light; but now the more advanced photographers have taken hints from artists, and latterly pictures are seen which, notwithstanding the mechanical character inherent in their production, create quite the impression of art.

The model—that is, the person to be taken—has a very essential share in the work of photography. Not unfrequently persons go to a photographer in a very morose frame of mind, or they lose their patience at some delay or other; it also often happens that people go who are slightly unwell—with headache or a bad night's rest. This is a great mistake; the bodily or mental

condition stamps itself infallibly on the picture, and often gives it an expression unlike the original, even after the photographer has used all his art upon it. In like manner it very frequently happens that persons at the moment of being photographed put on a perfectly strange expression, force a smile, stare, let the mouth fall open, or are disturbed by the iron rests which keep the head steady, and are quite essential if a well-defined picture is desired, but which are only submitted to under protest by the model, who fancies he can sit motionless without such aid.

None of these influences can be set aside by the photographer. The persons who present themselves to have their portraits taken are for the most part unknown to him. He has often only five minutes to study their faces, to find their best side, and to place them in accord with the surroundings. He probably attends to these matters as skilfully as any one, yet he has no power over the features of the original. Nor has he any idea whether the expression of a person is his usual one, or happens to be modified by ill temper or ill health. In the latter case it is impossible for the picture to please, however masterly may be the execution; yet the fault lies not with the photographer but with the original.

Another cause of failure is that many persons insist upon choosing their own position, whether of their own accord or prompted by friends. All attempts to make a good picture under such circumstances will generally fail, because the errors in perspective previously enumerated are overlooked. People in general do not know this, but the photographer does. Other inconveniences result from the very nature of photography. Blue eyes are

generally too light and dim, blonde or auburn hair too dark. Many of these difficulties are removed by clever retouching, but by no means all.

Still greater are the hindrances which the toilette and the caprices of fashion furnish. Bad taste in dress is more visible in photography than in nature. Ladies deficient in taste frequently make their necks, which are naturally short, appear still shorter and thicker by necklaces. They disfigure a form, perhaps naturally excellent, by long trains; the back of their head by an ill-chosen chignon; and their hair by ribbons of the brightest and most glaring colours. In these cases the photographer can do much service by his good advice. The difficulties are even increased if groups or children are in question.

Children must be amused: and if the photographer wishes to succeed in taking children's portraits, he must know how to win their confidence; this is the reason why many photographers achieve such success in this sphere, and others fail. As a child can never be long quiet, he must be taken as quickly as possible; such portraits therefore can only be taken in fine weather.

The same remark applies to groups of many persons. No photographer has twenty or thirty head-rests at his disposal, he is therefore frequently reduced to the necessity of trusting to the good-will of his sitters for not moving. Those groups are very ugly which show a row of persons sitting beside each other like so many pagodas. The clever photographer therefore fixes the attention of his sitters by some occupation, such as looking at an album, eating, drinking, or card-playing. These persons must then of necessity assume various positions, some showing their front face, others their profile. The differ-

ences of complexion and dress in groups present great difficulties. Thus the exposure which suits fair faces will be too short for the dark. But as all must have the same length of exposure, it is not surprising that many parts of the picture appear under and others over exposed.

From these causes, no one can expect to appear to so great advantage in a group as in a separate portrait; if it happens so, this must be ascribed to chance.

It is usual for people to expect too much or too little from photographic groups. Your companion in the group is commonly well satisfied if his own portrait suits his fancy, quite forgetting the ungraceful arrangement of the rest, or the want of sharpness of his neighbours, who do not interest him so much.

Gentlemen ought to wear dark clothes. Light trousers and white waistcoats often appear in pictures as white patches, destroying the effect of the whole, for the principal light ought not to be concentrated on such accessories but on the head. Ladies, in choosing their toilettes, generally overlook the abnormal action of colours. On the occasion of the triumphal entry of the Emperor and the German army into Berlin, in 1871, the young ladies chosen to grace the ceremony were afterwards photographed in their white dresses trimmed with blue, and were not a little surprised that, in the picture, the blue trimming was as white as the dress. Blue often becomes white in photography, though there is an exception in the case of the blue uniform of the Prussian infantry. On the other hand, yellow and buff become black; the same remark applies to red. The photographer can, by a careful treatment of the negative, in some degree counteract this defect in case the clothes are of uniform colour.

The many-coloured toilettes, however, now in fashion, produce a disastrous effect. Materials whose beauty consists in variety of colour, it is evident, cannot make the same impression in photography as in nature.

Persons of dark complexion, also those who are stout, should prefer dark clothes. It is well known that white clothing increases in appearance the size of the figure. Thin and pale persons are advised, on the contrary, to wear light clothes, as a pale complexion would appear even paler when contrasted with black. Light clothing is always to be recommended for children. Materials should be chosen which by their lustre make a rich and picturesque impression; for example, satin, ribbed silk, taffeta, and silky materials. Woollen stuffs appear for the most part dull and lustreless, but they give very good effects as drapery. Persons with short and thick necks would do well to avoid high shirt collars, which make the neck appear still shorter. Ladies with similar attributes must lay aside velvet, ribbons, and such things around the neck; while persons of long necks will be improved by such ornaments.

The weather, the season, and the time of day present serious difficulties in photography. The days in winter being considerably shorter and darker than those in summer, commissions at Christmas are very inconvenient. Rainy days in winter are for the most part useless for photography; in summer they are light enough. The hours immediately before and after noon are the most favourable, as we have already stated in our chapter on optics.

Besides the clearness of the weather, the amount of light admitted by the instrument is an important matter.

The brighter the image produced by the lens is, the shorter will be the time necessary for a sitting. The greater the diameter and the shorter the focal length of a lens is, the more brilliant is its image. But it is by no means possible to increase the diameter or diminish the focal distance as much as you please, for optical defects in the lenses, which have not yet been overcome, stand in the way of this. The best lenses hitherto constructed (portrait lenses) only produce small pictures of cartes de visite, or at most of cabinet size. Larger pictures can be produced only by lenses giving weaker images; therefore they require longer sittings—a circumstance that makes the operation more difficult in cloudy weather or with restless models (as children) than the preparation of smaller pictures.

Accordingly, the latter show, on the whole, a greater technical perfection. As they are also very cheap, it is natural that the small cartes de visite, introduced by Disderi at Paris, have attained a general popularity, and given rise to a new kind of album, displaying the portraits of friends instead of poetry, and almost entirely supplanting the old scrap-book.

We can only approve of the modern album with its light-drawn likenesses of those we love or respect. We do not however like to see cartes de visite hung from the wall, they are too small to have any effect, and their frames are too insignificant.

Photography, like engraving, is an art that succeeds best on a small scale. Pictures of more than quarter life size cannot easily be taken from nature, but life-size pictures are demanded by the public. The photographer prepares these from a small negative, by help of the

enlarging apparatus previously described in the chapter on optics.

For these pictures he requires a bright sun which, unfortunately, in our climate leaves him frequently in the



Fig. 67.

lurch. The small negative is placed in the apparatus (Fig. 67) at *N*, and on the table at *R* a sheet of sensitive paper is stretched. The lens at *O* projects a magnified picture of the little negative on the screen *R*, and when the apparatus is turned to the sun the large condenser *B* concentrates sufficient light on the picture to occasion a rapid browning of the paper: indeed, under favourable circumstances, a life-size copy can be taken in fifteen minutes.

Much has been said of instantaneous pictures. The Deputy Faucher remarked once, in the Prussian House of Deputies, "Instantaneous pictures are now possible. Portraits can be stolen by this process, and it will per-

haps be necessary to guard against it by the most extraordinary precautions—perhaps even masks will have to be worn." This statement is based on a mystification. Faucher had been made the victim of one of those photographers who, by incredible boasting and by puffing themselves, seek to impose on the public. Instantaneous pictures are possible if the object is clearly illumined by the sun; therefore an instantaneous picture of a brightly illumined landscape can be prepared. A portrait in a studio is quite another matter. Direct sunlight would produce an unpleasant glare and sharp shadows upon a dark background; the eyes would be contracted, and a very ugly picture would be the result. As we before remarked, very powerful lenses have been constructed, which admit of shortening the time of exposure. These are, however, only suitable for very small pictures, and are only employed for small, restless objects, like children, in which case the photographer is satisfied if he gets the chief part—that is, the head—as quickly as possible into the picture.

It occurs frequently that persons wish to have an old photographic picture copied. We here remark that, though such a copy is possible, a photograph taken from a photograph is never so fine as the original picture. The cause of this is, on the one hand, the brown tone of the photograph, which possesses very little photographic activity; on the other hand, the paper is sometimes glazed, and then produces a false light upon the reproduced picture, or is rough, and then the fibre of the paper gives the picture a disagreeable, coarse-grained appearance. On that account it is easy, even for unpractised eyes, to distinguish the copy from the original

photograph. Such copies are frequently to be met with at fairs and in stationers' shops, and can be bought for a ridiculously small price. In most countries, however, copying from original photographs is forbidden as piracy, and this prohibition ought soon to be introduced into Germany.

It has, indeed, been remarked that such infringement of copyright is advantageous to the public by lowering the price of favourite pictures.* But this advantage is no compensation for the injury thus inflicted on the author of the original pictures, who may have been put to considerable expense in obtaining his photographs, perhaps from distant places such as the Hartz mountains, or by the many failures before he has succeeded in making an imposing picture of a distinguished person. A great undertaking of this kind is seldom successful at first, and if his production is not protected by the law, he will prefer to give up producing such original pictures.

Section II.—Landscape Photography.

Its Scope—Difficulty of Taking Landscapes—The Photographic Tent—Application of Landscape Photography to Geography—Dry Plates—Stereoscopic Landscapes—Transparent Stereoscopes—Panoramic Picture

Landscape photography is a branch much less pursued than portrait photography. While portraits are generally made to order, it is a very rare thing to receive orders for a landscape. Such views are left to speculators, who employ photography as a means of representing favourite localities in largely frequented countries,

* Precisely the same argument can be advanced to defend the piracy of books, which is forbidden.

making thereby a profit with tourists. Thus photographers wander through the noteworthy sights of our capitals and mountains, and as the originals are accessible to every one, each of the competitors tries to outdo his fellows by excellence of work or cheapness. The copyist preys upon these original photographers; he does not undertake any costly journeys, but awaits the issue of original photographs to copy them at once, and offer them at a low price. The inclination of the public is here favourable to the cheap seller. A landscape is seldom bought for its value as a work of art, but more as a souvenir of a happy hour, or as a reminiscence which, in subsequent years, will recall some interesting object, whether a statue or a castle; therefore less is demanded in the case of views of landscape or architecture, and this is the reason why landscape photography is not at present in a very high state of perfection. The English are relatively the best in this branch, because they get good prices for their pictures and are protected against piracy. The Swiss views of Mr. England have a world-wide celebrity: in Germany pictures of equal merit are only produced by Baldi and Würthle at Salzburg. Braun of Dornach also deserves an honourable mention, having produced excellent landscapes, his Swiss views being known everywhere.

Superficial observers entertain the belief that one photograph of a landscape must be as good as any other, as the object remains always the same, and all are prepared by the same process.

Both assumptions are, however, erroneous. The object is not always the same, for a landscape appears under very different aspects in the morning and evening light,

or in fine and clear weather. Whoever studies these effects of light will soon discover at what hour a landscape will look most beautiful, and will choose it for taking his view. Accordingly, his picture will greatly surpass that of a superficial and hasty photographer, who takes the landscape as he finds it. The choice of the position is equally important. A few feet higher or lower, or a few paces to the right or left, and the whole aspect of the scenery is altered (see page 144). The man having the eye of an artist, who knows how to seek the best position, will at all times give the best picture.

The same remark applies to views of architecture and sculpture. It is evident that a photographer who undertakes such views must be favoured by wind and weather. A breeze stirring the trees often injures his picture, which may be rendered impossible for days together by wind or rain. To this difficulty may be also allied that of an unmannerly class of people, who insist on being taken with the picture, and thrust themselves right in front of the photographic apparatus, making the attempt impossible—a weakness that is more commonly met with in Germany than elsewhere, and is the more inexplicable as such people generally see nothing more of the picture.

A great inconvenience for the landscape photographer is that all the chemicals, bottles, glasses, dishes, etc., which are requisite for the process, must be carried on the journey; nay, more, the photographer needs a transportable dark room to prepare his sensitive plates.

The accompanying figure represents an apparatus of this kind, together with the photographer at work. The upper part of his body only is in his tent, but the

space between him and the tent is made light-tight by suitable curtains. For the sake of facility of transport, everything in a dark tent of this kind is contracted into the smaller space. A yellow glass q lets light into the interior: the silver bath is in a box y, and the necessary water is in the cistern x, from which a pipe passes into the interior. The whole tent can be folded up, and forms a box of the size of z in the figure.



Fig. 68.

Though these arrangements are very compact, they are still of considerable weight, making the ascent of difficult places, such as the Finsteraarhorn, the Wetterhorn, and the Jungfrau, impossible.

Dry plates are very useful in producing views of this kind, as they can be prepared at home and taken on a journey. The traveller can then dispense with a dark tent, collodion, silver bath, and the water for washing. The dry plates and camera are all that is necessary. It will be remembered from the description already given, that dry plates are prepared by washing an ordinary sensitized collodion plate, pouring on it some substance absorbing iodine, such as tannin, and then leaving it to dry. Unfortunately, plates prepared in this manner are less sensitive than the fresh wet plates, and the pictures they give appear less delicate than those taken with wet plates; the results, moreover, are very uncertain. Many plates spoil after a lapse of time. Then, the view obtained cannot be judged till it has been at home; and if, as often happens, it is a failure, it cannot be remedied by taking another picture. For these reasons, the wet-plate process has been preferred in taking landscapes, notwithstanding its inconvenience, and but few photographers work with dry plates.

Stereoscopic views of landscapes are very popular, for though so small, they surpass larger pictures in their power of truthfully representing landscapes. We have already described how these views are taken. If the light is bright and the lenses large, instantaneous views can be taken with the stereoscopic apparatus, and have been offered largely for sale.

The transparent stereoscopic views on glass, prepared by Ferrier and Soulier, are wonderfully beautiful. They are produced on a collodion film by placing the glass negative taken from nature on a dry plate, and then exposing it. A print of the negative is thus obtained

upon the glass plate exactly in the same manner as with sensitive paper, only the action of the light is at first invisible, and must be developed with pyrogallic acid. As the production of such glass positives requires a more laborious and lengthened treatment than the paper pictures, their price is higher.

Latterly, however, by the help of a printing process (the Woodbury process), it has become possible to produce these pictures at a considerably cheaper rate. We shall describe this process further on.

Though at first sight landscape photography may appear unimportant, yet it is of the greatest use for geographical information. There is no better medium for conveying a true picture of foreign lands, of rocks, plants, and animal forms, than photography. It has even become an essential auxiliary of exploring expeditions, being alone capable of giving a perfectly faithful description of what has been seen. The inconvenience of transporting a photographic apparatus, and the ready decomposition of the chemicals, naturally limit the use of photography in exploring expeditions, and require a very expert photographer; but that these obstacles can be overcome is proved, among others, by the excellent views taken by Count Wilzek and Burger at Nova-Zembla, Baron Stillfried in Japan, Burger and Lyons in India, and Dr. G. Fritzsch in South Africa. We shall show in the following chapter the importance of landscape photographs for land-surveying.

Panoramic views are a special branch of landscape photography. The noted photographer Braun, of Dornach (Alsace), has sold for many years pictures which contained half the circumference of the panoramas of the Rigi.

Faulhorn, Pilatus, and other well-known points. It is evidently impossible for a fixed camera to command at once such a panorama; the human eye cannot do this; the most we can survey is 90°, and this is only a quarter of the



Fig. 69.

whole circumference. If we wish to see the whole circumference, we are obliged to turn round. Martens, a German engraver residing at Paris, conceived the idea of taking panoramic views with the help of a revolving camera, or

of a revolving lens in a camera. Let the reader imagine a camera with a semi-cylindrical back, of which Fig. 69 represent a horizontal section, also a lens *o*. Then the image of any point *a* is situated on the line *a o b*, which is drawn from *a* through the centre of the lens. If the lens revolves round its centre, the image remains immovably at its place *b*; if it were to revolve about any other point than its centre, the image would be displaced. It is therefore evident that, if the lens revolves round its centre, it can form successively an image of half the horizon on the cylindrical surface. The only problem, then, is to produce a sensitive cylindrical surface. This is not difficult with sensitive paper, but much more difficult with glass, which is extremely breakable in this form. Accordingly, Brandon introduced a smooth plate, which rolls as it were round the cylinder *p p*; that is, which during the revolution of the lens is moved in such a fashion that it always remains perpendicular to the axis *o b* of the lens. The mechanism of such a camera is rather complicated, but it has maintained its ground in practice, and numerous panoramic views have been taken with it. We must confine ourselves here to a general description; those who seek for further details are referred to Vögel's "Manual of Photography."

Section III.—Photogrammetry, or Surveying by Photography.

Application of Photography to Measurement—Principle of Trigonometrical Measurement—Projection of Maps—Photographic Measurement of Altitudes.

An essential difference between a photographic view and an artist's painting is the fact, that it is not the production of the operator's will, but that its outline and

design are subject to determinate laws. All photographic views are produced by means of lenses. A lens image of this kind is always in exact central perspective; that is, each point lies on the straight line which can be drawn from the original through the optical centre of the lens. Let *a b c* (Fig. 70) be three objects, *K* a camera (of which the outline is given to facilitate comprehension), and *l* its lens; then the images of the objects *a b c* will be on the lines *a o*, *b o*, and *c o*—produced, viz., at *a' b' c'*; they have therefore the same relative position as the originals. Accordingly, a good photograph can serve to determine accurately the position of objects in nature, or to construct maps of the piece of ground that has been taken in the view.

For example, let the reader imagine the optical image of the camera placed flat upon the paper; and then, in the middle of the picture (in this case the tree *b'*), a perpendicular line be drawn equal to the focal length *o b'*. It is only necessary to draw lines from the point *o* to the images of the objects *a c* and *F* to at once find the directions in which the tower, the flag, and the trees will be seen from the position *P*. If now a second view be taken from a point *P'* which lies in the direction of the flag *F*, a second view is obtained *c'' b'' a''*, which naturally looks quite different from the first in consequence of the change of position. If this view from the second position be also placed on paper, in a position corresponding to *P'*, and a line *b'' o*, equal in length to the focal distance, be drawn as before, then the lines *c'' o* and *a'' o* will give the direction of the objects *a b c*, as seen from *P'*. If these lines be sufficiently produced on the paper, they will intersect at points the situation of which corresponds exactly to

that of the object; and thus, in two views from two points, the means is afforded of constructing a map in which the situation of all points contained in both views is exactly given.



Fig. 70.

A different procedure is followed in ordinary trigonometrical measurements. The first step would be to measure the distance $P\,P'$, then to set up an instrument for measuring angles at P, and to determine the angle made by the line $P\,P'$ with the lines $a\,o$, $b\,o$, $c\,o$; the

same operation being repeated at the other end of what is called the base line $P\ P'$. It is evident that so many measurements must be made at both points as there are objects of interest, whereas a photographic picture in one operation fixes the relative position of all objects. Accordingly, there is a considerable economy of time in the application of photography; and this is of great moment in time of war, when frequently, in consequence of interruptions on the part of the enemy, the leisure is wanted which is necessary for triangulation; also in journeys, when the stay at particular places is too short to make observations requiring time.

Therefore this process has great advantages in exploring expeditions, whose photographs would thus be doubly valuable; for not only do they give a view of the country, but also data for the projection of maps. For this purpose two views taken from each end of a base line are necessary. Moreover, the taking of these views must be carried out with mathematical accuracy: the camera must be placed in a perfectly horizontal position; its lens must give a perfectly correct image; the plates must be absolutely level, etc.—conditions which are not easy to comply with. To these other difficulties are added, proceeding from the very nature of photography, which requires clear, bright weather; with a troubled sky, or when the atmosphere is misty—the aerial perspective of landscape painters—distant objects are often so indistinctly given in the picture that no correct measurement can be made of them, though the surveyor can clearly distinguish and measure from nature in such weather. Further, the direct action of the sun offers difficulties to photography. If it stands in front of the

camera and shines full on the lens, it often occasions fogging on the plate, greatly affecting the value of the picture for purposes of measurement. All these circum-



Fig. 71.

stances militate against the application of photogrammetry, as this mode of measurement has been called by Meydenbauer, who has long used it. Meydenbauer pre-

pared a good map of the Unstrutthal by this method. But the experiences during the campaign of 1870 are not so satisfactory (the royal Prussian staff tried the process before Strasburg)—perhaps the imperfection of the apparatus used occasioned the unsatisfactory results. It is to be hoped, in the interests of geography, that future attempts will succeed in making this important method practically available.

Photography can determine the elevation of mountains and of buildings, as well as determine positions in a plain. Let it be supposed that $a\ b$ (Fig. 71) is a tower, and $a'\ b'$ its image in a photographic camera. It is evident that the image will be smaller than the object. According to a well-known mathematical law, the size of the image $a'\ b'$ is to that of the tower $a\ b$ as the distance of the image from the lens $o\ r$ to the distance of the tower from the lens. This gives the proportion:

$$o\ r : D = a'\ b' : x,$$

where D is the distance of the tower from the camera, which can be measured. The height of the tower can be easily found from the above proportion.

Meydenbauer has deduced the dimensions of the ground-plan and elevation of a house from a photograph.

Section IV.—Astronomical Photography.

Its Application—The Photographic Telescope—Eclipses—Protuberances—Corona—Sun-spots—Enlarged Images of the Sun—Researches of Rutherford—Astral-Photography—Pictures of the Moon—Photographs of the Spectrum—Photography and the Transit of Venus.

The application of photography to astronomy is twofold. First, to give a faithful representation of certain

phenomena of the heavens—which change so rapidly that the draughtsman cannot follow them; for example, the phenomena of eclipses, or others which are inconvenient to draw, such as sun-spots. Secondly, astronomical photography has to produce pictures of heavenly bodies which can be used for measurements. Photography has been used successfully for both purposes, and it is employed daily as an auxiliary to produce views of sun-spots at several observatories; for instance, in Germany, at the observatory of Herr Von Bülow, Privy Councillor at Bothkamp, near Kiel.

The mode of preparing astronomical pictures differs little from that of ordinary photographs. An ordinary photographic apparatus could be used for this purpose,



Fig. 72.

were it not that it gives too minute images of very remote objects, such as the stars. The size of the picture is in direct proportion to the focal length of the lens; therefore, in taking astronomical photographs, lenses are used the focal length of which is very long, by converting an astronomical telescope into a photographic camera.

The accompanying figure shows a telescope of this kind adapted to photographic purposes. The objective *O* remains in its place, the eye-piece, which would be fixed at the other end of the tube, is taken away, and an apparatus *V* (Fig. 72) is substituted for it, which is

identical with the hinder part of a photographic camera. It contains a ground glass slide *S*, which, after the image



Fig. 73.

has been focussed, can be exchanged for a sensitive plate. The focussing is effected by a rackwork motion at *T*.

But now a difficulty occurs through the motion of

the stars, which necessitates the telescope following this movement. For this purpose, the stand of the telescope is furnished with a driving-clock, which causes it to revolve in the direction of the course of the stars, so that the telescope is what is called equatorially mounted. Fig. 73 shows an arrangement of this kind.

The oblique support of the telescope resting on the foot is parallel to the axis of the earth. The polar axis of the telescope is turned completely round in this support once in twenty-four hours.

The telescope *d d* is not fixed immediately on this axis, but on an axis *c*, at right angles to it; it can be turned round the latter (the declination axis) in all directions perpendicular to the axis *c i*. The movement of the two axes allows any star to be brought into the field of the telescope.

The first attempt to employ photography for astronomy was made by Berkowsky, at the Königsberg Observatory, in the year 1851, by the help of Bessel's noted heliometer, during a total eclipse of the sun. He obtained a daguerreotype, the beauty of which was much lauded, and which showed very well the remarkable phenomena that appear during an eclipse of the sun—flame-like formations that stand out from the darkened disc of the sun, called protuberances. In the year 1860, Warren de la Rue in England, and Secchi at Rome, undertook an expedition to Rivabellosa, in Spain, to observe the eclipse of the sun, and both obtained interesting views on collodion plates. In 1868, the Government of the North German Confederation equipped an expedition to observe the eclipse of August 18th, and sent Dr. Fritzsch, Messrs. Zencker, Tiele, and the author to take photographs.

Another photographic expedition was sent out by the English Government to India. Besides these, the German, English, Austrian, and French Governments sent out expeditions for the ocular observation of the phenomenon.

Obstacles were, no doubt, encountered by these expeditions, nevertheless they produced results that finally settled the question about the nature of the protuberances, and moreover gained experience that materially lessened the labour of subsequent photographic observers.

We introduce a description of the expedition to Aden, giving a faithful account of the obstacles associated with an undertaking apparently so simple. The author wrote from Aden the following account of his arrival and residence at that place:—

"The aspect of Aden is by no means cheerful. A broken mass of rock, bare and desolate, the remains of an extinct volcano, among which are warehouses, shops, coal-sheds, flag-staffs, etc.;—such was the appearance of the place that was to be our residence for a fortnight. The colour green was entirely wanting there.

"Our luggage and ourselves were conveyed to land amid the shouts, quarrelling, and tumult of the Arab mob. On landing we learned that our colleagues, who had preceded us, had been received in the most courteous manner by the British authorities, and that two Indian huts—bungalows—used in this climate on the east side of the peninsula, had been assigned us as our station.

"After a long search we found the locality and our comrades, together with the members of the Austrian expedition, Dr. Weiss and Messrs. Oppolzer and Riha, and

in as excellent quarters as could be wished on this desert coast. The English authorities acted the part of host in the most generous manner. A whole staff of servants, cook, etc., waited upon us; carriages, camels, and donkeys were at our disposal, and all our wishes were anticipated. Thus our bodily comfort had little to desire; the temperature (26° Reaumur *), might be called low for the Red Sea, for a fresh breeze was always blowing on the heights of the Marshagill, on which our bungalows stood, and contributed greatly to our comfort.

"There still remained ten days to prepare for taking views of the eclipse. They were employed in preparing stands, mounting and arranging our telescopes. We used as observatory a bungalow, which we partly unroofed, in order to use our telescopes, and we converted the rest of its interior into a laboratory, washing-room, and store-room. In this bamboo cage—for it was nothing more—we were tolerably protected from the wind, but less so from the dust. Water was brought to us by donkeys, in leather bags. Two tents that we had brought from Europe answered the purpose of dark rooms. Spare apparatus for taking landscapes and portraits, that we had brought with us, gave us the material for taking views of the country and its population, and were also a useful means of testing our chemicals.

"Some trifling defects in the latter were quickly remedied, but it was not so easy to remove the effects of the dust and human exhalations. During the slightest exertion in that damp atmosphere, the perspiration flowed from the body in streams: it ran from

* 90·5° Fahrenheit.

the tips of the fingers, dropped from the face, and often a well-cleansed or prepared plate was spoilt by a drop of sweat. Nevertheless, practice taught us how to encounter this obstacle; some attempts at taking the sun, etc., were successful; and we were able to tranquilly await the eclipse. Only one thing gave us serious uneasiness—that was the weather. All accounts of Aden had unanimously represented its sky as perfectly clear, competent witnesses having asseverated that it rained there at most three times a year, and that clouds were exceptions.

"We were therefore not a little surprised when, on our arrival, we found the volcanic heights of Aden quite concealed with clouds, and when we were greeted with a shower of rain on the following morning. But we became still more anxious when, day after day, the sun was concealed by clouds, and this weather became worse rather than better in the course of time. The prospect of succeeding in our main object looked dreary enough, and soon all our hopes deserted us.

"On the day of the eclipse we left our quarters about 4 a.m. Nine-tenths of the sky were cloudy. We set to work in a resigned frame of mind. It was the undertaking of the North German expedition to photograph the eclipse throughout its continuance. For this purpose we used a telescope with a six-inch achromatic lens, with a focal length of six feet. This lens, made by Steinheil, gave an image of the sun three-fourths of an inch in diameter, which could be taken on a photographic plate by the help of an ordinary dark slide containing a plate for two pictures. As the sun and moon move, such an instrument, if stationary, would only give ill-defined

views. Accordingly, the telescope was connected with clockwork, which gave it a movement corresponding with that of the heavenly bodies. To avoid all agitation of the telescope, the closing lid of the objective was not placed directly upon it, but on a separate stand, and was connected with the telescope by an elastic sleeve.

"The duration of the total eclipse was at Aden three minutes, in India five. We had, however, chosen our station at Aden because photographic observers were already present in India, and because the eclipse began about an hour sooner at Aden than in India. Thus, by comparing our observations with those in India, a judgment might be formed whether those wonderful phenomena of light called protuberances, seen during total eclipses, changed or did not change in the course of this time. It was our present endeavour to take as many views as possible of the phenomenon in three minutes. With this object we had regularly practised, as artillerymen do their cannon.

"Dr. Fritzsch prepared the plates in the first tent, Dr. Zencker pushed the slides into the telescope, Dr. Tiele exposed them, and I developed them in the second tent.

"We had ascertained that it was possible in this manner to take six views in three minutes.

"The decisive moment approached. The cloudy sky anxiously surveyed by us, showed to our great satisfaction a few breaks through which the disc of the sun, partly concealed by the moon, and appearing as a crescent, was visible. The landscape appeared in the strangest light, being almost a half-and-half mixture of sunlight and moonlight. The chemical action of the light showed itself very weak. An experimental plate

only gave a view of the clouds after fifteen seconds' exposure. The sun's crescent became gradually smaller, the break in the clouds gradually increased, and we took heart.

"The last minutes preceding the total eclipse, which occurred at 6.20, fled on wings. Dr. Fritzsch and I crept hastily into our tents and remained there, preparing plates and developing. The consequence was that neither of us saw anything of the total eclipse. Our labour begun, the first plate was exposed, as an experiment, from five to ten seconds, in order to see what was the proper time for exposure.

"Mohammed, our black servant, brought the first slide into the tent to me. I poured the iron developer upon the plate, waiting breathlessly to see the result. At this moment my lamp went out. 'Light! Light!' I exclaimed; but no one heard me—every one had enough to do. I stretched my right hand out of the tent, holding the plate with the left, and fortunately grasped a small oil lamp, which I had placed ready for all emergencies, and now I saw the image of the sun appear upon the plate. The dark rim of the sun was surrounded by a series of peculiar prominences on one side, while on the other side appeared a singular horn—both phenomena perfectly analogous in both pictures. My delight was great, but there was no time for rejoicing; soon the second plate and, a minute later, the third plate were in my tent. 'The sun is emerging,' exclaimed Zencker. The total eclipse was over; but all this appeared as the work of a moment, so quickly had the time passed. The second plate showed under development only faint traces of an image, a passing veil of clouds had almost destroyed

the photographic action at the moment of exposure. The third plate showed again two successful views with protuberances on the outer rim.

"Rejoicing in this success, the plates were washed, fixed, varnished, and at once, although with very imperfect instruments, copies were taken on glass, and these, to avoid accident, were transmitted separately to Europe.

"Our extraordinary good fortune is apparent from the fact that, at a place distant only half a league from our station, nothing was seen of the total eclipse on account of the veil of clouds.

"We did not stay long at Aden after our chief object had been attained: in three days the steamer proceeded to Suez. Telescope, clockwork, and our heap of instruments and chemicals were quickly packed, placed on camels and conveyed to the harbour. On the 21st of August we bade adieu to the barren, rocky island, and started for Suez."

Aden was one of the points where the eclipse was first visible. As previously stated, England had also equipped a photographic expedition, which stationed itself at Guntoor in India. The eclipse was observed an hour later in India than at Aden. The same protuberances appeared in the Indian photographs as in those at Aden, but they present a very different form, which seems to show that these prominences are not compact bodies, but formations of a cloud-like nature; and this supposition was converted into certainty by Jansen's observations with the spectroscope, made simultaneously.

Jansen showed that in a total eclipse the protuberances display bright lines in the spectroscope. As this is the property of gaseous bodies only, the question as to

the nature of the protuberances was solved. Jansen determined at the same time the exact position of these bright lines, and discovered that the gaseous substance was glowing hot hydrogen. He subsequently made the discovery that an eclipse was by no means necessary in



Fig. 74.

order to detect the bright lines of the protuberances. They are seen on clear days if the slit of a spectroscope be directed on the sun's rim, and the changeable nature of these protuberances can every day be observed by the appearance and disappearance of these bright lines.

Zöllner of Leipzig even detected with the spectroscope a sudden burst of gas, also the sudden breaking away of gas clouds from their substratum, and their dispersion, all in the space of a few minutes.

We add a faithful copy of the Aden photographs, taken from Herr Schellen's excellent work on spectral analysis (published by Westermann at Brunswick). The



Fig. 75.

first view (Fig. 74) gives us the eastern rim of the sun; the western was covered by clouds. It is easy to recognize in it the large horn-like protuberance, which has an elevation of 184,000 miles, and gives an idea with what immense force masses of gas are projected from the surface of the sun. It shows, further, the remarkable

protuberance to the left, in which the masses of gas appear like powerful jets of flame driven sideways by a tempestuous wind; a light region surrounding the protuberances forms the glowing hot stratum of vapour permanently surrounding the rim, named chromosphere.



Fig. 76.

The second view presents only a series of point-like protuberances on the western rim of the sun, but these points are so large that our earth could almost find room in them. The eastern part of the sun was under the clouds during the taking of this view.

Finally, the third view gives a perfect representation of the total eclipse as it was observed in India. Besides the protuberances seen at Aden, there is another on the western rim of the sun, which was quite covered by clouds at Aden.

Photography has been latterly applied to the observa-



Fig. 77.

tion of total eclipses on a more magnificent scale. Thus, on the 7th of August, 1869, hundreds of photographers were actively employed in observing the total eclipse of the sun at Iowa, in North America, and more than thirty telescopes were set up to retain the phenomenon. By these observations, the question respecting the nature of the protuberances was finally set at rest, and the only question that remained related to the corona. By corona

is meant a kind of nimbus of white light surrounding the sun when totally eclipsed. Many observations of total eclipses have been undertaken to decide its nature. A very beautiful view of the corona was obtained by Whipple, at Shelbyville in Kentucky, August 7th, 1869. The feeble light of this phenomenon renders a much longer exposure necessary than in the case of the protuberances. At Shelbyville, the exposure for the corona lasted forty-two seconds, whereas five seconds sufficed to take the protuberances. Nor was the nature of the corona as yet determined.

In 1870 an English expedition, conducted by Lockyer, was sent to Catania to observe the corona, and the author accompanied it. Unfortunately, owing to the unfavourable weather, the observations were only partially successful. However, a detachment of the expedition, conducted by Brother, in Syracuse, succeeded in obtaining a good view of the corona, and we give a faithful woodcut (Fig. 77) copied from this photograph.

The black prominences round the sun's disc give the situation of the protuberances which were visible on the day of the eclipse. We call attention to the fact that they are not visible in the photograph of the corona. To take a view of the corona requires an exposure eight times as long as for the protuberances. During this long exposure the images of the protuberances received too much light, and have therefore become paler instead of brighter, so that their outline becomes confounded with the less bright parts.

Photography is applied to other important purposes in astronomy besides taking pictures of eclipses. Views of the sun are taken daily. The observation of centuries

has established that the sun is continually changing: spots appear, increase, and disappear. All these phenomena were at an earlier date explained as openings in the cloudy luminous atmosphere of the sun, which was supposed to surround its dark central mass. Now they are looked upon as immense whirlwinds, which rage in the atmosphere of the sun (see Schellen's "Spectral Analysis," page 200), or as cloud-like condensations. Their nature has not been perfectly ascertained. These sun-spots follow the revolution of the sun's body round its axis, and experience manifold changes during this time. It is only by means of these spots that the duration of the sun's revolution has been determined. Recent observations have established that the number of the spots increases and decreases periodically, and that this period is connected with the magnetic phenomena of our earth. These circumstances have led to a closer study of the spot formations, and photography has offered a valuable aid for this purpose. It gives at a particular moment a faithful view of the sun's surface, and photographs taken daily give us the most exact representation of the spots, their size and number. A comparison of the views during one month affords an instructive survey of the changes on the sun's surface, relating more faithfully than words the history of the central body of our planetary system. Lewis Rutherford, of New York, who has made valuable contributions to astronomical photography, has taken a great number of these views at the photographic observatory built at his own expense.

These views, taken on successive days, exhibit manifold groups of spots, often of considerable size; and the change in their form and position is thus accurately

recorded (the latter consequent upon the revolution of the sun). These impressions are not prepared, as were the pictures of the eclipse, in the principal focus of the telescope, but in an additional apparatus (Fig. 78) which



Fig. 73.

answers the purpose of a magnifying apparatus. This contains a small lens *L*, which projects on the ground glass *G* an enlarged image of the small representation of the sun *S* produced by the great lens *O*.

In this manner Rutherford obtains directly a picture of the sun about two inches in diameter. This enlarging apparatus is not to be recommended in the case of eclipses; for the brightness of the image produced by the great telescopic lens is materially weakened by the enlargement. When the image is twice the size, the weakening of the light is fourfold; when it is three times as great, the weakening is ninefold, and so on. In views of the unclouded sun this is of no consequence, for its light is so intense that it bears a considerable enlargement, and yet remains bright enough to give a view on a momentary exposure. The protuberances, however, give out much less light, and if their image were magnified they would become so faint that a longer exposure would be required than the duration of the eclipse.

The solution of other important astronomical problems has been attempted with the help of photography; for example, the production of pictures of the stars.

The object of such pictures is the representation of the constellations, or the relative position of the stars. It always has been one of the principal objects of astronomy to determine the position of the fixed stars. It may be thought that the catalogue of the stars is already completed, and that the matter is settled; but this is not the case. As far as photography can at present be applied, that is, to stars of the ninth magnitude, the catalogue is not complete. Moreover, the measurements of the past may require correction in consequence of improved methods.

The photographic process is of great importance for this purpose, because it offers advantages in the facility of its application and correctness of its results. Many readers may inquire why so much trouble is taken to determine with the greatest accuracy the positions of thousands and millions of fixed stars. The answer is that the fixed stars are not stationary as their name implies; nothing is stationary in nature, and hence such study is never at an end. No doubt the fixed stars change their position so slowly that the builders of the pyramids four thousand years ago beheld the constellations much as we do. It is only the finest astronomical measurements that show any change within a limited number of years. However, the study of the proper movement of the fixed stars has now begun, and requires very accurate measurements carried on for generations.

Another interesting point comes into consideration in connection with this subject. On the one hand, the fixed stars are not without movement; on the other, their distances from the earth are very various, the nearest being enormously great. The photographer who wishes

to take a graphic view of an object, will always try to take it from different points. Two views of a moderately remote object taken from two points only two inches apart, appear different to the eye, and produce, when viewed in a special manner, a stereoscopic effect. No distance on earth is great enough to give different pictures of the same constellation; nevertheless, within the space of one year we describe a circle round the sun having a diameter of 184 millions of miles, so that in half a year we are 184 millions of miles from our present position. This enormous distance is in certain cases just sufficient to show a change in the relative position of certain stars, though not to the naked eye. By this means the distance of the nearest fixed stars has been determined, amounting to billions of miles.

By careful comparative measurements of positions of neighbouring stars, continued for years and centuries, a change can be proved to exist, and the proper movement of the stars can be calculated. The distance of the stars can be deduced by carefully collating the yearly recurring changes in the positions of the stars. It is evident that photography, which affords the means of fixing these positions, must be of the greatest value for both these astronomical problems.

Photography of the stars was first introduced about twenty years ago by Professor Bond, of Cambridge, Massachusetts, but it was Mr. Lewis Rutherford, of New York, who perfected the method. He constructed a photographic objective of 11 inches diameter and about 13 feet focus. This objective shows a considerable focal difference; that is, the violet and blue rays have a different focus from the yellow and red. If a clear image of the star

is focussed, the sensitive plate would be adjusted to the focus of the yellow rays, and the focus of the chemically operative blue rays would fall beyond the sensitive plate, and an indistinct picture would result. The plate must therefore be adjusted to the focus of the blue rays; but this is not so easy to find. After it has been found approximately, it is corrected by taking different photographs of a star, changing the position of the plate each time. The point is determined at which the best and sharpest picture is obtained, and, by continual repetitions of the attempts, the chemically active focus of a lens of 13 feet focal length can be accurately determined to within $\frac{1}{150}$ of an inch. It is well known that all heavenly bodies have the same focus, on account of their great distance.

No photographic objective gives a correct picture with a large surface. Accordingly, to obtain the accuracy required by astronomy, the surface to be devoted to the image can only be very small, or about $1\frac{1}{2}$ degrees in diameter. Any remaining distortions are controlled and corrected by photographing a very correct scale, and comparing the picture with the original. A field of $1\frac{1}{2}$ degrees, or three times the moon's diameter, embraces the well-known constellation of the Pleiades.

Rutherford's telescope is arranged as in Fig. 73 (p. 169); it is moved by clockwork, so as to exactly follow the movement of the stars.

The views of large stars taken with it, after a short exposure, all appear as small round points which can only be seen through a magnifying glass. In the case of a long exposure their size depends on the more or less strong vibrations of the atmosphere, which occasion the

flickering of the stars. Stars of the ninth magnitude can be photographed with an exposure of eight minutes; the light of these stars is ten times weaker than that of the faintest which can be detected on a clear night by the naked eye, and their images are very small points. It would be difficult to distinguish these small points from dirt spots on the plate. To do this, Rutherford makes use of an ingenious device. He brings the telescope, after the first exposure of eight minutes, into a slightly different direction, and makes a second exposure of eight minutes, while the clockwork continues to operate, and moves the telescope correctly in this second direction.

In this manner two images are obtained of every star on the plate, closely adjacent; the distance and relative position being in all the same. These double images can be easily found on the plate and distinguished from accidental spots. If the telescope stops, it is evident that the images of the stars make a movement on the plate, the bright stars describing a line. This line is of great importance to determine the direction from east to west on the plate. For faint stars which leave no line a third exposure is necessary to determine this direction. This is done after the clockwork of the telescope has been stopped for some minutes.

Rutherford has already taken numerous views of the stars, and they will serve as important means of comparison, after the lapse of centuries, in order to discover what change has taken place in the position of the fixed stars.*

* Details respecting Rutherford's observatory are contained in the "Photographischen Mittheilungen," Jahrg. 1870. Berlin: Oppenheim.

But another heavenly body invites us specially to study it by the help of photography; that is, our nearest neighbour, the moon. The unassisted eye recognizes its uneven surface ("mountains in the moon") and the varying shades of its ground (moon spots). Its surface contains a thousand problems, appearing as a rigid, almost vitreous, waterless, airless waste.

Warren de la Rue has tried to take photographic pictures of this singular body, which is so near to our earth and yet so different; he succeeded in obtaining, with the help of a telescope, a small view of the moon, which he enlarged to 24 inches diameter with an enlarging apparatus (p. 94).

The moon gives out less light than the sun. It is therefore taken to the best advantage in the principal focus of the telescope. (See Fig. 72, p. 168.) In the most favourable case, three-quarters of a second suffices for exposure, but it is rare to obtain sharp negatives, owing to the disturbance of the atmosphere, and to obtain a sharp image of the moon is a test of patience. After Warren de la Rue, Rutherford is celebrated for his moon-pictures; his improved telescope, set up purposely for photographic purposes, gave a still sharper image of the moon than De la Rue's, and our frontispiece is a diminished copy of the enlarged picture of the moon from an original, for which we are indebted to Rutherford, forming a genuine map of the moon of no small importance to astronomy.

Some years ago Schmidt, at Athens, maintained that an extinct volcano observed by Mädler is no longer to be found, and he thereby proved the possibility of changes on the apparently rigid surface of the moon. If a

photograph of the moon's surface could have been taken forty years ago, when Mädler observed the volcano, we should now be certain about this point, which is still doubtful.

But the sun and its eclipses, the moon, and stars are not the only objects of astronomical photography. Its province extends further since the discovery of spectrum analysis.

When it was discovered that the wonderful lines intersecting the sun's spectrum (see chap. vii. p. 62) were occasioned by glowing substances of different kinds, and that each element shows invariably the same lines, so that the presence of certain spectral lines establishes the presence of certain elements, it became necessary to possess an exact map of the countless lines of the solar spectrum. Then, by comparing this map with the spectrum of a flame or of a star, it could be at once seen what substances give these lines. Kirchhoff, one of the discoverers of spectrum analysis, and Angström have prepared such maps of the solar spectrum. Their labour would have been materially simplified had Rutherford published his photograph of the spectrum a year earlier.

Rutherford's photograph only shows the lines of the chemically active part of the spectrum—from green to violet—but it does this with wonderful clearness. Many lines that appear faint to the naked eye show themselves strong and sharp in the picture; nay, lines are discovered in the photograph of the spectrum which Kirchhoff did not see at all in the spectrum itself.

The causes of this phenomenon may be twofold: either the eye is not sensitive to certain rays of light—as we know it is not influenced by the ultra-violet rays,

which have a strong photographic effect,—or it is possible that changes take place in the sun: that at certain times fresh substances come to its surface, and thereby new lines become apparent.

The photograph of the spectrum may be taken with the aid of an ordinary spectroscope, seen in Fig. 79. This consists of a tube *A*, which has a fine slit *F*, through which the light penetrates, and at the other end a lens, which makes all the rays from the slit parallel, and conducts them to the prism *P*. The rays are then refracted



Fig. 79.

and pass into the tube *B*, and can be observed through its narrower end. If the object is to photograph the spectrum thus seen, a photographic camera is placed light-tight on the tube *B*, its eye-piece is drawn a little out, and then the image of the spectrum appears upon the ground-glass screen.

Attempts have been made to solve other important problems by the help of photography. Thus, Dr. Zencker hoped to be able to trace the path of shooting stars by means of it. Unfortunately, these were found to give out too little light to produce, while they lasted, an impression on the photographic plate.

The transit of Venus affords a new and grand problem for photography.

In determining the distance of heavenly bodies, the diameter of the earth's orbit is taken as a base line; therefore the knowledge of the exact length of this base is assumed. Now, this amount has only hitherto been determined by approximation, and is in round numbers one hundred and eighty millions of miles.

Many efforts have been made to determine this distance more accurately. It is, however, a problem of great difficulty. Let it be conceived that there are at two opposite points of the earth, a and b (Fig. 80), two observers who look with telescopes at a star x, and measure the angles which the rays $x\ a$, $x\ b$ make with the line $a\ b$; it can be determined from both angles and the line $a\ b$ (which is easily found) what the distance of the star is from a or b. This is the trigonometrical method, and it gives reliable results, if the distance of the star is not too great; thus, for example, the distance of the moon, which is about ten of the earth's diameters, is easily ascertained. If the star to be measured is too remote, the rays $a\ x$ and $b\ x$ are nearly parallel, no difference exists between the two



Fig. 80.

angles at a and b, and the trigonometrical method is useless. This is the case with the sun, which is ninety-five millions of miles from the earth. We can therefore only ascertain its distance by indirect methods.

According to a law discovered by the celebrated astronomer Kepler, the squares of the periods of revolution of the planets vary as the cubes of their distances from the sun. Thus, if the period of the earth's revolution is U, and that of Venus u, the distance of the earth E, that of Venus e, according to this law,

$$U^2 : u^2 = E^3 : e^3.$$

If the cube root is extracted from both we have—

$$\sqrt[3]{U^2} : \sqrt[3]{u^2} = E : e, \text{ hence,}$$

$$\sqrt[3]{U^2} - \sqrt[3]{u^2} : \sqrt[3]{u^2} = E - e : e.$$

But $E - e$ is the distance between the earth and Venus. When this has been determined, three terms of the proportion are known; for the periods of the revolutions of Venus and the earth are accurately known. Then, by simple rule of three, the fourth term e can be found; that is, the distance of Venus from the sun. If to this is added the distance of the earth from Venus, we obtain the distance of the earth from the sun, which was required.

Thus the determination of our distance from the sun depends on that of our distance from Venus, which must be taken at the moment when Venus is between the earth and the sun. But Venus is only visible at the moment when it is between the sun's disc and the earth. This is only exceptionally the case—twice in every century—and then it appears as a small black point on the sun's disc, which, however, continually changes place,

on account of the earth's movement and its own. This circumstance renders simultaneous measurements at two different and remote points of the earth very difficult, and therefore the idea has been entertained of using photography as an auxiliary. If by its help, and in the manner described above, a sun picture is taken during the transit of Venus, the distance of Venus from the sun's centre can be easily measured upon it. The centre of the sun is a fixed point which can be assumed to be stationary.

If the earth is supposed to be at *E* (Fig. 81), Venus at *V*, and the sun at *S*, the observer at *a* will see Venus below the centre of the sun, while an observer at *b* will see Venus above it. Accordingly, Venus will present a different position to the sun's centre on photographs taken at various points of the earth.

Fig. 81.

Now, the position of the centre of the sun is very accurately known. The sun's diameter subtends an angle of about 30 minutes, so that if divided into 30 parts, each part would represent an angle of one minute. It is only necessary therefore to measure how many of such parts Venus is distant from the sun's centre, to find at once the angular distance of Venus from this point or *m a V*. If this angle is subtracted from the angle which the line *a b* makes with the direction of the sun's centre *m a b*, the remainder will give the angle *V a b* which Venus makes with the line *a b*, which gives all the data necessary to calculate the

distance of Venus, and, from that, the distance of the central body which forms the foundation and base of all astronomical measurements.*

The determination of this angle by photography is of special value, as this measurement can easily be made at any convenient time, whereas direct measurements can only be made while the phenomenon is visible, and hence many errors are introduced in the excitement of the moment. Measurements of this kind require apparatus of the most accurate description, and the adoption of many precautions; therefore preliminary experiments have been already commenced to determine the degree of accuracy which a measurement by means of photography admits. If these preliminary experiments give a favourable result, numerous photographic expeditions will be sent out to observe the transit of Venus. Germany proposes to occupy five stations: Tschifu in China, Muscat on the Persian Gulf, Kerguelen's Land, and the Auckland Islands. Besides these, England, France, Russia, and America are equipping photographical expeditions which will occupy various points, and thus we may hope that though some stations may be visited by unfavourable weather, still numerous plates will be obtained by means of which this great astronomical problem can be solved.

* Our space does not permit us to enter into the details of the method of determining the solar parallax; it is only our purpose to give a plain intelligible statement of the first principles of the problem. Those who are specially interested in the subject are referred to "The Transit of Venus over the Sun," by Dr. Schorr. Brunswick: Vieweg. 1873.

Section V.—The Application of Photography to the Observation of Scientific Instruments.

The Thermometer and Barometer—Neumeyer's Apparatus for determining the Depth of the Sea.

Meteorological observations require a daily reading of the barometer and thermometer. To economize this reading, and yet to receive a perfectly safe register of the state of the thermometer and barometer at each minute, photography has been turned to account. Let the reader imagine behind the tube of a thermometer *R* (Fig. 82) or barometer a drum, which revolves round its axis *a* by means of clockwork. Let sensitive paper be wrapped round this drum, and the whole be enclosed in a cylinder *S*, which has only a small slit behind the thermometer through which the light can penetrate. The upper part of the thermometer will let the light through, while the thread of quicksilver will stop the light. Therefore the strip of paper above the quicksilver will blacken, and the limit of the blackening on the paper will rise and fall with the mercury. Now the time can be marked beforehand on the paper. As the drum revolves once in twenty-four hours, the strip of paper need only be divided perpendicularly into twenty-four parts, and the first part be moved opposite the thermometer directly the clock strikes twelve, after which



Fig. 82.

the whole may be allowed to revolve. Thus the blackened strip will show the height of the thermometer at all times of the day. In the same manner, the height of the barometer can be registered by photography.

Professor Neumeyer has latterly employed a similar instrument to determine the temperature in the depths of the sea. As there is no light producing chemical action at those depths, Neumeyer sends down a light-producing apparatus. This consists of a galvanic battery, and a Giesler's tube; that is, a tube in which very attenuated nitrogen gas is enclosed, and through which the electric current is passed. The tube then gives out a faint light. But this faint light has a powerful chemical action, because it contains many of the invisible ultra-violet rays (see p. 64), and in three minutes it effects the blackening of the paper. Neumeyer also attempts to determine with his apparatus the direction of the oceanic currents. For this purpose the apparatus has attached a vane like that of a weathercock, which can move the instrument in any direction whilst suspended. If any currents exist, they will turn the apparatus so that the vane is parallel to their direction. A magnetic needle is enclosed in the apparatus, and moves over a disc of sensitive paper; this magnetic needle points, of course, to the north, and the luminous tube above it fixes its position on the sensitive paper, which is firmly fastened to the box. Therefore, it can be easily seen what situation the apparatus has assumed with reference to the magnetic needle—that is, the north.

Section VI.—Photography and Medical Research.

Photographs of the Interior of the Eye, the Ear, etc.—Stein's Heliopictor.

Medical science has already made great use of photography, both as a means of obtaining pictures of interesting anatomical preparations and phenomena of short duration, and in giving exact anatomical views of the different organs. The interior of living organs has been disclosed by ophthalmoscopes, otoscopes, and laryngoscopes, and the image seen by the eye with these instruments has been successfully photographed. Dr. Stein, of Frankfort-on-the-Maine, has done good service in this branch, not only as a practical photographer, but also by the construction of suitable apparatus. It would exceed the limits of this book to describe all the apparatus necessary for this purpose. We shall content ourselves with the description of one, that for taking the interior of the ear.

The apparatus (Fig. 83) consists of three parts: 1st, the ear-funnel *A*; 2nd, the illuminating apparatus *B*; 3rd, the photographic apparatus *D*, with the lenses *C*. These parts are placed together, as may be seen in the accompanying diagram. The instrument is fastened by a ball and socket joint to a suitable stand, in order to give it the proper direction, according to the position of the sun. The ear-funnel *A* is a conical tube about $1\frac{1}{2}$ inches in length, to push aside the small hairs which interrupt the view; it is made of vulcanized india-rubber. The illuminating apparatus *B*, which is easily closed by a cover at *a d*, consists of two metal tubes, soldered to-

gether at a right angle at *b c*, of which one is provided with parallel, the other with curved sides. At the place where the two tubes unite is a perforated metallic mirror (*e g f*), inclined at an angle of 45°.

The photographic apparatus consists of a double objective *C* and a small camera, two inches deep. The ground-glass screen *X*, and the dark slide *Y*, are fitted in a frame *D*, easily moved. A plano-convex lens is placed at *h*, between the objective and the illuminating apparatus. According to the position of the sun, bright cloud, or any other source of light, the apparatus *B* can



Fig. 83.

be moved by turning round on its axis; so that, in conjunction with the joint of the stand, the apparatus can be turned easily and steadily in all directions.

The rays which penetrate into the tube *B* are thrown by the perforated plane mirror *e f* through *A* on the drum of the ear. Reflected thence, they pass at *g* the perforated plane mirror, and the image of the drum of the ear is thrown by the lenses on the ground-glass slide *n o*. The image is focussed either by shifting the objective by means of the screw at *p*, or by moving the lens at *h*, according as an enlarged image or one of life-size is desired.

During the photographic process, an assistant must pull the ear muscle backwards and upwards, in order to give a proper direction to the funnel in the tortuous aperture of the ear. The exposure in the sunlight, if a good collodion is employed, lasts half a second; under bright clouds on a clear day, from five to ten seconds, according to the intensity of the light. The exposure is effected by opening and closing a shutter at *c d*.

In order to render photography more accessible to physicians and scientific investigators, Dr. Stein has constructed an ingenious instrument called the "heliopictor," with which wet-plate photographs can be taken without any dark room. The heliopictor is a kind of dark slide which can be placed at the back of any camera. Dubroni, of Paris, first constructed such developing boxes. This box, a section of which is given in the diagram below, contains a glass vessel *K*, into which a silver solution can be poured through a stop-cock, not visible in the figure. The glass plate to be prepared is coated with collodion, then brought through the door *T* into the box, and placed on the aperture *O* of the vessel *K*. The door *T* is then closed, and the plate is thus pressed by the spring *a* watertight against *K*. After this, the box is turned over to the right, the silver solution flows over the plate, and renders it sensitive. The course of this operation may be observed through a yellow glass slide *S*, which admits no chemical light. After the plate has been properly sensitized, the box is again placed upright, and brought into the camera in place of the ground-glass



Fig 84.

slide, *S* is drawn up, and thus the plate exposed. Then the silver solution is drawn off through a stopcock, and a solution of green vitriol poured in instead; by tilting the box this flows over the plate and develops the picture. The development may be watched through the yellow slide *S*: when it is completed, the picture is taken out and fixed.

Stein has improved his developing box by substituting a vulcanized india-rubber vessel, easily taken out and cleaned, for the glass receiver. He also introduced the method of filling and emptying the receiver by means of a stopcock, Dubroni having employed pipettes. Both apparatus are described in detail in the "Photographischen Mittheilungen," Jahrgang X. Nr. 117, 118.

Section VII.—Photography and the Microscope.

On Microscopes—Taking Microscopic Views—Their Application.

Nowhere has photography shown itself a more brilliant auxiliary to or substitute for the art of drawing than in the representation of microscopic objects. This was indeed attempted in the earliest days of photography, for Wedgwood and Davy attempted to fix the images of the solar microscope on sensitive silver paper. This solar microscope seemed, in fact, to be specially adapted for photographic purposes. Its construction is shown in Fig. 85. The microscopic object is inserted at *m*, and is either a drop of liquid upon a glass plate, or a small solid body compressed between two thin glass plates.

The small lens *L* projects an enlarged image of this

minute object on an opposite screen, or a white wall, exactly as shown in the following figure.

The rackwork at *D* serves to regulate the distance of the lens from the object *m*, and thereby to focus the object sharply upon the screen. *E* is a diaphragm by which the ragged edge of the round image is cut off. The tube *B C* contains the lenses which concentrate the light. Each considerable enlargement diminishes the light of the picture materially; if it is enlarged three times, the light is diminished to $\frac{1}{9}$; if enlarged fourfold,



Fig. 85.

to $\frac{1}{16}$; if fivefold, to $\frac{1}{25}$; if a hundredfold, to $\frac{1}{10000}$. With such a diminution of brightness the eye would not see anything, if care were not given to throw an intense light on the object. The system of lenses contained in the tube *B C* answers this purpose. This concentrates the sun's rays, which are reflected by the mirror *M* into the tube *B*, on the microscopic object; and the latter becomes in this manner so intensely illuminated that it admits of any amount of enlargement. The room in

which the instrument is placed is dark; accordingly, all the conditions are present that enable proper photographs to be taken. All that is requisite is to expose a sensitive plate in the place of the image



Fig. 86.

Few persons, however, possess a solar microscope. For ordinary investigations a microscope is used similar to that in the accompanying figure. It contains at *o* a system of lenses, which projects an enlarged image *S R* (Fig 88) of the small object *r s*. This is viewed through the eye-piece *c d* (Fig. 88), which is placed at *n* (Fig. 87), and again magnifies the image *S R*, so that a still greater image *S′ R′* (Fig. 88) is produced.



Fig. 87.

This is seen directly by the eye of the observer. The necessary light is thrown on the object by the help of a concave mirror *s s′* (Fig. 87).

To produce photographs with the help of such a microscope, a photographic camera, properly supported, can be placed directly on the eye-piece *n* (Fig. 87). This camera does not require a lens like those previously described, p. 88. The eye-piece of the microscope serves this pur-

pose, and is inserted through a light-tight sleeve into an opening in the camera. If, now, the tube h is raised, an enlarged image of the object at $S\,R$ will appear on the ground-glass screen of the camera, and can be easily photographed.

It is necessary in doing this that all light not emitted from the object should be excluded. If the mirror $s\ s'$ (Fig. 87) throws light on the object, many rays pass beside it, fall on the lenses, and occasion reflections that materially disturb the clearness of the image. In this case it is advantageous to insert a system of lenses between the mirror $s\ s'$ and the object, concentrating all the rays on the object.



Fig. 88.

Instead of sunlight, an artificial light is sometimes used; for example, the electric or magnesium light, thus making the observer independent of the weather. The beauty of the micro-photograph depends essentially on the beauty of the preparation to be photographed. This must be so arranged that it shows perfectly clearly all characteristic parts; all disturbing accessories, dust and so on, must be removed, for they are equally magnified with the object. A skilful preparer is therefore necessary for successful micro-photography, which also depends on the excellence of the instrument, its proper arrangement, and the choice of the proper exposure. It is important in a microscope for this purpose that the lenses should be corrected for the chemically active rays. (See pp. 185, 186.)

Excellent results have been achieved in micro-photography by Neyt at Ghent, Girard and Lackerbauer in Paris, Fritzsch and Kellner at Berlin, and Woodward in America.*

Microscopic photography is of the very greatest use for preparing pictures of anatomical preparations which change quickly, and of such chemical substances as undergo rapid decomposition, also of the microscopic crystals, which are enclosed in many kinds of stones, and show themselves clearly in thin polished plates. In the photographs the angles of these crystals can be easily measured with the help of a protractor, and from them the nature of the crystals may be inferred. Professor Gustavus Rose, in his treatise on meteorites, has reproduced in steel engravings many micro-photographs of this kind, taken by the author.

Section VIII.—Microscopic Photographs and the Photographic Pigeon Post.

Nature of Microscopic Photographs—Their Importance for Libraries—Employment of the Pigeon Post.

Some years ago jewellery and toys were offered for sale in Paris, containing small lenses in place of jewels. If these were held before the eye, small transparent pictures, some of them portraits, and others writings, were visible. These little pictures were the so-called microscopic photographs on glass. Such a picture is by no means the representation of a microscopic object, but of a large-sized object, only it is so small that a micro-

* Full details are given in "Die Photographie, als Hülfsmittel mikroskopischer Forschung," by Moitessier and Bennecke. Brunswick. Vieweg.

scope is required to see it. The production of these photographs does not differ from that of others; it only requires an instrument forming images of microscopic minuteness, and this is effected by employing small lenses of very short focal length. In using these a direct photograph is not taken, but in the first place a photographic negative is prepared with an ordinary camera from the object chosen; after this, with the help of the small lens, microscopic positives on glass are obtained with the ordinary collodion process. These are then cut, and a small lens fastened on them, and then they are mounted in metal. Such pictures are in themselves little else than toys, which have, however, been put to a bad purpose, for indecent photographs have been thus placed in the hands of unsuspecting persons—a fact that speedily brought this branch of photography into discredit. But there are circumstances in which such microscopic photographs can be of extraordinary value. Simpson in England has called attention to the fact that, by the help of photography, the contents of whole folios can be concentrated within a few square inches, and that the substance of books filling entire halls, when reduced by microscopic photography, can be brought within the compass of a single drawer—a circumstance which, with the enormous increase of material that has to be stored by our libraries, may be of importance. Of course, either a microscope or a magic lantern would be required to read such microscopic works.

Hitherto photography has not been applied to this purpose, though Scamoni's heliographic process, described further on, would considerably facilitate the creation of such microscopic libraries. Microscopic photographs,

however, have obtained great importance in promoting pigeon despatches. During the siege of Paris in 1870, the blockaded city held communication with the world outside by means of balloons and carrier pigeons. The first mode of communication was used almost exclusively for political objects; the second only admitted the transmission of very light letters. Letters, however condensed, could scarcely have been sent more than two or three at a time by a pigeon. In this case, microscopic photography presented a valuable means of concentrating many pages on a collodion film of only one square inch, and so light that more than a dozen packed in a quill could be sent by one pigeon. Dagron, at Paris, who first prepared microscopic photographs, also was the first to prepare these pigeon despatches. All the correspondence which had to be diminished was first set up in type, and printed together on a folio page. A microscopic photograph was made of this folio page, contained in about the space of $1\frac{1}{2}$ square inches. The collodion film of the picture was then removed from the glass by pouring a collodion over it which contained castor oil in solution. The collodion soon dries, and can then be separated from the glass, carrying the film of the picture with it. Such films contained in some cases as many as 1500 despatches. At the place of arrival the films were unrolled and then enlarged by the help of a magic lantern; a number of writers thereupon set to work to copy the enlarged despatches, and ultimately forwarded them to their respective addresses. Thus Paris corresponded, by the aid of photography, for six months with the outer world, and even poor persons were able to let their relatives know that they still lived.

Section IX.—Pyro-Photography.

Pictures on Porcelain—Their Production by Photography—Grüne's Method—Its Application for the Decoration of Glass and Porcelain.

An ordinary photograph is, as paper, very combustible, and exposed to injury from corrosive substances. Encaustic images on porcelain and glass do not participate in this exposure to injury, and therefore attempts have been made to prepare fireproof photographs, especially for the decoration of glass and porcelain. Success has crowned these efforts in several cases. One of the simplest processes is that of W. Grüne at Berlin.

Grüne found that the collodion image—which, as we have seen (p. 109), consists of minute parts of silver—is capable of manifold changes, and that, moreover, it is easily transferable, by means of the elastic collodion film, to other bodies. The film, with the picture, can be removed from the glass, placed in different solutions, and then transferred to curved surfaces, etc. If the collodion picture is placed in a metallic solution, a chemical change ensues. Assuming the solution to contain chloride of gold, then the chlorine passes over to the silver, of which the picture consists, chloride of silver is formed, and metallic gold is precipitated as a fine blue powder on the picture. Thus a gold picture is obtained.

With certain precautions this can be transferred to and burnt into porcelain. By this means a dull image is obtained, which can be rendered brilliant by polishing. Grüne has employed this method to produce gold ornaments on glass and porcelain. Drawings and patterns of various kinds are photographed; the image obtained is

changed into one of gold, then burnt in, and thus the most beautiful and complicated decorations can be produced without the assistance of the porcelain painter.

If a silver picture be plunged into a solution of platinum instead of a solution of gold, a platinum image is obtained. This assumes a black colour on being burnt into the porcelain. In this manner black portraits, landscapes, etc., have been produced on porcelain.

Pictures of this kind can be prepared in other colours than black. For example, if the photograph is dipped in a combined solution of gold and platinum, the gold and platinum are precipitated on the picture. The image thus obtained, if burnt in, presents a very agreeable violet tint.

Solutions of uranium, of iron, and of manganese effect precipitates on a collodion picture, modifying its colour, and, when burnt in, produce different brownish or blackish tints. We shall see, later on, that there are other means of producing such pyro-photographs. Details will be found in the chapter on the photo-chemistry of the chromium compounds.

Section X.—Magic Photography.

Invisible Photographs—Their Development—Magic Pictures and Magic Cigar Holders.

Closely connected with Grüne's process for producing pictures on porcelain, is what is called magic photography. A few years ago small sheets of white paper were offered for sale which, on being covered with blotting-paper and sprinkled with water, displayed an image as if by magic. The white sheets of paper, to all appearance a blank, were photographs which had been bleached

by immersion in a solution of chloride of mercury. If a photograph not containing gold—all the usual paper photographs contain gold—be immersed in a solution of chloride of mercury, a part of the chlorine passes over to the silver of the picture, and changes the brown silver particles into white chloride of silver, which is invisible on the white paper. At the same time subchloride of mercury (mercurous chloride), which contains less chlorine than the chloride of mercury, is precipitated. This body is also white, and therefore invisible on the white paper. Now, there are several substances which colour this white subchloride of mercury black. Among these are ammonia and hypo-sulphite of soda. If, therefore, the invisible picture is moistened with one of these substances, it is coloured black and becomes visible. In the magic photographs formerly sold there was hypo-sulphite of sodium in the blotting-paper; this was dissolved on moistening the paper, the solution penetrated to the picture and made it visible.

Quite a different kind of magic photograph was offered for sale some years later—the magic cigar-holders. These contained a small sheet of paper between the cigar and the mouthpiece, which was exposed to the action of the cigar smoke; with continued smoking an image became visible on the sheet of paper, which contained a magic photograph of the kind described above. The image was brought out by the vapour of ammonia which is contained in the smoke, and which has also the property of colouring the magic photographs black.

The magic photographs of recent times were introduced at Berlin by Grüne, but their principle was known before, as J. Herschel had produced similar ones in 1840.

Section XI.—Scamoni's Heliographic Process.

Defects of the Silver Positive Process—Relief of the Photographic Negative—Impress of the same on Copper.

It was stated at an earlier page, that the time required to produce photographic positives formed a serious defect in the process. Every picture that has to be printed from a negative must have a longer or shorter exposure to the light, and the worse the light, the longer the time required. This is of no moment with a dozen portraits, but if hundreds or thousands are to be prepared, time is of consequence.

Another disadvantage in the silver print is its high price and doubtful durability. Attempts have been made, since the discovery of photography, to overcome these defects by combining it with printing-press processes—lithography or metal-plate printing. The ordinary process of printing from a metal plate is as follows. The drawing is engraved upon a copper or steel plate; this is covered with engraver's ink, the ink penetrates into the incisions, and under a heavy press passes over to the paper, thus forming the engraving. Impressions of this kind can be made in a short time in great quantities, without the help of light, and without employing expensive salts of silver. We showed in the first chapter (p. 10) that an incised drawing on a metal plate can be made with the help of photography by coating it with asphalt. But the same object can be attained in other ways; and one of the most original is that of Herr G. Scamoni, at St. Petersburg, the able heliographer of the Russian Imperial Office, for the preparation of State papers.

He observed that an ordinary photographic negative does not form a plane surface, but appears in relief; the transparent places—shadows—being deeper than the opaque. But the difference is very slight. Scamoni tried to increase it by treating the freshly taken and developed picture with pyrogallic acid and solution of silver. In this manner fresh silver was precipitated on the picture, which has the property of attracting and retaining silver separated chemically. The relief was considerably increased by this strengthening process. It can be augmented by a treatment with solutions of chloride of mercury and iodide of potassium, which transform the metallic silver into more bulky compounds. A relief was ultimately obtained nearly as high as the incisions of an engraved plate are deep. If, now, a collodion positive be taken of a negative from a linear drawing, and treated as above described, we have all the requisites for producing from it an engraved copper plate. The relief-like photographic plate is brought into a galvano-plastic or electrotype apparatus, of which we shall speak further on. This produces on the plate a coherent copper precipitate, which is in low relief where the plate shows high relief; that is, where there are strokes or outlines. Thus a copper plate is obtained from which impressions can be taken as well as from one that has been engraved. This process is now used to reproduce drawings like copper plate.

Maps are prepared in this manner, in which the original can be photographically enlarged or diminished; also writings on an enlarged and diminished scale. Scamoni has thus reduced a page of the illustrated journal, "Ueber Land und Meer," to sheets of one inch in width, on which the print is perfectly legible through

the microscope. Feats of this kind are not mere play, but they have a great importance for the preparation of paper money and for libraries, as we showed at pp. 11 and 205.

Section XII.—Photography and Jurisprudence.

Photography as a Means of Identification—Photographs of Criminals, of Railway Accidents, Fires, Documents, etc.

The application of photography to jurisprudence is of great interest. The faithful likeness of a man, or of an object, makes their recognition more certain than the most circumstantial description in words; and photography gives us such likenesses. Accordingly, repeated attempts have been made to utilize it as a means of identification. This was first attempted in 1865, when the season tickets for the photographic exhibition at Berlin contained the portrait of the holder, that they might not be transferred. This plan is now adopted in the season tickets of the Zoological Gardens at Berlin. It is still more important for the recognition of criminals. Old offenders are now photographed in prisons, partly as a means of recapture in case of escape, partly to detect them in case they should be again brought in under a false name.

Justizrath Odebrecht, in a treatise on jurisprudence, recommends that photographs should be taken of bodies found dead or, in case of murder, of the victim and the surroundings, for the information of judges. This has been repeatedly done. Further, the scene of a railway accident, buildings that have been destroyed by fire or storms, are photographed for the information of railway

and insurance companies, or of the legal authorities. Photography is of especial use for this purpose since the pictures may be completed within a few minutes, and made even during the repairs. It is also of value in jurisprudence for detecting forgeries. Very frequently forged cheques are photographed in order to send a copy for the information of those interested. Stolen and recovered articles are also often photographed to bring them to the notice of the proprietor. In many large cities the police cause pickpockets and sharpers to be photographed, and show an album of this kind to persons who have been robbed.

Section XIII.—Photography, Industry, and Art.

Photography as a Means of Artistic Culture—Extension of the Art of Drawing through Photography—Pattern Cards—Building Plans.

We have already laid stress upon the importance of photography as a means of reproducing works of art. It makes every work of art accessible to persons of slender means, and therefore it has become as important an auxiliary for popular culture in the province of art as the printing-press is for science.

Photography is equally important in those branches of industry in which accurate plans are indispensable; for example, architecture and the construction of machinery. In their case photography forms an addition to the art of drawing, effecting in a few minutes what the draughtsman could only accomplish in several hours or days, and copying with a faithfulness to which no draughtsman could attain. In connection with this subject we have already described, in our third chapter,

the technical importance of the *lichtpaus*, or new Talbot-type process. It is the easiest kind of photography, but it only gives copies of the size of the original; however, the negative process allows an enlarged or diminished copy to be taken of every drawing, according to option. Photography is already very generally used for these reproductions. It is equally important for taking views direct from nature, be they machines or parts of machines, buildings or parts of buildings. Pictures of this kind present not only a graphic image, but they serve for instruction and demonstration in lectures. The photograph of a house, of which the length, depth, and height are known, supplies sufficient data for the dimension of any part of it if the perspective be taken into consideration. Pictures on a small scale are commonly sent out as specimen cards. Iron foundries, manufactories of bronzes and of porcelain frequently issue price lists with photographic illustrations, which are multiplied from negatives of originals by the Albert-type process. (See the following chapter.)

Further, an original application of photography has been made by architects who are at a distance from a building under their direction. They cause photographs to be taken every week, giving them a clear picture of the progress of the building. We have already hinted at the services that photography can render in the manufacture of porcelain, and further in combination with the multiplying arts. We shall learn more on this subject in the following chapter.

CHAPTER XV.

PHOTOGRAPHY WITH CHROMIUM COMPOUNDS.

We have given a full account, in the first part of our book, of the chemical and physical principles of photography with salts of silver, and of its application to art, science, life, and industry.

Numerous attempts have been made to substitute other sensitive materials for the expensive salts of silver, and some of these attempts have been crowned with success. It is true that no substance has been hitherto found permitting a negative to be prepared in the camera as easily as iodide of silver. For the production of camera pictures from nature, we have no substitutes for iodide and bromide of silver. But positives from negatives already existing can be successfully produced, not only by the help of salts of silver, but also of other metallic combinations. The results obtained are indeed inferior in beauty to the silver pictures, but we shall see, later on, that they admit of multiplication in the printing-press without the help of light. We shall now describe the most important of these processes.

Section I.—Combinations of Chromium.

Oxides (Combinations of Chromium with Oxygen)—Salts of Chromium—Chromic Acid—Chromic Acid Salts in the Light—Ponton's Discoveries.

A black mineral called chrome iron ore occurs in nature, especially in Sweden and America. If this is fused with carbonate and nitrate of potash, a beautiful orange-red salt is formed, which dissolves in water and readily crystallizes on evaporation. This orange-red salt is bichromate of potash. It consists, as implied by the name, of chromic acid and potash. The latter is the chief component part of the soap-boiler's ley; the former is a combination of a metal, like iron, with oxygen. Chromium and oxygen combine together in several proportions, thus:

28 parts chromium with 8 parts oxygen form protoxide of chromium.
28 „ „ „ 12 „ „ „ sesquioxide of chromium.
28 „ „ „ 16 „ „ „ dioxide of chromium.
28 „ „ „ 24 „ „ „ chromic acid.

The last combination, chromic acid, is the best known of all. It may be prepared by adding sulphuric acid to a solution of chromate of potash: it crystallizes in red needles, which readily part with their oxygen. Thus alcohol, dropped upon chromic acid, takes fire; the chromic acid instantaneously gives up part of its oxygen to the alcohol, and is changed into a green substance, sesquioxide of chromium. The sesquioxide of chromium forms salts with acids; for example, sulphate of chromium. This unites again readily with sulphate of potash to form a double salt, which is known by the name of chrome alum, and is sold crystallized in very beautiful dark

violet octahedra. It is employed in dyeing, together with chromate of potash.

If chromate of potash be mixed with a solution of protosulphate of iron (green vitriol), a brown precipitate of peroxide of chromium is formed, the iron salt having removed a part of the oxygen from the chromate. This is often formed by the action of substances absorbing oxygen on chromic acid or its salts.

Chromic acid is of special interest to us, because both it and its salts are sensitive to light. Neither pure chromic acid, nor chromate of potash, are changed by light; they can be exposed for years to the sunlight without any decomposition being perceived. But as soon as a body is present that can unite with oxygen—for example, wood-fibre, paper, etc.—the light immediately produces its effect. This fact was published in the same year as the discovery of photography, in 1839, by Mungo Ponton, in the "New Philosophical Journal." He writes:—



Fig. 89.

"Paper immersed in bichromate of potash is powerfully and rapidly acted upon by the sun's rays. . . . . When an object is laid in the usual way on this paper, the portion exposed to the light speedily becomes tawny, passing more or less into a deep orange, according to the strength of the solution and the intensity of the light. The portion covered by the object retains the original bright yellow tint which it had before exposure, and the object is thus represented yellow upon an orange ground, there being several grada-

tions of shade or tint according to the greater or less degree of transparency in the different parts of the object.

"In this state, of course, the drawing, though very beautiful, is evanescent. To fix it, all that is required is careful immersion in water, when it will be found that those portions of the salt which have not been acted on by the light are readily dissolved out, while those which have been exposed to the light are completely fixed on the paper. By this second process the object is obtained white upon an orange ground, and quite permanent. If exposed for many hours together to strong sunshine, the colour of the ground is apt to lose in depth, but not more so than most other colouring matters."

It appears that Ponton made experiments similar to those of Talbot, in the first period of silver photography. Perhaps he also copied leaves (see p. 5). The copies which are produced in this manner on chromate of potash are, however, immeasurably fainter than the copies on silvered paper.

They may be easily prepared by exposing under dried leaves, a drawing, or a negative in a printing frame, pieces of paper which have been soaked in a solution of chromate of potash for about a minute, and then hung up to dry in the dark or by lamplight.

The chromic acid is then reduced to brown peroxide of chromium, but if the exposure lasts very long the reducing process goes further, and a green oxide of chromium is formed. In this case the picture appears fainter.

Ponton's experiment remained a mere curiosity until the inventor of photography on paper containing silver

salts discovered another property of chromate of potash, which led to the most extensive applications.

This property consists in the action of the combinations of chromium on glue.

Section II.—Heliography with Salts of Chromium.

Properties of Gelatine—Bichromate of Potassium and Glue—Talbot's Discovery—Effects of Light on the Solubility of Glue—Photographic Steel Engraving—Pretsch's Photogalvanography—Printing in High and Low Relief—Importance of the Former—Difficulty of producing Half-tones by the Heliographic Method.

Glue in its purest form, known by the name of gelatine, is insoluble in cold water, but it absorbs cold water like a sponge, and thereby swells. If it is warmed with water, it dissolves; but on cooling the solution solidifies to a jelly. This property is used to thicken soups. If to the warmed solution of glue be added alum, or a salt of the oxide of chromium, or chrome alum, the glue becomes insoluble in water, and forms a precipitate. On this is based the well-known system of white tanning; for in the tanning of a piece of leather the alum combines with the gelatine contained in the leather, and this becomes thereby insoluble, and at the same time durable.

Bichromate of potash and glue can be dissolved together in warm water in the dark, without the glue suffering any change from the chromate. If a plate or a sheet of paper be covered with such a solution of gelatine and bichromate of potash, and the film be allowed to dry, it becomes firm, and yet remains soluble in water as long as it is kept in the dark. But as soon as the film is exposed to the light, the bichromate of potash is reduced to oxide

of chromium, and this tans the film of gelatine; that is, makes it insoluble in water.

This observation was made by Fox Talbot in 1852, and, as a careful observer, he knew directly how to turn it to account. He coated a steel plate with a solution of chromate and gelatine, let it dry in the dark, and then exposed it under a drawing or a positive glass picture. The black lines kept back the light. Accordingly, at these places the gelatine remained soluble, but was rendered insoluble under the white places, by the action of light. After exposure he washed the plates in the dark with warm water. By this means the places that had remained soluble under the black lines were dissolved; the others were retained on the plate. Thus Talbot obtained a drawing on the metal itself on a brown ground. This is worthless by itself, but it provides the means of producing a steel plate for engraving.

We have already explained, at p. 210, the nature of steel and copper-plate engraving. Both processes consist in the production of a metal plate which contains, in incised lines, the drawing that is to be reproduced. These lines retain the ink which is rubbed upon the plate, and transfer it to the paper. The hard steel plates have the advantage of lasting for many more copies than the softer copper plate; only the steel engravings are far inferior to copper-plate in artistic beauty, and therefore the former have lost favour. But the steel engraving is very important for preparing technical and scientific diagrams, paper money, and the like, as less artistic beauty is required in their case. It was steel plates of this kind that Talbot produced by the help of light.

We have seen that his steel plate was covered with

an insoluble film of gelatine, and that the metal was uncovered at all places where the light had not operated. He poured on it a fluid which ate into the steel; for example, a mixture of acetic acid and nitric acid. This mixture, of course, only attacked the steel where it was exposed, and thus produced an incised drawing in the steel plate, so that the latter, after being cleaned, gives as good an engraving as if it were the work of the engraver.

Thus a new process was found to replace the difficult work of the engraver by the chemical action of light.

We have mentioned in the first chapter a similar process, based on the application of asphalt and a different one by Scamoni. (See p. 210.)

This discovery of Talbot was soon followed by a more productive one on the same ground.

An Austrian, Paul Pretsch, prepared, in 1854, copper-engravings by a similar method, with the help of the electrotype process. He also took a film of gelatine, which contained chromate of potash, exposed this under a negative or a positive picture, and then washed it in hot water.

After doing this, all the places were retained which had become insoluble through the light, and after the washing and drying they stood out in high relief.

Accordingly, in copying under a positive, the lines which were black in the original appeared in low relief, and the white parts in high relief.

This film was placed in an electrotype apparatus. This apparatus has the property of precipitating copper or other metals on a surface. It consists of a galvanic cell, as described p. 70, and a trough containing a solution of sulphate of copper. The reliefs which are to be copied,

having been made conductors of electricity by a coating of graphite, are suspended from the zinc pole *B* (Fig. 90) of the battery in the sulphate of copper: to the copper pole *D*, a plate of copper is attached. As soon as the galvanic stream passes, the solution is decomposed, and the copper adheres to the relief. The thickness of the copper depends on the time the current is allowed to last; accordingly, plates of any thickness can be produced.



Fig. 90.

If the original was incised, the electrotype impression will be in relief, and *vice versâ*. Therefore, in the above case an impression is obtained with lines in high relief.

This kind of plate is also adapted to give impressions, but rather differently from an incised copper plate. In the latter, the engraver's ink is rubbed into the incised marks, and then under strong pressure conveyed to paper.

In a plate with a picture in relief, the impression takes place as in printing; the raised places are rubbed over with printer's ink by the help of a leather

ball, or of a cylinder blackened with ink, and then printed on paper. Letter-press is produced in this manner; all its letters are in high relief; also all woodcuts which accompany the text.

The printing-press is the simplest and cheapest mode of multiplying copies. It admits of the use of cheap papers, whilst copper-plate engraving requires a thick, soft, special paper. The printing-press, moreover, admits of woodcuts being printed in the text, whilst copper-plate printing requires special plates. Lastly, the printing-press works with extreme rapidity, whereas copper-plate printing requires much more time.

Further, the printing-press does not use up the type rapidly, as it works under feeble pressure; while copper-plate printing, which requires strong pressure, wears the plate considerably, so that after striking off a thousand copies, the impressions are no longer as good as at first.

The production of photographic plates for the printing-press is of the greatest importance, and Pretsch has taken the lead here. His process did not, indeed, produce the most perfect results. The incised plate which he produced on the gelatine film by the help of light was not deep enough to produce a high relief in the galvanic impression; but this is necessary, for otherwise the printer's ink penetrates into the incised parts, which ought to remain white, while the washing of the exposed gelatine films with hot water easily destroys the finer parts of the picture, and this detracts materially from the value of the copies. Moreover, difficulties arise in preparing the electrotype plates; the film swells up and loses its form. In short, the affair is not so simple as it appears; little

difficulties exist, and these occasion errors which the unprofessional hardly observe, but which considerably diminish the effectiveness of the picture.

At an early period it was found that these processes offered a special difficulty, viz., the reproduction of the transitions from light to shade—the half-tones. These were so very imperfect that the representation of natural objects—portraits and landscapes—was speedily given up, and people confined themselves to the reproduction of drawings, maps, and the like, on an enlarged or diminished scale, and thereby to producing stereotype plates for copper engraving and printing. This application is of no little importance, for it prepares a metal plate for printing, by the help of light, in as many hours as an engraver requires days, and at far less cost.

We add two plates to the present work, which have been prepared by Scamoni of St. Petersburg, by the help of gelatine and bichromate of potash, by a modification of the process just described. Both are impressions from heliographic plates: the smaller one—Plate III., "Am Rhein"—is a plate in high relief, which is printed in the printing-press; the other—Plate IV., "Johannisfest"—an incised plate, in the style of copper engraving.

Section III.—The Production of Photo-reliefs.

Photo-sculptures—The Pantograph—The Fount Process—Chromogelatine-relief—Fount-relief by Cold Water—Relief by Cold Water—Difficulty of its Production—The Transfer Process.

More than ten years ago intelligence was received from Paris of an entirely new discovery—photo-sculpture—which was said to produce statues by the help of light.

According to the description, this was effected as

PLATE III.

P. 224

ELECTROTYPE FROM HELIOGRAPH.



Plate IV.

follows: a person was placed in the middle of a circle of about twenty photographic apparatus, which at a given moment took twenty pictures of the person, and represented him on every side. These photographs were afterwards transferred to clay, by means of an instrument commonly called a pantograph. This consists of a system of bars *a b c d* (Fig. 91). Of this system one bar can be turned about a pivot *x*, the others are moveable at the joints; *m n* are two pencils. If one pencil *m* is carried



Fig. 91.

along a drawing, the other pencil *n* makes the same movement, and, if a piece of paper be placed under it, *n* draws exactly the same line which the first pencil *m* describes. If instead of the pencil *n* we conceive a knife, which cuts out in clay the outline described by *m*, a profile is obtained in clay by moving *n* along the outline of an image, and in this manner all the outlines of the person taken can be transferred to clay. This photo-sculpture, as it is called, can only be carried out imperfectly. A careful manipulation by a very clever artistic hand is necessary for the work, and is indeed the essential point. As far as the author has examined the

matter, the pantograph is a mere pretence. A clever artist models the bust according to the photographs.

Nevertheless, these reliefs can be produced by light, and these reliefs are not inventions of advertisers; they are easily produced, and it is surprising that the process has not yet made a stand.

We have mentioned above the properties of gelatine, and remarked that it has the power of absorbing cold water and thus swelling up. This property is lost if the gelatine is saturated with chromate of potash and exposed to the light. If this exposure is made under a negative, all the places situated under the transparent parts lose this property, while the other places not affected by the light retain it. Accordingly, if the exposed film be thrown into water, the places which are not affected by light swell, whilst those affected by light are not altered. The result is a true relief,—the lights are in high relief, the shadows in low relief,—and this is so strong that it can be cast in plaster of Paris. For this purpose the relief is dried with blotting-paper, rubbed with oil, and then a paste of plaster is poured over it. This soon hardens, and gives an impression of the gelatine relief, being in high relief where the gelatine is hollowed, and *vice versâ* (Fig. 92).



Fig. 92.

It appears as if a plate might be easily obtained for letter-press from such a gelatine relief. Let the gelatine film under a drawing be supposed to be exposed. The black lines then keep back the light; accordingly, the gelatine particles come out in high relief on being wetted with water. The drawing is therefore represented in

high relief, and this is exactly what the printer requires; nothing further would now be required than to cast the relief in plaster, and recast the plaster form in metal, as happens daily in the stereotyping of woodcuts. But unfortunately this process breaks down, owing to a trifling circumstance—the lines in the wet relief do not swell to the same height. But the printing-press requires them to be perfectly level, otherwise they cannot be equally inked and printed.

On the other hand, the casting can be very well utilized as a picture in relief, if suitable retouches are given to it. Reliefs of this kind with portraits were sold some years ago for seals, but the execution was very imperfect, and therefore they soon lost favour.

But reliefs can be obtained in another way from an exposed gelatine film, namely, by hot water. As we have seen above, this dissolves the parts which, not having been affected by light, have remained soluble, while the parts affected by light, and therefore insoluble, remain untouched. These parts that have remained insoluble stand out as prominences.

Another precaution is necessary. Suppose that *N* (Fig 93 *a*) is a negative, that *c c* are its transparent parts, and *b* the semi-transparent, what are called half-tones. If a film of prepared gelatine *g* (Fig. 93 *b*) is exposed under them, the light penetrates in various degrees, according to its strength—most in the transparent places, less in the semi-transparent, and not at all in the opaque parts.

Accordingly, insoluble films of different thickness will be formed, as represented in *b*. The shaded parts in the figure denote the portions that have become insoluble.

If now the film of gelatine (Fig. 93 *b*) is plunged in

hot water, all the parts left white in the figure become dissolved; but at the same time the half-tones not adhering to the substratum P—for instance, paper—become detached and are torn off. Therefore a relief of the form d remains behind; the half-tones (y y) are wanting. In order to avoid this a support must be given to the exposed surface to retain the half-tones. For this pur-



Fig. 93.

pose a piece of paper, moistened with white of egg, is laid on the exposed surface and becomes firmly attached to it. If the sheet is now immersed in hot water, the film P becomes detached from g, the little portions of gelatine remain attached to the albuminized paper; the white places in Fig. 93 b become dissolved, and all the half-tones y y adhere firmly to the new layer, as

in Fig. 93 *e*, and form a relief. This is named the transfer process. If the relief produced by cold water, described p. 226 (Fig. 93 *e*), is compared with that produced with hot water (Fig 93 *c*), the difference is at once apparent: in the former case the parts not affected stand out in relief, in the latter case those exposed to light.

Section IV.—Printing in Relief.

Production of Photographic Half-tones—Production of a Printing Plate in Relief from a Gelatine Relief—Woodbury's Printing Process—Its Importance—Printing in Relief on Glass—Magic-lantern Pictures.

Although production of reliefs with cold and also with hot water, described in the previous chapter, has not at present been utilized for any kind of photo-sculpture, a new printing process has been founded on it, which was invented by Woodbury in 1865, and has been called Woodbury-type, from its inventor.

The heliographic methods of printing previously described are apparently very simple. Pictures of all objects cannot, however, be prepared by these methods. A linear drawing, such as a map or letterpress, can be reproduced either on an enlarged or diminished scale, by these methods; but pictures with half-tones, such as sepia drawings or photographs from nature, cannot be so copied. The soft half-tones become rough and hard, rendering the picture very ugly. According to Osborne, the cause of this is found chiefly in the nature of half-tones in copper-plate printing, which are formed by a series of lines at various distances from each other or by roughening the plate; the latter method produces a series of points, which, according to their distances from each

other, give a lighter or darker shade or half-tone. The half-tone of sepia drawings and photographs is quite different. It is not formed of strokes or points, but is a homogeneous light or dark colour.

Accordingly, it was first necessary to break up the photographic half-tone into a series of strokes or points, to make it a copper-plate half-tone, and this constitutes the difficulty.

Woodbury conceived the idea of producing, by a new printing process, homogeneous half-tones, perfectly similar to those of photographs or sepia drawings.

He produced a relief by exposing a film of prepared gelatine under a negative, and then treating it with hot water. (See last chapter.) This relief shows the dark parts of the original in high relief, and the light parts in low relief. For the negative is transparent where the original is black; hence the light passes unimpeded through those places. The half-tones are formed by the varying height of the gelatine film. (Compare Fig. 93 *e*.)

If this gelatine relief is suffered to dry, it becomes wonderfully hard and firm. It can then be placed with a plate of lead under a strong press, and a *cliché* of the relief can be thus obtained in lead. The prominent parts of the gelatine relief appear, of course, depressed in the lead, and the depressions prominent, as represented in Fig. 93 *d*.

Woodbury uses this lead relief as a printing plate. But he does not print it off with oily printer's ink, which is too opaque, but with a semi-transparent gelatine ink. This is poured warm on the plate in a horizontal position, it penetrates into the depressions, and now, if a piece of paper be placed upon it and pressed gently down, the

gelatine consolidates quickly, and an impression in relief is obtained on the paper. As the ink is transparent, it appears in thin sheets much less black than in the thick, and in places where its thickness gradually diminishes occurs a transition from black to white—a perfectly homogeneous half-tone. As soon as the coating dries, the relief contracts considerably, but the semi-transparency remains, and thus it is possible to reproduce the most beautiful half-tones of photography by printing. Any colour may be used in this process.

This relief-printing of Woodbury has already attained a high importance. It makes the multiplication of photographic negatives from a single printing form possible without the help of light. It is therefore of importance where a great number of pictures are required; for example, in the production of copies of oil-paintings and drawings. Photographers do not use it much in portraiture, because the production of a faultless gelatine relief and its impression on lead require great practice and an expensive apparatus, which would not pay in the limited sphere of portrait photography.

The frontispiece of the present work, representing the moon, from a photograph by Rutherford (mentioned p. 188), is an impression in relief, by the Relief Printing Company in London.

It is a special advantage of the relief-printing process that it admits of printing on glass. Wonderful transparencies are thus obtained, very effective as window ornaments. Goupil has prepared copies of oil-paintings by this method, and they are frequently to be seen in the windows of our dealers. The transparent stereoscopic pictures on glass, produced by this process, are

equally charming—in sharpness and softness they almost excel the ordinary silver copies. Recently a number of beautiful magic-lantern pictures, produced by the Woodbury process, have been offered for sale, and will be eventually used as an important means of instruction in schools. The author has a collection of American landscapes of this kind, which, when enlarged in the magic lantern, are more instructive than the fullest geographical treatise.

Pictures of this kind can be sold much cheaper than the ordinary transparent photographs for stereoscopes. (See the chapter on landscape photography, p. 155.)

Section V.—Pigment Printing.

Poitevin's Process—Production of Pictures in any Kind of Pigment—Its Difficulty—Inverted Impressions—Transfer Process—Comparison of Pigment and Silver Prints—Braun's Facsimile of Coloured Drawings—Transfer by Contact.

We have seen above that gelatine mixed with bichromate of potash becomes insoluble in the light. This fact was made by its discoverer, Talbot, the basis of heliography—that is, of photographic steel engraving. Poitevin, a Frenchman who has done much to promote photography, founded on the same method another process: he produced pictures in various colours. He first used carbon as a pigment, thus obtaining carbon pictures.

The process is simple: Poitevin coated paper with prepared gelatine coloured with lampblack, and exposed this under a negative; he then washed the film in hot water, which dissolved those parts of the gelatine un-

affected by the light, whilst the insoluble parts retained their colouring matter and thus formed a picture.

Practical difficulties occur even in this simple process. As has been already mentioned, the action of the light does not always penetrate the whole thickness of the film. The half-tones have, therefore, no support, and are torn off in washing (see Fig. 93 *e*, p. 228). Before treating the films with hot water, it is therefore necessary to transfer them, as described in the chapter on photo-reliefs. An albumenized sheet is pressed in the dark on the coloured film of gelatine, and then the whole is plunged into hot water; the half-tones adhere to the paper pressed upon them, and the image appears uninjured on it, as in Fig. 93 *e*.

The picture is, of course, reversed; that is, what was originally to the right in the lower image comes now to the left. That this is so can be easily seen by writing a word with thick ink in large letters on a piece of paper, and laying a piece of blotting-paper on the wet writing. The reversed impression of the writing is seen on removing the blotting-paper. In the letter copying-press the same thing takes place, and therefore the letters are copied on very thin paper, that they may be read on the reversed side, because viewed from that side they appear in their first position. The gelatine prints cannot be printed on such thin paper; therefore, if the reversed position is inconvenient, the picture must be again transferred. This has been latterly managed in the following manner:—

The moist gelatine film is placed after exposure upon a smooth zinc plate, to which on drying it becomes very firmly attached. The copy thus glued to zinc is immersed

in warm water, the paper becomes detached, and the developed image adheres to the zinc plate. A sheet of white paper is now fastened with glue upon the zinc plate, and allowed to dry. The gelatine picture adheres firmly to this paper, and may, with care, be detached from the zinc plate. The picture thus appears unreversed upon the paper. This more recent form of the process is employed in England at Woolwich Arsenal.

The pictures thus obtained are very similar to those of the Woodbury-type; they surpass the latter, however, in the fineness of their details and the ease with which they may be produced.

This process has not yet supplanted silver printing, for the expense of the material, owing to the twofold use of paper, equals that of silver photography, and the labour, being somewhat more complicated, is therefore dearer. The pigment impressions have a great advantage in the fact that they can be produced in any colour; genuine Indian ink may be used for them, and then perfectly durable pictures are obtained that do not turn yellow or black.

In the same way red, sepia, blue, and so on, can be mixed with the gelatine, and thus pictures can be produced in those colours. This circumstance is important when it is wished to reproduce coloured drawings. Quantities of such drawings and sketches of the old masters are in various museums. Braun of Dornach, in Alsace, the same photographer who made himself conspicuous for his Swiss views, has undertaken to reproduce such drawings in their original colour by the process just described, preparing first a silver negative in the usual way, and printing from this on coloured gelatine films.

He has thus made cheap facsimiles of many drawings of which no copy had previously existed.

Latterly, a very interesting observation has been made by Abney, in England, in relation to the foregoing process. He remarked that if an exposed film of gelatine remained a long time in the dark the insolubility increases. Accordingly, a film of this kind which, freshly developed, would only give a faint image, after some hours gives a strongly defined image. This fact allows the time of exposure for pigment pictures to be considerably reduced; that is, a larger number of pictures to be made in the same time.

Still more interesting is an observation of Marion, at Paris. He exposed under a negative a sheet of paper sensitized with bichromate of potash, and then pressed it in the dark on a moist film of coloured gelatine also sensitized with bichromate. The gelatine became insoluble wherever the paper had been affected by the light, and on development with hot water a pigment picture was obtained on the paper.

Section VI.—The Albert-type.

Services of Poitevin and Tessié de Mothay—Albert-type—Methods—Use and Comparison with the Woodbury-type.

We have seen that the parts of a gelatine film containing bichromate of potash, which are exposed to the action of light, become insoluble in water, and do not swell on being moistened; at the same time they acquire the property of adhering to fatty inks. Thus if an exposed film is moistened with a wet sponge, the unaltered places

only absorb the water. If, on the other hand, printer's ink be rubbed over the film, those places only which have been changed by the light retain the ink. This fact was discovered by Poitevin, the author of many valuable discoveries in photographic chemistry.

If a piece of paper be pressed on such a film of gelatine, coated with printer's ink, the ink adheres to the paper, and thus a print is obtained of the negative, under which the film had been exposed.

This peculiar mode of printing gave at first very imperfect results. The process was rendered difficult from the fragile nature of the gelatine film, the difficulty of finding the right time for exposure, the proper consistency of the printer's ink, and other obstacles. After a hundred impressions, the film of gelatine was generally so injured that it was useless. Tessié de Mothay, at Metz, obtained moderately good results with the process, but Albert, of Munich, was the first who succeeded in making it of any practical importance.

All experimenters before Albert had transferred the gelatine film to metal, to which it only adhered imperfectly. Albert poured the gelatine solution of bichromate of potash in the dark, on glass, and exposed it, after drying, glass upwards, for a short time to the light. In this way the light produced a superficial effect; the part of the gelatine adhering to the glass became insoluble, and thus firmly fixed. A negative was then placed on the film and exposed to the light. A faint greenish picture is thus produced. The exposed film is then washed in water until all the bichromate is removed, and then is suffered to dry.

To print from such a film, it is first rubbed with

a sponge wetted with a dilute solution of glycerine. Those parts only of the film which are unaffected by light absorb the water. A leathern roller is inked by rolling it on a slab of marble on which printer's ink has been spread, and then lightly passed several times over the gelatine film. All places which have been affected by the light retain ink from the roller, but not so the others, and finally a well-defined picture appears on the originally almost colourless surface. As soon as it has been sufficiently inked, a piece of paper is laid upon it, and passed through rollers coated with india-rubber, the plate being laid on a sheet of the same material. In this manner the ink of the picture passes over to the paper, and produces thus an impression with all half-tones. The inking and printing can be repeated at option, and thus thousands of copies may be prepared if the plate is very firm.

These Albert-types, or "Lichtdrucke," as they have been latterly called, approach, but do not equal, the silver prints in beauty. The process is well adapted for copying pencil and chalk drawings, which are reproduced with the utmost fidelity. Herr Albert has reproduced and published Schwind's Fairy Tale of the Seven Ravens, and several cartoons of Kaulbach, by this process. It has also been used by Obernetter for printing the views taken by the photographic department of the Prussian army in the late war. The views of the Vienna exhibition, sold in the building, and by many supposed to be ordinary photographs, are Albert-types by Obernetter of Munich, who, as well as Albert, has done much in developing this process. In the annexed double picture by Obernetter we give a specimen of an Albert-type.

The brilliancy of these pictures is produced by giving them a coat of varnish.

If the prints by this process be compared with Woodbury-types, it is seen that the latter give the shades and dark parts better, but that the white parts often appear discoloured. The Woodbury-types are also much more like photographs than the Albert-types, for the latter have a lithographic tone. It is only by coating with varnish that they are made to resemble photographs. But both methods are rather inferior to ordinary silver photography, which has never been surpassed in the uniformity of its half-tones, in the beauty of its lights, and the depth of its shadows, and which has one special advantage over both processes, and that is the ease of production. The preparation of pictures by the Albert or Woodbury processes requires a printing plate, to obtain which a more complicated plant is necessary than in the case of the ordinary silver print, and also a skilled artist. Silver printing gives good results with simple means, and even in inexperienced hands. It will therefore always be preferred for portraits, where the object is often only to produce a dozen pictures. The Woodbury and Albert processes are of great importance when the object is to produce large numbers of pictures in a short time.

Section VII.—Aniline Printing.

Aniline Colours—Action of Chromic Acid on Aniline—Its Use in Photography—Willis's Printing Process—Its Application.

Every one knows the brilliant aniline colours—Hofmann's violet, magenta, aniline green, and others. We are indebted for these wonderful pigments, surpassing all

earlier dyes in brilliancy, depth, and reflecting power, principally to the noted chemist, Hofmann. The colours are due to the action of various oxidizing agents on aniline.

Aniline is a substance which resembles ammonia in its chemical relations, but having a different odour and a different chemical composition. The substance is obtained as a brown mass from coal tar on distillation.

If this brown fluid is treated with chlorine or nitric acid, or manganese and sulphuric acid, or arsenious acid, various shades of colour are produced. One specially interesting us is the colour formed by heating aniline with chromate of potash and sulphuric acid; the result is a peculiar violet substance—aniline violet. Chromate of potash, as already seen, plays a part in some of our photo-chemical processes, and on this substance is based the aniline printing invented by Willis.

Willis immerses a piece of paper, in the dark room, in a solution of chromate of potash and sulphuric acid. He exposes the paper under a positive picture, *e.g.*, a drawing or copper engraving. The light shines through the white paper, and in these places the chromic acid is reduced to oxide of chromium, which does not affect aniline colours; on the other hand, the chromic acid remains unchanged under the black strokes, which keep back the light. After the exposure a very faint picture is seen of unchanged yellow chromic acid.

If this faint picture is exposed to the vapour of aniline, a brown colour is produced at the places where the yellow strokes exist, and in this manner the original faint yellow becomes well defined. To expose the prints to aniline vapour they are placed in a covered box with

a piece of blotting-paper, moistened with a solution of aniline in benzine. This process produces a positive picture from a positive, and is therefore very valuable in producing faithful copies of drawings. These copies are of course reversed, as if seen in a mirror. This circumstance limits their use in many cases. We have already explained the reason of this reversal (p. 233). Copies can, however, be obtained in their proper position if the original drawing is very thin. In that case the back of the drawing is placed against the chromic acid paper, and the light is suffered to shine through it from the upper surface.

Another disadvantage of this process is that the chromic acid paper must be always freshly prepared, as it quickly spoils, and the difficulty of ascertaining the proper time for exposure. If the time is too short, unchanged chromic acid remains everywhere on the paper, and thus the whole picture is blackened by the aniline. If, again, the time is too long, the light acts gradually through the black strokes of the drawing, reduces the chromic acid, and the paper then remains entirely white in the aniline fumes, as no more chromic acid is present to form aniline colours. These circumstances limit the value of the method, and cause the *lichtpaus* process (p. 25) to be preferred to it. In England the aniline printing is practised by the inventor, who prepares copies to order.

Section VIII.—Photo-Lithography.

Nature of Lithography—Chromo-lithography—Zincography—Poitevin's Discovery—Photo-lithography—Its Application in multiplying Maps quickly—Its Importance in War—Difficulties—Photo-lithography with Asphalt.

By lithography is understood a process of printing from a drawing or painting on a prepared stone. Near the little Bavarian town of Solenhofen, there is a clayey, rather porous limestone, easily polished and worked. Such limestone is used for lithography. But the lithographic press differs essentially from copper-printing and book press, because the drawing on stone is neither raised nor incised. The lithographic stone forms, when ready for printing, a smooth surface; and in this the process is peculiar, differing from all other modes of printing. If a drawing is made on a lithographic stone with ink consisting of colour and a fatty substance, *e.g.*, oil, and the stone is moistened with water, the porous stone is wetted only in those places where there is no oily colour, for oil repels water. An oily ink, such as printer's ink, is then rubbed on the stone with a leathern roller and only adheres to the previously inked spots—that is, to the drawing.

After the stone has been inked as above, if a piece of paper is pressed upon it the ink passes over to it, and a lithographic impression is obtained. The stone can be evidently used any number of times, and thus thousands of copies can be produced. This style of printing has many advantages over copper engraving. The engraving of a copper plate is a difficult matter, often requiring a labour of years, whereas the drawing on stone

is almost as easily made as on paper. In like manner, printing from a stone plate has fewer difficulties than that from a copper plate. Corrections are easier to make on the stone, and further, after the surface has been removed by grinding, the same stone may be used for another drawing, and so on for many years. These circumstances have brought lithography into general use: technical drawings, wine labels, circulars, visiting cards, price lists, calendars, illustrations of books, atlases, scientific pictures, and a thousand other things are produced by lithography. Of late years a development of this process, called chromo-lithography, has come into general use, and is by far the most important method of producing coloured pictures mechanically. Chromo-lithography is rather more complicated than common lithography. If it is wished to make a chromo-lithograph of a painted picture, not only one stone, but a separate stone for every colour must be prepared. For example, to prepare a picture of an object in which blue, red, and yellow tones appear, a drawing in blue ink of all the blue parts must be made on a separate stone; a second and third stone are required for the yellow and red places. Prints must be made from each stone successively on the same piece of paper in the proper position, and thus a picture in colours is obtained. If such a picture is then coated with a brilliant varnish it becomes an "oleograph." Though chromo-lithography offers great advantages for maps, ornaments, etc., and affords many excellent artistic specimens—*e.g.*, the chromo-lithographs of Hildebrandt's water-colour paintings—we must express an adverse opinion of oleography, which, with a few honourable exceptions—by Prang at

Boston, Korn at Berlin, and Seitz at Hamburg—produces pictures of very small artistic value, and has done much to injure public taste.

An artist's taste and knowledge of colour are necessary for chromo-lithography, and the printers do not possess them.

Closely related to lithography is zincography, which we shall glance at here before passing to photo-lithography.

Zinc, curiously enough, has the same property as lithographic stone; for if drawings in oily chalk be made on a zinc plate, and then the whole moistened with gum water, the plate may be inked with oil colours, and thus a picture be obtained of the chalk drawing. The printing, therefore, presents results similar to those of lithography; but the preparation for zinc printing has more difficulties than lithography, so that the use of zinc for this purpose is limited.

We have given a brief survey of the principles of lithography and zincography, as far as necessary to understand what follows. Both processes resemble the Albert-type printing in many respects; in both cases the surface has the peculiarity of retaining ink in some places and repelling it in others—but the Albert-type is of recent date, while lithography has existed seventy years. When photography was invented, it deprived lithography of an important branch, that of portraits. Even in 1850 numerous lithographic portraits were made of individuals. But since the introduction of cartes de visite, portrait lithography has greatly fallen off, and is only used for cheap likenesses of distinguished persons. The lithographs from oil-paintings have also suffered through

photography, which thus entered into competition with lithography. Poitevin, who allied the two by inventing photo-lithography, endeavoured to economize the labour of the lithographic draughtsman, and to replace it by the chemical action of light. He coated lithographic stones with chromate of potassium and gelatine, and exposed them under a photographic negative. The picture thus obtained was then washed and inked. All parts affected by light took the colour, and gave an impression in the press. The first attempts of the kind were very imperfect; the pictures were especially wanting in half-tones, which were lost in washing, as they are in the pigment process (see p. 233). An improvement was introduced by Asser and Osborne; they printed the negatives on paper prepared with bichromate of potash coated with gum gelatine or albumen, and then they inked this. Such paper has the peculiar property of retaining printer's ink on the exposed places only. After inking, the paper was carefully washed and then pressed on a lithographic stone. This absorbed the colour, and thus the picture was perfectly transferred to the stone, from which excellent lithographic prints could be obtained in the ordinary way. Though half-tones were thus produced, the impression fell far short of photographs in quality. The lithographic half-tone differs essentially from the photographic, which forms a homogeneous surface, while the lithographic half-tone appears as a mass of black points more or less near together. The granular structure of the stone does not allow such delicacy as may be attained by photography; therefore, photo-lithography is employed only where cheap production of many copies is of greater moment than delicacy.

Quite recently, maps of rivers and mountains have been sold by Kellner & Co., at Weimar, which have been produced by photographing plaster reliefs, and printing from the negatives then obtained by photo-lithography. The maps were produced without the aid of a draughtsman and at so low a price as to make them accessible to the poorest students.

Photo-lithography cannot be used to reproduce works of art. For this the Albert-type, with its excellent half-tones, is a formidable competitor, though photo-lithography is very useful, because a great number of impressions may be obtained from the same plate, while the number from a gelatine plate is always limited, and the prints moreover are of varying quality.

In one branch photo-lithography surpasses all other reproducing arts; that is, in producing copies of maps which have been drawn by hand. The preparation of geographical maps requires much time and care. The outlines of mountains, rivers, and countries must be executed with the greatest exactitude, corresponding to the measurement. Frequently draughtsmen and engravers are employed for the various details, and though working conscientiously, inaccuracies are unavoidable, and make corrections necessary. All this takes time and trouble. If the object is now to make an enlarged or diminished copy of an existing map, the same difficulties occur, and the diminishing is especially troublesome. The pantograph is a useful aid here, but does not exclude inattention in the draughtsman. In this respect photography is invaluable as an aid to map-making. With very great ease, enlarged or diminished copies of an original may be prepared as negatives by photography; in a few hours

this is copied on stone, and within a day photo-lithography can throw off thousands of enlarged, diminished, or original sized copies.

If it were wished to make a lithographic stone drawing by hand, several days would be necessary, and it would be far less exact. No photographic printing process is as rapid as photo-lithography, and it has in consequence been much used in map-making, especially where a large number of copies are required. In the French war, the advancing troops needed, before all things, maps of the territory to be occupied. But there was not a sufficient supply of maps of France to provide whole Army Corps with. It is impossible to keep a stock of such maps, as no one can tell where a campaign will take place. Photo-lithography was here an important means of preparing thousands of copies from one original map; and thereby contributed to the successful advance of the German army, which, with these maps in hand, showed itself better acquainted with the enemy's territory than the enemy's troops themselves. The photo-lithographic establishment of the brothers Burchard, at Berlin, produced in the war of 1870-71, 500,000 maps. Plate V. is a specimen of this process.

In connection with this subject we must mention Herr Korn of Berlin, whose work belongs more to pure art. Particularly admirable are the photo-lithographic copies of the drawings made by Berg in the Japanese expedition. These are so faithfully reproduced that original and copy cannot be distinguished—the character of the originals being, of course, very favourable to photo-lithographic reproduction.

Faint drawings place difficulties in the way of photo-

REDUCTION OF
A SECTION OF THE ORDNANCE SURVEY MAP
OF ENGLAND.

PLATE V.

Stratford upon Avon & Moreton in Marsh Railway
Stratford upon Avon & Midland Junction Railway
Station
Bearley
Snitterfield
Bearley Cross
Bearley Wharf
Wootton Wawen
Hatchet Pathlow
Hill Farm
Gipsey Hall
Wilmcote
Bishopswick Hill
Little Bercton
Bishopton
Park Farm
Bell Inn
Temple Grafton
Binton Hall
Spring Farm
Haulton
Packwood Hill Bridge
Wixcych
Ryon Hill
Alveston
Oxstall
Hemmings Mill
Tiddington
Pimlico
Clopton Bridge
Stratford Bridge
Stratford Field
Old Stratford
Drayton
Shottery
Hunter Hill
Dorsell
Dorsell Hill
Hall End
Hunks Barn
Alveston Hill
Alveston Pasture
Alveston Heath
Gaydon
Lighthorne
Kingston
Lower Milcote
Avon
Weston upon Avon
Milcote
Milcote Station
Clifford Chambers
Clifford Hill
Hill Farm
Hides House
Mond's Close Cottages
Low Farm
Stratford Heath
Grafts
Atherstone upon Stour
Atherstone Hill
Gallibrook Barn
Preston upon Stour
Preston Park
Park Lane Barn
Church Hill
Whitchurch
Aldermanst
Aldermanchurch Farm
Wimpstone
Wimpstone Farm
Tredington
Tredington Field
Tredington Wharf
Tredington Tunnel
Tredington Locks
Shop House
Kinsbe
Willicot
The Farm
Wimpcote
Ticknell Barn
Midland & Great Western Railway
Honeybourne Branch
Stratford upon Avon & Midland Junction Railway
Stratford upon Avon & Moreton in Marsh Railway
Brick House
Road Mill
Windmill
Windmill Farm
Hollowmoor Farm
Hollowmoor Bridge
Bridge
Ford
Ford Mill
Alveston Mill
Alveston Hall
Alveston Pasture
Hunter Hill
Hunter Hill Farm
Tiddington Bridge
Pimlico Bridge
Hunter Hill Bridge
Alveston Hill Farm
Alveston Pasture Farm
Alveston Heath Farm
Grafts Farm
Low Farm
Stratford Heath Farm
Hides House
Mond's Close Cottages
Clifford Chambers
Clifford Hill
Hill Farm
Milcote
Milcote Station
Weston upon Avon
Avon
Kingston
Lower Milcote
Gaydon
Lighthorne

graphic reproduction, especially when they have a bluish tint; and therefore pencil drawings are very difficult to photograph. No perfect photo-lithograph can be produced from an imperfect photographic negative. Thus far, therefore, the character of the original has a very material influence. Berg's drawings are executed in strong black Indian ink, and therefore easy to reproduce. In the Austrian Institution of Military Geography, the map drawings which are to be copied by photo-lithography are so executed from the first that they make a favourable photographic object, or, to use the technical term, come out well. For the photographic reproduction of a drawing brown tints, such as umber, when mixed with Indian ink, are the best. On the other hand, much depends on the paper being without blemish; yellow spots, scarcely visible to the eye, have the same effect in photography as black ink. We knew a case in Korn's photographic printing-house where an unblemished drawing of a map came out as a photograph full of spots. The defect was attributed to the chemicals, until it was found that minute rust spots in the paper, which had got into it during manufacture, were the cause of the defect. In such cases the evil can only be remedied by retouching the negative.

The nature of photo-zincography will now be clear to the reader: for the treatment of the zinc plate and of the stone is the same. The negative is either copied directly on the zinc plate, coated with gelatine and bichromate, or a copy from the negative is prepared on chromo-gelatine paper, and the paper is then inked and transferred by pressure to the zinc plate. In both cases the prints may be taken directly from the zinc plate.

It must be remarked that, even without photography, direct mechanical copies can be made of maps, writings, etc., if the original be executed in oil colours by a transfer process. The back of the original is moistened with acidulated gum water, and then the face is inked with an oily ink which adheres only to the oily strokes of the drawing or printing. The original, thus freshly inked, is then placed on a fresh stone, or a freshly cleaned zinc plate, and pressed. The drawing passes over to the stone or the zinc, and can be easily multiplied by inking and printing. It is difficult to preserve the original, which is often much damaged by the pressure. Still more difficult is it to obtain clean lines, for the ink is often squeezed out by the pressure, and if the lines are close, as in the mountain lines of maps, they run together ; therefore the process has been more applied for copying old books, which have been reproduced page by page in this way.

It is self-evident that only reproductions of the original size can be made by this process.

We have to mention another process of photo-lithography, based on the use of asphalt. We have already described this in our first chapter as a sensitive substance, and also a process called heliography, which produces, by means of photography, copper plates and steel plates for printing. Asphalt serves also for photo-lithography. A lithographic stone is sprinkled with a solution of asphalt in ether, allowed to dry in the dark, and exposed under a negative. The asphalt becomes insoluble on the exposed places, and is retained upon treating the stone with ether or benzine. If the stone is then damped, the moisture only penetrates where no asphalt covers the stone. On rolling it after this with an inked roller, the fatty ink is

not retained by the damp places, and only adheres to the asphalt—that is, to the picture; thus a stone giving impressions is obtained. This method gives good results in the hands of several practitioners, and is preferred by many to the gelatine process, though asphalt is much less sensitive than the prepared gelatine.

Section IX.—Encaustic Photography with Salts of Chromium.

Poitevin's Process—Action of Bichromate of Potash on Sticky Substances—Pictures developed by Dust—Pictures on Porcelain—Oidtmann's Pyro-photography—Application to the Decoration of Glass—Photography and Painting on Glass.

Photography has become allied to almost all the multiplying and descriptive arts, though it was at first looked upon as their rival. It is not supprising, therefore, that it has become a help in porcelain painting and decoration. We have already mentioned (p. 207) the peculiar process of changing silver pictures into gold and platinum pictures, transferring them to porcelain, and burning them in. This method might be called a wet process; the same end can be obtained by a dry method, and by the help of salts of chromium. The original method was invented by Poitevin, and subsequently was materially improved by Joubert in London, and Obernetter at Munich. It consists in this: a mixture of gum, honey, and bichromate of potash is poured on glass; the film is carefully dried in the dark, and then exposed under a positive. This film of gum, when freshly prepared, is sticky and retains any colouring matter strewn over it in powder, but after exposure to light the film loses its stickiness. If this exposure takes place under a

drawing with black strokes, the film under them will retain its stickiness, but lose it beneath the white, transparent parts of the paper.

Therefore, if any colouring matter in powder be strewn over the film after exposure, it adheres where the strokes of the drawing have protected the film from the light, but not at other places, and thus a picture in powdered colour is obtained. If this coloured powder and the surface on which it is strewn are fire-proof—as glass and porcelain—the picture obtained can be burnt in, and pictures of various shades can be produced, according to the choice of the powdered colour. Pictures of this kind can be transferred from one surface to another. If a collodion film is poured upon the powdered picture and suffered to dry, and then the whole immersed in water, the collodion film with the picture can be easily separated from the surface on which it was produced, and transferred to and burnt into other surfaces—glasses, cups, etc. Thus Joubert in London has actually burnt in large pictures on glass. Obernetter at Munich, and Leth at Vienna, Leisner at Waldenburg, and Stender at Lamspringe, Greiner at Apolda, and Lafon de Camarsac at Paris have also produced encaustic pictures on porcelain in the same manner.

This process is not much employed for portraits. On the other hand, Oidtmann at Linnich,* has employed it advantageously in glass manufacture. He has copied tapestry pictures from lithographs directly on glass, and burnt them in, thereby producing cheap window ornaments. At the Vienna exhibition, there was over the

* See "Photographische Mittheilungen," Jahrg. 1869. Berlin: Oppenheim.

door of the Emperor of Germany's pavilion a rosette ten feet in diameter, produced by Dr. Oidtmann by the above process. The same person has also employed the process to produce mosaic glass pictures, similar to the mediæval paintings on glass. These mosaic glass pictures are produced by cutting out coloured pieces of glass corresponding to the figures and their colours. For example, for a human figure, the outline of the face was cut out of a flesh-coloured glass plate; the same thing took place for the drapery, in glass plates corresponding to the colours. The lights and shades and details—for example, nose, mouth, and eyes—were then drawn with black fusible colour on the proper piece of glass assigned to it, and burnt in, after which all the separate pieces of the glass were set together with lead. Dr. Oidtmann does, by means of photography, what the draughtsman does in this mosaic glass-painting. He copies the outlines of the face from the large-sized original lithograph, or woodcut, on the proper piece of glass, and powders it with fusible black colour, and thus obtains a picture which can be burnt in, and treated in the manner described. At the Vienna exhibition there was a copy of "The Crucifixion" by Dürer, produced in this manner, and composed of 150 glass pieces. Dr. Oidtmann prepares the large-sized original pictures by magnifying small woodcuts by photography. (See p. 91.) Dr. Oidtmann has also attempted to produce pyro-lithographs, by proceeding on the principle of chromo-lithography. (See p. 242, Photo-lithography.) He copied the similarly coloured parts of a painted drawing—covering over the others—on a film of gum and chromium, powdered this with a suitable colour, and then copied the other colours of the original

successively in the same manner. He thus obtained a picture, in powders of various colours, which could be burnt in.

Section X.—Photography and the Sand-blast Process.

The Nature of the Sand-blast Process—Its Employment in Heliography instead of Corrosive Acids.

Tilghmann, at Philadelphia, made the observation, during his residence at the watering-place Longbranche, that the windows exposed to sea wind became quickly dim. He found that this was occasioned by fine sand, which the wind drove against the window; this gave him the idea of making ground glass by blowing sand against it, and he succeeded perfectly. He covered a glass surface with an iron screen, in which figures and letters were cut; and kept this in a current of air and sand. In a short time the exposed parts of the glass were ground, and thus a picture of the figures produced on the glass. A blast of a pressure of only four inches of water and a period of ten minutes are required for this work. If the air pressure is stronger, or steam is used to convey the sand, at a pressure of 60 to 120 lbs. to the square inch, the effect is wonderful. Sand blown with such power through a narrow pipe bores deep holes into the hardest stones, and even into glass. The process has been used to bore stone and metal plates. Figures cut in a cast-iron screen placed over a stone surface, can be deeply engraved in a short time in the stone. The iron plate is also affected, but much more slowly than the stone slab. A cast-iron plate $\frac{3}{16}$ of an inch thick is only reduced $\frac{1}{16}$ of an inch, in the same time that a cut 300 times deeper is made in

marble. India-rubber endures the sand stream almost as well as iron. Marble, protected by a perforated screen of india-rubber, may be cut 200 times as deep as the screen is thick without perceptibly affecting the india-rubber.

With the pressure of 100 lbs., such a sand stream can penetrate in one minute $1\frac{1}{2}$ inches deep into granite, 4 inches into marble, and 10 inches into soft sandstone.

The circumstance that soft bodies can be used as shields has led to elegant applications of this method in the industrial arts. For example, if glass be covered with lace pattern and a sand-blast be directed on it, the glass becomes ground in the meshes, and a copy of the lace is obtained on glass. In the same manner, paintings with a gum colour upon glass can be produced clear on an unpolished ground by the sand-blast. This circumstance led immediately to the application of photography. If a gelatine picture is produced on glass by the transfer process (see above), the surface of the glass at all the dark spots of the picture is protected by a layer of gelatine. If now a sand stream is allowed to operate upon it, it roughens the glass only at the uncovered places; thus a picture is formed. If the gelatine picture is a negative, the shadows are dim. A plate ground in this manner may be used for printing with printer's ink. The metal plates of Talbot's heliographic process may be etched by the sand-blast instead of by acids, which often eat sideways into the fine strokes, making them too wide. The sand, in consequence of its direction being at right angles to the plate, cannot widen the lines, and therefore the incisions may be carried to a great depth, and then the plates may be used with letter-press.

Tilghman suggests that a gelatine positive should be produced upon a cake of resin; that this should be blown upon and deeply hollowed out. A cast in plaster from this will form a mould for a type-metal cast, which could be used for printing.

These are interesting experiments, which ought in time to lead to important practical results.

Section XI.—The Photometer.

In many of the above described processes, it is very important to determine the exact time for exposure. This is not easy, because the picture appears only faintly



Fig. 94.

or not at all, therefore the appearance of the picture gives no safe criterion respecting its completion. This circumstance has necessitated the application of a photometer, to determine the duration of the exposure. Such photometers have been constructed by Byng and Swann in England, and by the author. The author's photometer consists of a semi-transparent paper scale *L* (Fig. 94), whose transparency diminishes from 2 to 25.

This scale is formed of layers of paper, the number of which is expressed by the figure printed on them; under

this scale is exposed a strip of chromated paper; that is, paper which has been plunged into bichromate of potassium. The strip is enclosed in a little box in such wise that, when the cover *D* with the scale is shut down, the paper and the scale are in close contact; the light now shines through the scale and browns the paper strips lying under it. The paper is first affected under the thin transparent part of the scale, and thence to the opaque end, the rapidity depending on the strength of the light. To know how far the effect of the light has extended, figures are printed on the scale, which do not permit the light to pass; they therefore remain clear on a brown ground, and the place to which the effect of light has advanced is indicated by the figure that appears there.

To use this instrument, some experimental prints must be made first. Supposing it were desired to prepare a pigment print from a negative, the film of pigment is exposed under the negative at the same time as the photometer. After some time, lamplight is used to see how far the photometer paper is browned. The significant number is noted—photometer degree—and half the negative is covered, the other half continuing to be exposed until a higher degree of the photometer. Then the pigment picture is developed, and the degree of the photometer is determined where the favourable result has been obtained. Rarely more than one attempt has to be made; when this has determined the degree up to which the negative must be copied, the time of exposure can always be regulated with the help of the photometer. Practised hands only determine the degree with a few negatives, and easily ascertain up to what degree a fresh negative must be printed.

Section XII.—The Chemical Action of Light, and the Pea-Sausage.*

In the campaign of 1870, the well-known pea-sausage was one of the most important articles of food for the army, and was prepared daily by thousands. The fabrication of the interior portion caused little difficulty, but the obtaining so many skins created much difficulty. As the supply fell short, a substitute was sought in vegetable parchment. This paper, which is produced by dipping blotting-paper in sulphuric acid for about a second, then washing and drying, is distinguished by its skin-like properties of resistance. It is impenetrable to water, and difficult to tear. It is therefore used for the production of bank-notes. It was attempted to make sausage skins of this paper, by doubling a sheet cylindrically and pasting it together. No glue or gum can however resist the effect of the boiling water in which the sausage has to be cooked, and so the artificial sausage skin fell asunder. Dr. Jacobson solved the problem by producing an adhesive substance, with the help of the chemical action of light, which could resist boiling water. He mixed the glue intended for the sausage skin with bichromate of potash, and exposed the glued parts to the light. This made the glue insoluble, and now the artificial skin endured boiling water thoroughly well. The number of sausage skins prepared in this way, by the chemical action of light, amounted to many hundred thousands.

* Erbswurst.

CHAPTER XVI.

PHOTOGRAPHY WITH IRON, URANIUM, AND COPPER COMPOUNDS.

Historical—Combinations of Iron—Action of Light on a Solution of Ferric Chloride—Ferric Chloride and Paper—Blue Iron Pictures—Iron-gold Pictures—Process with Salts of Iron—Iodine Pictures—Combinations of Uranium—Uranium Pictures—Their Development—Copper Pictures of Obernetter.

We remarked further back that the number of substances sensitive to light is much greater than appears at first sight; and in fact, on close investigation, it would probably be found that all substances are more or less sensitive. Even in the first period of photography, in the year 1840, Herschel observed the sensitiveness of salts of iron, Burnett that of salts of uranium, and Kratochvila prepared successful daguerreotypes on copper plates, in a manner analogous to that for silver plates. The latter process has been energetically cultivated, but hitherto without any important result.

It has long been known that a solution of ferric chloride, a yellow substance composed of chlorine and iron in ether, is bleached by light, the ferric becoming ferrous chloride, a colourless salt which contains less chlorine. The same change is produced in contact with paper;

thus, if clean paper be soaked in a solution of one part of ferric chloride in six of water, dried in the dark, and exposed under a negative, the yellow paper becomes white beneath the transparent parts of the negative, because the ferric chloride there becomes ferrous chloride. The faint picture thus produced may be easily coloured intensely dark by immersion in a solution of red prussiate of potash. This salt combines with the ferrous chloride to produce Prussian blue, but leaves the ferric chloride unchanged. In this manner a blue picture is obtained. If such a picture be plunged in a solution of gold, it becomes of a light blue colour, because the ferrous chloride produces a precipitate of metallic gold. And, similarly, all substances which form dark precipitates with ferrous chloride will serve to develop such pictures.

Another process consists in transforming the iron pictures into iodine pictures. A positive (for example, a drawing) is printed on a piece of paper sensitized with ferric chloride; the print comes out in yellow lines of unchanged ferric chloride, on a white ground. If this is now immersed in a solution of iodide of potassium and starch, the ferric chloride decomposes the iodide, and sets free iodine, which combines with the starch, forming the black-blue iodide of starch, and thus colours the lines of the picture.

There are several other methods of making the colour of the iron pictures darker. The pictures in Prussian blue gradually fade, for this dye is bleached by light (blue parasols rapidly lose their colour in the light). The same remark applies to pictures of iodide of starch; the gold pictures are too pale, and their preparation too costly.

The salts of uranium present the same phenomena as the salts of iron. Uranium itself is a rare metal, the salts of which are much used as colouring materials; thus, there is a yellow oxide which, when burnt into porcelain, colours it dark green, and fuzed with glass, imparts to it a beautiful grass green (uranium glass).

Two chlorides of uranium—uranous and uranic chlorides—corresponding in their composition and properties to the ferrous and ferric chlorides, are also known. The best known salt of uranium is, however, the nitrate, which is reduced by light to uranous nitrate in the presence of organic matter (for example, paper). If a piece of paper be immersed in a solution of one part of the salt in five of water, dried in the dark, and exposed under a negative, a very faint picture is produced, which consists of uranous oxide. If the print is now immersed in a silver or gold solution, the picture becomes at once visible, since uranous oxide precipitates gold and silver as such from their solution (silver as a brown, gold a violet powder).

Uranium is, however, too scarce and too dear to be employed generally in photography.

As can be perceived, the salts of iron and uranium are analogous to the salts of chromium, by only being sensitive to light in the presence of organic bodies. In a pure state, salts of uranium and iron do not change in the light.

The sensitiveness to light of salts of copper has hitherto only been studied very imperfectly. Copper forms with chlorine a green salt, soluble in water—cupric chloride,—which is reduced to cuprous chloride in the light. Obernetter took advantage of this fact, by

mixing chloride of copper and chloride of iron together, and saturating paper with them. This was exposed to light under a negative, then plunged in sulpho-cyanide of potassium, and ultimately treated with red prussiate of potash. The result produced by this somewhat complicated process was a brown picture.*

* See Vögel, "Lehrbuch der Photographie," p. 32. Berlin: Oppenheim.

CHAPTER XVII.

THE CHANGE OF GLASS UNDER THE INFLUENCE OF LIGHT.

Faraday's Observation on Manganese-glass—Change of Mirror-glass in the Light—Almost all Kinds of Glass are Sensitive to Light—Gaffield's Experiments—Disadvantages of the Change of Glass in the Light—Explanation of the Change of Manganese-glass—Action of Light on Topaz.

THE celebrated physicist Faraday made the observation that flesh-coloured glass, which is stained with manganese, became rapidly brown in the light. This fact remained for a long time isolated, until, years later, other observations of the same kind were made.

A very handsome plate of glass was exhibited in a mirror shop at Berlin. It bore the inscription "Spiegelmanufactur" in brass letters. After being exhibited for years, the business was broken up, and the mirror, on account of its beauty, was taken away by its owner, the brass letters were removed, and the plate cleaned. To the surprise of the proprietor, the letters remained plainly visible on the glass, notwithstanding all attempts to remove them. The surface was even ground away, but this did not produce any effect on the letters. It was found that the glass had become yellow throughout, and that it remained white only at the places where the opaque

letters had kept off the light. The plate of glass was cut into halves. One half, with the word "Spiegel," remains in the Physical Museum of the University of Berlin.

Some very interesting observations on the action of light on glass have been recently made by Gaffield, who finds that almost all sorts of glass are affected by light, and that in many cases an exposure of only a few days suffices to produce a change. Gaffield went systematically to work in his experiments. He cut the glass to be examined into two parts, placed one in the dark and the other in the light, and compared the two after a few days. In almost all cases he remarked that the colour of the glass became deeper on exposure to light. Two kinds only of German and Belgian green window glass were unaffected. The exposed glasses recovered their original colour on being heated to redness.

This alteration of glass by light has a most injurious effect in photography. The yellow tinge, which the glass gradually assumes, absorbs a part of the chemically active light. This absorption makes itself strikingly evident, because the time of exposure for photographs must be continually lengthened.

The greatest change is produced in glass containing manganese. Peroxide of manganese, or black manganese, is frequently added to glass to bleach it. The oxygen of the peroxide converts the dark-green ferrous oxide contained in the glass into the lighter ferric oxide. In the light the converse reaction takes place. The ferric oxide is reduced to ferrous oxide, the oxygen combines again with the manganese to form black manganese, and thus the colour of the glass becomes deeper.

In many minerals the opposite effect to that in glass

is produced on exposure to light; their colour becomes paler instead of deeper. This is the case with the Siberian topaz, which soon loses its golden-yellow colour in the light. A splendid crystal of topaz, six inches long, belonging to the Mineralogical Museum at Berlin, has in this manner lost much of the beauty of its appearance.

CHAPTER XVIII.

PHOTOGRAPHY IN NATURAL COLOURS.

Observation of Seebeck and Herschel—Bequerel's Coloured Pictures on Silver Plates—Researches of Nièpce—Effect of Black Colours—Coloured Pictures on Paper of Poitevin and Zencker—Want of a Fixing Medium for Coloured Photographs.

PHOTOGRAPHY has already achieved grand results: but it has still one problem to solve—the production of photographs in natural colours. There are plenty of coloured photographs to be seen, but in such cases the colour has been added with the paint brush; it is a kind of *retouche,* which in most cases does not improve the picture. By photography in natural colours, however, we mean the production of pictures in the colours of the original object by light alone. Numerous experiments in this direction have been recorded. Some attempts to prepare coloured pictures by the chemical action of light have indeed been successful, but such pictures are rapidly destroyed by the same agent to which they owe their formation. No means of fixing coloured photographs has been discovered.

The first attempts to make coloured photographs date a long way back. Professor Seebeck of Jena, as early as

1810, found that chloride of silver, when exposed to the solar spectrum, became coloured in a corresponding manner. This observation, published in Goethe's "Farbenlehre," ii. p. 716, passed unnoticed, until, in the year 1841, after the discovery of the daguerreotype, experiments in the same direction were made by the celebrated Sir John Herschel. He took paper saturated with chloride and nitrate of silver, let a powerful solar spectrum fall upon it, and obtained immediately, like Seebeck, a coloured image of the spectrum, agreeing, however, only imperfectly with the original. Bequerel was more successful. He ascertained that the solution of nitrate of silver in Herschel's experiments had a disturbing effect, and he worked with chloride of silver alone. He employed silver plates, which he plunged in chlorine water. A white film of chloride of silver was thus formed on the plates, and, on exposure to the solar spectrum, an image was obtained, the colours of which agreed very closely with those of the spectrum. Bequerel observed that the duration of the action of the chlorine water was very important, and he preferred at a later date to chlorinate the plates by the galvanic current. For this purpose he suspended them in hydrochloric acid from the copper pole of a galvanic battery (see p. 221). The current decomposed this acid into chlorine and hydrogen. The chlorine passes to the silver plate, and forms chloride of silver. This method enables the operator to produce a film of chloride of silver of any thickness, according to the duration of the current. The brownish subchloride of silver is thus produced, and this is chiefly sensitive to coloured light. This sensitiveness is, however, not great: it suffices to fix a powerful spectrum, but it requires a very

long exposure to obtain pictures in the camera obscura; and all such pictures, unfortunately, darken in the light. Bequerel found that the sensitiveness was increased by heating the plates. This observation was turned to account by his successor, Nièpce de St. Victor (the nephew of Nicophore Nièpce, see p. 9), who made numerous attempts from 1851 to 1867 to produce coloured photographs, accounts of which he communicated to the Paris Academy.

He worked, like Bequerel, with silver plates, which he chlorinated by immersion in a solution of the chlorides of iron and copper, and then heated them strongly. He thus obtained plates which appeared ten times more sensitive than Bequerel's, and allowed him to copy in the camera obscura, engravings, flowers, church windows, etc. He relates that he not only obtained the colours of objects in his pictures, but that gold and silver retained their metallic splendour, and the picture of a peacock's feather the lustre of nature.

Nièpce de St. Victor introduced a further improvement, by covering the plate of chloride of silver with a peculiar varnish, consisting of dextrine and a solution of chloride of lead. This coating made the plate still more sensitive and durable. At the Paris exhibition of 1867, Nièpce exhibited various coloured photographs, which lasted about a week in a subdued daylight (they were shown in half-closed boxes).

Among these pictures were a couple of black pictures on a white ground, which had been copied from copper-plate engravings. These excited great interest, and justly so, because in these pictures the darkest parts of the object had apparently produced a stronger effect

upon the plate than the lighter or perfectly white parts. This is, of course, the exact opposite of what takes place with ordinary photographic paper, where the darker parts come out light, and vice versâ. This production of black by black can only be explained by assuming that the black is actually not black, but that it reflects ultra-violet light invisible to the eye. (See p. 58.)

Since Nièpce, who died in 1870, the only persons who have paid attention to coloured photographs are Poitevin at Paris, Dr. Zencker * at Berlin, and Simpson in London. The two former investigators have reverted to the older process, as employed by Seebeck and Herschel, *i.e.*, they prepared pictures on paper, only the preparation of this paper was peculiar. Paper saturated with salt was made sensitive in a solution of silver, like the photographic positive paper (see p. 50), then washed to remove the solution of silver, and afterwards exposed to the light in a solution of subchloride of tin. By this means violet subchloride of silver is formed from the white chloride of silver. The subchloride of tin only operates as a reducing medium. This paper is in itself little sensitive to coloured light; but if it be treated with a solution of chromate of potash and sulphate of copper, its sensitiveness increases considerably, so that it is easy to copy with it transparent coloured pictures. Nevertheless, the colours are never so vivid as in the original, the red tones showing themselves the strongest. After printing, the pictures are washed with water, to make them less sensitive to light. In this condition they showed tolerably well in a subdued light, but no means

* Those who take a special interest in the matter are referred to Dr. Zencker's "Lehrbuch der Photochromie." Berlin, 1868.

have been found hitherto to make them perfectly durable. Hypo-sulphite of sodium (see p. 27) cannot be employed, as it destroys the colours directly. We must hope that future investigators will succeed in supplying this deficiency. The first attempts in uncoloured photographs also failed for want of a fixing medium (see p. 6), which was only discovered seventeen years later by Herschel.

CHAPTER XIX.

PHOTOGRAPHY AS A SUBJECT TO BE TAUGHT IN ART AND INDUSTRIAL SCHOOLS.

Importance of School Photography—Its Use for Technical Institutions—Photography as an Object to be taught in Art Schools and Universities.

THE previous chapters prove how manifold are the applications of photography. It has entered into art, science, industry, and life as a new kind of written language. Photography is to form what printing is to thought. Printing multiplies what is written, photography what is drawn; nay, more, it draws automatically by chemical means. No doubt a certain technical experience in the art is required, which can only be gained by practice; but it is easy to learn, and the time cannot be distant when it will be taught as an extension of drawing in all industrial schools. Years are devoted to the study of the art of drawing, of piano playing, and other things; a course of instruction lasting half a year would suffice to teach photography.

The author has been for nine years professor of photography in the Royal Industrial Academy* at

* Gewerbeakademie.

Berlin, the only technical institution in Germany where photography has as yet obtained a place in the course of study. It is by no means the object of this institution to train professional photographers; it only admits photography so far as it is of importance for art and science.

Practical instruction is given in this institution in the positive, negative, and other processes of photography, namely, with special reference to their use for the reproduction of drawings and for taking pictures of machines and buildings. Other institutions are still hesitating about admitting photography. The importance of the matter is still depreciated; what is new is viewed by many as inconvenient. We cannot avoid introducing, in connection with this, a passage from a work recently published, "Photography as a Subject to be taught in Industrial Schools," by Professor Krippendorf of Arau. The author says:—

"Industrial schools are founded for the special purpose of preparing pupils for a life in one of the branches of art or industry, and special attention is therefore paid to such arts and sciences as are likely to be most useful, and first of all to drawing and natural philosophy.

"Industrial training must not only take into consideration that these subjects form a complete system, taking the place of the classical languages as a basis of general culture, but it must also draw into its system the new inventions and discoveries of science, in order to win new standpoints to react with more advantage on practical pursuits.

"Now, amongst such subjects which have advanced the most rapidly in the last ten or twenty years, stands

photography. This art is a genuine product of science, and not merely the result of a lucky change. It has the great merit of having been first conceived as an ideal, and then practically carried out. It is therefore an art full of value in itself, based on science, and one whose productions delight and are gladly viewed by all, extending the knowledge of pupils, and giving an idealizing tendency to young minds.

"There is scarcely any other subject in which it is a downright necessity to keep in view an independent observation of the result. Physics and chemistry are taught as results of successful experiments, and give no clue for the detection of the source of errors. The pupil only observes what the teacher puts before him, and both are satisfied if the law is found in the experiments. The methods of observation cannot be thus properly learnt, and yet this is specially fitted to sharpen the judgment. But if photography is admitted in the school course, we gain a subject which fixes the attention of the pupil in a way that no other can do. The study of photography depends principally on learning to avoid the sources of error, and their origin—a further argument for its introduction in such schools.

"If we turn to the outside of the art we meet with many other grounds in its favour.

"Art and science are learnt in technical schools for practical ends. A knowledge of drawing is specially demanded on entering the engineering profession. It may even be affirmed, of two equally talented and diligent pupils, the best draughtsman will take the first place. Drawing is the centre of gravity for most

technical professions, and for this reason alone technical and freehand drawing ought in no case to be neglected. But photography is destined to support these technical studies, as it is also a mode of drawing. Indeed, if it be proposed to draw a complicated machine—as a weaver's wheel—in a few minutes, photography is the only means of doing this. The labour, otherwise requiring weeks, is reduced to an affair of a quarter of an hour, and is so perfectly done that all proportions are duly observed, and the projection must be correct from whatever point it is taken, if proper lenses be used.

"If we follow the biography of gifted pupils, we often trace them, aided by Government stipends, going first on distant journeys to study modern and ancient buildings, and bringing home as faithful designs of them as possible. What a severe labour this implies for the architect, amidst a foreign population, in a trying climate, who has to make faithful sketches in a short time amidst countless obstacles! On the other hand, how it is all abridged by photography! What would not the young travelling engineer give to take plans of entire manufactories which he has only a few minutes to view? What would not the highly cultivated philologist give to retain for himself and others, in a durable form, the overpowering impressions of life in the past, which he can only feel as a transient emotion, on the classical ground of Greece and Italy? It is our duty to announce publicly, that all these wishes have become a possible and a tangible reality through the progress of photography, and that the practice necessary to effect this is easily attained."

Krippendorf omits here an important point, which is, the great value of photography to those who are devoted

to practical typography, whether it be lithography, book printing, copper-plate printing, printing of paper money, porcelain manufacture, or dyeing; for in all these branches the aid of photography is very important. We refer to the chapters on pyro-photography, heliography, and chromo-photography. In these branches we see photography as an auxiliary to the multiplying arts.

Though it has done great things in this connection, we see very few heliographers and photo-lithographers. The reason of this is found simply in the fact that art schools, training lithographers and copper-plate engravers, entirely overlook photography. It is set aside as no art at all by persons who feel themselves artists, yet to whom it would be useful. But in the before-mentioned alliance of photography with lithography and metal-plate printing, good results can only be achieved by the operator being equally skilled in both arts. The author has often witnessed the failure of heliographers, lithographers, and photographers who tried to work by combining the two arts. It is therefore necessary that the schools of art should take the matter in hand, and if so, a new subject, the Albert-type process, hitherto unknown to the lithographer (see p. 243), must soon become domiciliated in those institutions.

But a knowledge of photography is equally important for painters. The photography of oil-paintings has undergone a great development of late years. Adverse opinions of it are indeed uttered by strict art critics, such as Thansing, just as idealistic tourists formerly ranted against railways, because travel was thereby robbed of its poetry. These people were right from their point of view, but they could not stop the introduction of rail-

ways; and, though travel may have become less poetic, railways have the advantage of giving an opportunity to persons of slender means of making excursions, and thereby enriching their minds with a knowledge of foreign countries and people, and of improving their health. Photography affords to persons of small income similar advantages in the province of art. Paintings, too expensive to be purchased by any save the rich, became slowly and imperfectly known to others by the expensive medium of copper-plate engravings. These engravings were also confined to a limited circle. But now photography reproduces with the rapidity of lightning, and with perfect accuracy, the latest creations of art, whilst its cheapness makes them accessible to all. The copy is not so artistic as that of the engraver, but it suffices to bring all that is new quickly to the knowledge of all, and in spite—or in consequence rather—of this, the engraving coming after still retains its value.

The negatives from oil-paintings, however, require retouching, in order to equalize the false effects produced by colours. This *retouche* may be very injurious if carried out by unskilled hands. The most suitable hand is that of the painter who painted the original. Good painters have already successfully worked at reproducing negatives from their own originals, and the impressions from plates retouched by the artists themselves must evidently have a much higher value than those emanating from other hands. This presents a new field for the artist; but it can only be worked with good results if the art pupils have become familiar in art schools with the technical routine of negative retouching, and with taking positive impressions from them.

In conclusion we add a few words on the education of the professional photographer.

We have already shown that if portrait and landscape photography are to produce really solid results, they require a knowledge of the principles of art. But hitherto nothing has been done to train photographers artistically. Moreover, photography can only be raised, in an artistic point of view, when art schools render a study of art possible to the photographer. The time must be at hand when all small jealousy directed against photography must fall to the ground. Experience has already found that it is not a rival but a handmaid to the well-trained artist.

Photography can be the more readily introduced in schools, as its tuition requires much less time than drawing, the results of which are often out of all proportion to the time spent in learning. Four hours a week for six months suffice to train a pupil in photography to enable him to go on by himself, even without a knowledge of chemistry.

Schools of science, as well as of art, must also attend to this subject, because photography is very useful as an aid to natural science.

This new art gives beautiful illustrations for science and art lectures by the magic lantern. The investigator can by its means give faithful original pictures of the results of his labours (see page 93). Hitherto proper apparatus was wanted; the magic lanterns sold in Germany gave imperfect images. Latterly, R. Talbot, in Berlin, has introduced American magic lanterns, which are best adapted for lectures.

The Woodbury press has been joined to the above for

the illustration of lectures; and the latest improvements in dry plate photography have had the result that dry plates, like *lichtpaus* paper, have become articles of trade, making the production of photographs much more easy. Thus one improvement combines with another to make photography what it ought to be—a universal art of writing by light!

CHAPTER XX.

THE LATEST IMPROVEMENTS IN PHOTOGRAPHY DOWN TO 1883.

NEARLY ten years have elapsed since this book was first published, and they have been marked by some progress in photography. New and interesting processes have been introduced; others, which were defective, have been perfected; while others, again, which were hailed hopefully, have failed to fulfil their promise. But, in spite of these changes, the fundamental principles of photography remain unmoved. The negative and the positive processes constitute the basis on which the combination of photography and printing from stone or metal must rest. We may, therefore, consider the principles already laid down as fully established.

SECTION I.—NEW DEVELOPMENTS OF THE LICHTPAUS PROCESS.

Since the first edition of this book, the *Lichtpaus* process has undergone very great improvements. The costliness of paper prepared with silver led to further care being given to the cheaper process of aniline printing (see p. 238). This, however, was not always to be relied upon. Engineers have met with better success with the "blue process," or cyanotype, which is easier to

manage, and is an improvement on Herschel's process with ferric chloride (see p. 257). In one hundred parts of water dissolve eight parts of red prussiate of potash and ten parts of citrate of ammonia. A fluid is obtained which remains unaltered in the dark, and becomes bright blue by exposure to the light; the red prussiate of potash is reduced to yellow under its influence, and the iron chloride is precipitated in the form of Turnbull's blue. If paper is treated with the unaltered solution by artificial light, and left to dry, when it is subsequently exposed to daylight under a drawing, a white reproduction on a blue ground is the result, which only needs washing to render it permanent. This process is analogous to that described on p. 28. Positives cannot well be obtained from these blue *Lichtpaus* negatives, because the blue ground does not effectually intercept the chemical rays of light. It has also this disadvantage: that the paper is three times less sensitive than when sensitized with silver, so that in winter, under a dull light, the process is a long one. But it is the simplest in practice of all the *Lichtpaus* processes.

Another, and somewhat more elaborate one, gives a positive from a positive. This process was perfected by Pizzighelli.* Paper is sensitized by applying a mixture of gum arabic with citrate of ammonia and a solution of ferric oxide; when dry, it is exposed to the light under a positive till the lines are faintly visible as light on a darker background. The copy is then washed with a solution of yellow prussiate of potash, and a bright blue positive appears, which can be rendered permanent by

* See "Anthrakotypie und Cyanotypie," Pizzighelli (Vienna: pub. by the *Photogr. Correspondenz*).

washing with hydrochloric acid diluted with nine tenths of water.

Section II.—The New Emulsion Dry-Plate Process.

The most interesting development which has taken place in the last ten years is in the negative process. Dry plates are now prepared for negatives far superior to the wet plates formerly in use, and yielding results at least equal to these; so that, in fact, dry plates, which were of value only to the landscape-photographer, have now become indispensable even for studio-work. Nor is this improvement of less value in the application of photography to scientific purposes.

The first step towards perfecting dry plates was taken by Carey Lea. He found that the preparation of dry plates could be essentially simplified by producing the sensitive salts of silver in the collodion itself. He also found that bromide of silver gave more sensitive dry plates than iodide of silver, when a different developer was used. His mode of preparing dry plates depended, therefore, on the production of bromide of silver in collodion. He dissolved bromine salts in collodion, added a solution of silver, and thus produced silver bromide, which remained suspended in the glutinous medium, forming what was termed the *emulsion*. The superfluous salts were removed by washing with pure water, after the mixture had been left to dry in shallow saucers. This film, after being again dried, was dissolved in alcoholic ether, and gave a pure emulsion which dried instantly on the plates. The sensitiveness of these dry plates was about one-fourth as great as that of a wet iodized collodion plate.

The process of developing these dry plates, however, is different from that described on p. 113. They are not developed by precipitating silver which adheres to the exposed spots, but by a process of reduction acting directly on the exposed portions of the bromide of silver and reducing it to metal. This is effected by washing with a very powerful reducing agent, such as pyrogallic acid mixed with ammonia (known as the alkaline or chemical developer), or by potassio-ferrous oxalate.

This emulsion process with bromide of silver was an important step; still, the sensitiveness of the plates thus obtained was not high enough for them to compete successfully with the wet plates. This was not achieved till a new vehicle was adopted for the application of the bromide of silver — namely, gelatine. By dissolving gelatine and bromide of potassium in warm water, and adding a solution of silver, bromide of silver is formed, which remains suspended in the mucilaginous fluid. This, when cold, becomes rigid, and can then be cut up and washed with cold water to remove the superfluous salts; warmth again dissolves it, and it is applied to the glass plates in a horizontal position. The film soon sets, but it takes much longer to dry than a collodion film; twenty-four hours, or more.

This process would scarcely have excited any attention as compared with the use of collodion, but that it was discovered that the sensitiveness of these plates under certain conditions was as great as that of wet plates, and that this sensitiveness of the gelatine emulsion could be greatly increased simply by long warming. In fact, plates thus prepared were more than ten times as sensitive as collodion plates. This, which was discovered

by Bennett in 1878, soon made gelatine plates extremely popular.

The unlimited permanence of dry plates prepared by this method allowed of their being manufactured in large quantities, at first in England, but latterly on the Continent also. There are two establishments for making them at Berlin, and others at Frankfort-on-Maine, Cologne, Munich, etc. Many photographers prefer to buy the plates ready prepared rather than undertake the troublesome task themselves. To the amateur, these ready-prepared dry plates are, of course, invaluable; they relieve him of the manipulation—not always successful—of the collodion, and of the silver bath, unclean at the best, of the labour of cleaning the plates, etc.

Great as the merits are of the gelatine plates, they have this disadvantage, as compared with the collodion plates—of being slower and more troublesome to develop, and more difficult to intensify, fix, and wash; and in hot weather the picture is apt to float off.

The sensitiveness of the gelatine, however, amply compensates for these defects, since it allows the photographer to work under a very unfavourable light, which would render the use of the old wet plates impossible. Various attempts have, indeed, been made to remedy them by combining collodion and gelatine to form the emulsion. The author himself endeavoured to do this by dissolving the dried gelatine emulsion in acetic acid, and mixing it with collodion. This preparation is permanent, and, when applied to the plates, dries as quickly as collodion; it resists the action of hot water, and is easily and quickly fixed and washed. It would be better still if means could be found of combining pure collodion

(without gelatine) with bromide of silver. This problem still remains to be solved.

The investigations of Stas, Monckhoven, Abney, Eder, and the author, have proved that bromide of silver occurs in at least two conditions, one of which is less sensitive and is most affected by the indigo rays of the spectrum (indigo-sensitive), while its sensitiveness is but slightly enhanced by warming; and a second, which is most affected by the blue rays (blue-sensitive; see p. 65), and of which the sensitiveness is greatly increased by warmth. The second condition of bromide of silver forms only in aqueous solutions; the first only in alcoholic media, like collodion; and the blue-sensitive is very reluctant to combine with collodion.

Another, and even greater, advantage of the sensitive form of bromide of silver present in the gelatine plates is that it preserves the light-picture—the photograph—for a very long time unaltered, whereas it gradually disappears from the collodion film. Gelatino-bromide plates can be kept for years after exposure before they are developed, and the rapid traveller who uses photography as a record of his observations is spared a considerable amount of time and labour. In working with dry plates on a journey, all that is requisite is to be able to change the exposed plate rapidly and safely for one that has not been exposed in the dark case. This change must be effected in a dark room, or a room lighted with a reddened light.

Red light, which can easily be obtained by the use of a ruby lamp-glass, does indeed act on these plates, but so slowly that the exchange and the development of the picture is rendered possible. It is difficult, however,

when travelling, to be sure of finding a dark room suitable for this exchange It is customary, therefore, to have a separate dark slide for each plate. If the traveller has a dozen, say, of dark slides, each with its plate, and a sufficient reserve of prepared plates, these twelve, after exposure during the day, can be changed at night, when the whole world is a darkened chamber.

The carriage of even twelve slides is, however, a matter of some difficulty, so changing cases have been devised to contain a dozen or more dry plates, which can be drawn out through a slit in a sliding lid and slipped into a dark slide adjusted to the slit, and constructed to shut instantly. Thus they are not exposed to the light at all. After exposure, the plate is restored to the case in the same manner.

It would be better still if the use of glass plates could be entirely avoided. Attempts have been made to apply gelatine emulsion to the surface of paper, to be kept rolled up in a dark box, and unrolled by some contrivance which will bring successive portions of the roll into position for exposure. The mechanism has not yet been made to act with sufficient precision to be used in travelling with any confidence; besides, the paper back is fatal to the further use of the negative. Better results may be hoped for from experiments in applying the emulsion to the surface of tough transparent sheets of collodion or gelatine.

The method of working with the new emulsion plates is easily deduced from the foregoing description. The plates, after exposure in the camera, are developed in the dark room under a red light. The bath contains a strong reducing fluid; either a mixture of one part of saturated

solution of ferrous sulphate (green vitriol) and three parts of saturated solution of oxalate of potassium, or a very dilute solution of pyrogallic acid (1 : 500), with from ten to twenty drops of ammonia. These agents reduce the bromide of silver that has been acted on by the light to black metallic silver, and reveal the picture; it is not till later that they begin to act on the bromide of silver that has not been touched by the light, and this leads to a general fogging of the plate. To prevent this, a "restrainer" is added; *i.e.* a small quantity of bromide of potassium dissolved in water. When every part of the picture is visible, the plate must be washed, dipped in a bath of saturated solution of alum to harden it and make it water-proof, and then fixed; that is to say, the bromide of silver must be removed by soaking in a solution of sodium hyposulphite. After this, much washing is needed to get rid of the superfluous sodium solution.

If the picture is now too feeble, it may be intensified after it is washed. The process, however, is different from that applied to wet plates (see p. 44). The ordinary silver intensifier is not available with gelatine plates, as it is too liable to produce spottiness; it is usual, therefore, to intensify gelatine pictures with mercuric chloride. This parts with some of the chlorine, which combines with the greyish-black silver of which the picture consists, forming a silver sub-chloride. After intensifying, the plate must again be thoroughly washed. When it is dried and varnished it can be used for printing from (see p. 50).

Section III.—Platinotype.

Many attempts have been made to supersede the silver process described at p. 50 by some other which may be less costly, and by which pictures may be produced better able to resist sulphur vapours. These efforts were first directed to improving the pigment-printing described on p. 233. The principle remains the same, but instead of transferring the picture to zinc, it was applied to glass coated with collodion, or to paper with a film of gelatine. The process gained in certainty, and the pictures were more artistically beautiful than those taken with silver, but they did not lead to the hoped-for results; for, though they were more stable chemically speaking, they were more liable to mechanical injury by rubbing or from the effects of damp. Occasionally, and especially in Belgium, the pigment process was employed in portrait-studios; hardly ever in Germany.

More recently, however, another attempt, made by Willis, has brought platina-printing into notice, and it would seem that it is likely to become popular, particularly with amateurs. The pictures it gives are unglazed and pure black and white, so that they have the appearance of copper-plate engravings rather than of photographs; the process is comparatively simple. The material used is paper saturated with platino-chloride of potassium and ferric oxalate, which is sold ready for use, and may be kept for a long time if damp is excluded; it is preserved in tin cases, with chlor-calcium to absorb all moisture. This lemon-tinted paper is exposed under (or through) the negative. A pale picture is printed off, which becomes strongly intensified by im-

mersion in a hot solution of neutral oxalate of potassium. Light has reduced the ferric oxide to an insoluble ferrous oxide, which, under the developing treatment, is dissolved by the oxalate of potassium; and then the platina salt already acted on by the light is reduced to a black platina powder. The developed prints only need washing in water to remove the salts, and the process is complete. These pictures resist the vapour of sulphuretted hydrogen; they do not turn yellow; and the surface is not so easily injured as that of pictures produced by the pigment process, which ought to be a great recommendation for photographs viewed as documents to be preserved as records.

A third process of reproduction by the use of gelatino-chloride has been elaborated by Dr. Eder, to whom photography owes so much, but it has hitherto not come into extensive practice.

Section IV.—Photography by Electric Light.

Until lately, photography was entirely dependent on natural light. The artificial lights described in Chapter VIII. were too costly to produce, and too inconvenient in practice to find general acceptance. This is still the case, indeed, as regards the magnesium light; but it is different with the electric light.

The application of electricity has of late been widely extended. The dynamo-electric machine has proved a real fount of electricity; by its means the powerful electric current which is indispensable to the production of the electric light can be generated at a small cost by machinery—gas or steam.

Van der Weyde, the photographer of the upper ten

thousand in London, was the first to use the "dynamo" for purposes of photography. A Siemen's machine placed in the cellar of his house in Regent Street, and driven by a gas-engine, supplies him with a galvanic arc with the illuminating power of more than four thousand candles.

Fig. 95.

The direct rays of this blinding light are not, of course, applicable to portrait-taking; the muscles of the face would involuntarily contract, the eyes be screwed up, and black, sharp shadows would give a spotty effect

throughout. Van der Weyde obviated these defects by excluding the direct rays, and illuminating the figure of the sitter by a reflected light from a hemispherical reflector, in which the electric light is placed. Fig. 95 shows the arrangement of a photographer's studio fitted with the electric light. The reflector A is suspended by a contrivance which allows of its being turned up or down, and to the right or left. The electric light is within, at R. Close in front of the light is a small metal screen, which keeps the intense direct rays from falling on the sitter. The figure is only illuminated by the moderated light from the reflector. The reflector is five feet in diameter, and the extent of the reflecting surface obviates the production of sharp black shadows; reflecting screens are also adjusted to illuminate the shadows.

It has thus been possible to dispense entirely with daylight in taking portraits; and this brings with it the additional advantage that the photographer need not construct his studio on the roof, but can make use of any room or cellar, even without a window, for taking portraits.

The management of electric lighting requires special skill, or the picture will be flat and toneless. Van der Weyde has proved, however, that portraits can be taken by it in no respect inferior in beauty to heliographs, and, in fact, not to be distinguished from them even by connoisseurs. Some interest was excited, a few years since, by a statement in the London papers that the Prince of Wales had gone, after the opera at midnight, to sit for his portrait at Van der Weyde's studio.

The electric light has been applied to the purposes of photography in Russia, and especially at St. Peters-

burg, as well as in England. The long northern winter, with only five and a half hours of daylight on the shortest day, makes such an auxiliary very important. It was employed there with great success some few years since by the court photographer, Levitzky, and his portraits of the imperial family which are current in the trade were all taken by the electric light. There is a studio for electric photography in Berlin.

In the south, where the skies are clear and the daylight pure, the electric light is not so necessary an adjunct; hence few photographers have as yet gone to the expense of the necessary apparatus. Its use will, however, no doubt, become general as soon as electric wires are laid through our streets to supply electricity from centres of generation for lighting, motor power, and chemical purposes (electrotype), so that photographers need not be at the expense of working their own electrical machinery.

SECTION V.—PHOTOGRAPHY AS A MEANS OF SCIENTIFIC INVESTIGATION.

The application of photography to astronomy has been greatly extended within the last few years by the introduction of dry plates. The hopes that were entertained of its utility in observing the transit of Venus (p. 191) have not, it is true, been fulfilled. The undulations of the atmosphere give rise to a tremulous motion of the image in the telescope, which resulted in strange irregularities of form, particularly at the contact of Venus with the sun, so that the pictures were useless for very delicate measurement. The exactitude required was within $\frac{1}{1000}$ of an inch. Hence no more precise results were obtained from photographic pictures of the transit

than from ocular observation, and for the latest transit, in 1882, the use of photography was reduced to a minimum.

For daily records of the sun's face, on the other hand, photography is now constantly employed, particularly by the celebrated Professor Janssen, of Paris, who has produced some marvellous magnified images of the sun, showing the minutest details of its structure. In the same way, photography has proved valuable in recent eclipses, not only in recording the forms of the protuberances and the corona (see p. 179), but also in revealing their spectrum. It has led to the detection of the hydrogen lines and of Frauenhofer's lines in the corona, and of new constituents in the protuberances (see pp. 62, 177).

A more difficult task than these is the portraiture of very faintly luminous bodies, such as comets and nebulæ; these, in fact, could not be photographed till the highly sensitive dry plates had been discovered. By them, Janssen, the illustrious director of the photographic department at the Meudon observatory, near Paris, succeeded in taking a photographic image of the second comet of 1881 (distinguished by astronomers from the first of that year by the letter *b*). How feeble the light of this comet was, may be understood from Janssen's statement, that its illuminating power was three hundred thousand times less than that of the full moon. Fig. 96 is a woodcut from Janssen's photograph.

The sensitive plate gives not only the picture of the comet, but that of the fixed stars in the vicinity. It reproduces even the faintest, invisible to the naked eye, including several which had till now escaped observa-

tion, and which are included in no catalogue of the stars.

But even the spectrum of these pallid objects has with much difficulty been obtained; with difficulty, because of all the light sent to us by those remote bodies only that very small portion can be dealt with which can pass through a slit in the metal screen of the spectroscope (see p. 190).

Fig. 96.

The fixed stars yield not bright lines, but dark ones, like our own sun. But the dark lines of these suns, distant from us billions of miles, often differ widely from those of the spectrum of our sun. The observation of such spectra presents great difficulties in consequence of the comparatively feeble light they send to the eye; and here photography is a valuable assistant in defining the lines. Photography, it is true, only gives a record of the

red and yellow lines under certain favourable conditions, but it shows very distinctly the lines in the blue, violet, and ultra-violet * portion of the spectrum.

Huggins, the English astronomer, was the first to attempt to photograph the spectra of the stars by an exposure of some hours; and to his great surprise he detected in the spectrum of Sirius not only the hydrogen lines I., II., III. (see Fig. 97), but a number of lines at the violet and ultra-violet end never before observed (IV., V., VI., and VII. in Fig. 97); nor was it known to what metal they could be referred. At the same time, however, the author was giving his attention to the photographic image of the spectrum of incandescent hydrogen, and



Fig. 97

detected the lines marked in Fig. 97 as *a*, *b*, *c*, *d*, and, besides these, a series of hydrogen lines, invisible to the eye, marked *e*, *f*, *g*, *h*. Accurate comparison showed that these occupied the same positions as the new lines in Huggins's star-spectra, and proved that they must belong to hydrogen.

Huggins has lately succeeded in imaging the spectrum of the feeblest nebulæ and of Wells's comet. In this, certain mysterious lines were detected which are not as yet accounted for.

Instantaneous photography could not fail to derive

* The portion of the spectrum beyond the violet end which is invisible, or scarcely perceptible to the eye.

impetus from the introduction of the highly sensitive gelatine plates. Not only are they convenient and easy to work with; they made it possible to obtain instantaneous images even under an unfavourable light, giving them in detail instead of as mere silhouettes. Attempts to photograph flying birds even proved successful. Marey, of Paris, constructed a "photographic pistol" for this purpose. It is simply a photographer's camera of somewhat peculiar form, resembling a revolver. The object glass is in the barrel, and a small sensitized plate is adjusted in the revolving chamber. If the instrument is

Fig. 98 and 99.

pointed at a flying bird and the spring pressed, a mechanism is released by which the revolving chamber turns once round in a second of time, in twelve distinct jerks; and at each of the twelve pauses a spring-shutter opens for $\frac{1}{700}$ of a second. This is enough to produce an image of the flying bird on the highly sensitive gelatine plate, which thus records twelve succeeding positions of the wings: these are of great value in the study of wing-action. The pictures are, of course, minute, but photography enables us to make enlargements of such minute images with the greatest ease. Figs. 98 and 99 are examples of these enlargements.

The instantaneous photographs of horses in movement by Muybridge, of San Francisco, done in 1879, were executed not with dry plates, but with wet plates under particularly favourable conditions of daylight.

Section VI.—Book-Illustration by Photography.

The most important recent development of photography as applied to metal plates for printing is the process known as *phototype*, by which plates with the lines in relief are produced for printing with letter-press (see p. 219). These have undergone many improvements since this book was written, so that it now seems possible to produce plates in relief from any negative, and special drawings are no longer needed for illustrative reproductions of this class.

Two processes which have attracted considerable attention are those of Meisenbach, of Munich, and of Ives, of Philadelphia. Meisenbach first prints off a positive on glass in the ordinary manner from the negative. Over the positive he places a transparent glass plate covered with a more or less close network of fine engraved lines, and takes off a new negative from the two plates by transmitted light. In this the half tones are broken up by the network of lines and appear as minute points, having much the same effect as an ordinary woodcut. This negative is copied on to a zinc plate covered with asphalt (see p. 248), on which a positive is produced. On this acid is poured, the asphalt protecting the metal so that the zinc remains untouched under the shadows, while the lights are eaten away. The result is a plate in relief suitable for printing in text.

Ives's process is somewhat different. So far as it is

known, it consists in preparing a photo-relief with hot water (see p. 228), and taking off an impression in wax; this is covered with fine cross-hatching by a tool for the purpose (a sort of engine-turning), engraved, and cast in copper by electrotype process. The shadows are broken up by the cross-hatching. Fig. 100 is printed from one of Ives's plates.

Fig. 100.

Besides these processes, plates in relief are frequently produced by photography from drawings. Copies are taken of the negatives, on zinc coated with asphalt, and then etched. Angerer and Göschl, of Vienna, have lately simplified the method of producing drawings for reproduction, by introducing a coarse-grained (or toothed)

paper, which gives a broken surface to the shadows when worked with black chalk. The catalogue of the Berlin Art Exhibition of 1883 contains many examples of prints by this process.

Photogravure.

Woodbury's process (see p. 229) has given rise to a very interesting copper-plate process, which for beauty of results has thrown all other heliographic experiments into the shade; in the reproduction of oil pictures especially it is unrivalled. It is know as photogravure. It was discovered by Woodbury himself in 1867, but was brought to its present height of perfection by Rousselon, the head of the department to Messrs. Goupil and Co., the publishers, of Paris.

The plates in relief prepared by Woodbury's process cannot be used with ordinary printing ink (see p. 230). The incised lines are too smooth to hold it well; they lack roughness, or "tooth," as it is termed. Woodbury tried to produce the necessary roughness by mixing finely powdered glass with the gelatine, and this, treated by the process described on p. 230, gave a roughened relief. A cast taken by electrotype gave an incised copper plate with rough or toothed lines, which could be printed from with ordinary printing ink. The minuter details of the process have not been made public. Beautiful pictures, resembling mezzotint in effect and tone, are produced by it and sold at a very moderate price, cheaper than silver prints.

Goupil has recently combined this process with printing in colours, in imitation of old English prints from copper plates. For this purpose he uses thin metal

stops to cover the plates while each colour is put on by a roller.

For instance, if green is to be printed off, every portion of the plate that is not to print green is stopped out with a metal plate; the same is done for red, blue, yellow, etc. When the plate has been under all the rollers with a different stopping-plate for each, the picture is printed off. Goupil has brought out a number of reproductions of oil pictures by this method, and some—but not all—are good and effective.

Klic (of Vienna), the Photographic Society (of Germany), and Rud. Schuster, of Berlin, have endeavoured to achieve similar results in photogravure, and by a simpler method, by exposing a copper plate coated with chromium, and then etching it. The details of the process, called by Schuster (of the firm of Lüderitz) photo-copper etching (*Lichtkupferätzung*), are not known; but it has already led to interesting results. The advantage of etching is that the process is much more rapid than electrotype.

INDEX.

Accuracy of Photographs, 117
Aden, Eclipse of the Sun, 171
Æsthetic Defects of Photographs, 21
Albert, 236
Albert-type, 236
Albumen Pictures (see White of Egg), 33
Aniline Colours, 238
Art and Photography, 269
Artificial Light and Photography, 67
Asphalt, 9
Astronomical Photography, 167, 289

Bank-notes copied by Photography, 11
Barometrical Observations by Photography, 195
Becquerel, 265
Berkowsky, 170
Brewster, 97
Bromine, 106
Buildings, control of, by Photography, 214
Burchard, 246

Cabinet-shape, 53
Camera, 7, 87
Carbonic Acid, Decomposition of by Light, 74
Cartes de Visite, 53
Charcoal Pictures, 232
Chemical Ink, 5
China Decorations, Photographic, 207, 249
Chloride of Silver, 4, 107
Chromic Oxide, 216
Chromium, Compounds of, 216
Collodion, 34
——— Plates, 279
Comets, Photographs of, 290, 292
Contrasts of Light and Shade reproduced in Photography, 122
Copper-plate Printing, Photographic, 10, 210, 220
Copper Salts in Photography, 259
Corona, Photography of the, 181

Daguerre, 12
Daguerreotype, 13, 14
Davy, 5
Development, 17, 42, 109
Disderi, 36
Distance, 138
Draper, 17
Dry Plates, 279
Dubroni, 199

Egg, White of, 33
Electric Light, 70
———, Photography by, 286

Electrotype Process, 221
Elements, 104
Emulsions, 279
Encaustics, 207, 249
Ettinghausen, 16

Facsimile, 234
Field Photography, 162
Fixing, 24
Foreshortening in Perspective, 143
Fritzsch, 179, 204

Gaffield, 262
Gelatine Plates, 280
Genre, Tableaux de, 124
Glass Painting and Photography, 250
Globes, Abnormal rendering of, by Photography, 121
Groups, Pictures of, 149
Gun Cotton, 34

Half-tones reproduced by Heliography, 224; by Photo-lithography, 244; in Photo-reliefs, 228
Heliography with Asphalt, 10; with Salts of Silver, with Salts of Chromium, 211
Heliopictor, 199
Herschel, 24
Horn silver, 4

Images, Accuracy of Photographic, 117
——— Optical, by Refraction, 81
——— their dependence on the Artist, the Apparatus, and the Original; their Difference and Reality, 117–130
Instantaneous Photography, 292
Instruments, Treatment of Scientific, by Photography, 195
Iodide and Bromide of Silver, 109
Iodine, 17, 106
Iron, Salts of, Photography with, 257

Joubert, 249
Jurisprudence and Photography, 212

Karsten, 16
Kellner, 204, 245
Kirchoff, 62

Landscape and Photography, 155
Land-Surveying Photography, 162
Lantern, Magic, 91, 275
Leaf Prints, 25
Leisner, 250
Lenses, 85
Libraries, Use of Microscopic Photographs in, 205
Lichtpaus Process, 277
Light, as a Chemical Agent, 54
——— Chemical Effects of, 102
——— Electric, 70
——— its Nature, 55
——— Lime, 69
——— Magnesium, 68
——— Pictures, 23
——— Refraction of, 81
——— Sky, 75
——— Sun, 73
Lithography, 241

Magic Cigar-holders, 209
——— Photography, 208
Magnesium Light, 68
Magnifying Apparatus, 153
Medical Research and Photography, 197
Mercury, 17, 109
Meydenbauer, 166
Micro-photographs, 202
Microscopes, 202
Microscopic Photographs, 204
Minerals, Change of, by Light, 262
Morse, 17
Moser, 16, 103

Negative Process, 37
——— Retouche, 48
Negatives, 28, 31
Neumeyer, 195

Nièpce de St. Victor, 33, 266
Nièpce Nicophore, 9

Obernetter, 237, 249, 259
Oidtmann, 250
Osborne, 244
Ozone, Formation of, by Light, 105

Panoramic Apparatus, 162
Pantograph, 225
Paper, Durable, Sensitive, 30
——— Negatives, 28, 31
——— Photography, 23
Parallactic Exposition, 168
Patterns, Photographic, 214
Pea-Sausage, 256
Perspective, and its Influence on Photography, 131
Perspective Foreshortenings, 132
Petzval, 19
Phosphorus, Sensitive to Light, 104
Photographs from Photographs, 154
Photography, Development of Modern, 31
——— in Colours, 296
Photogravure, 296
Photo-lithography, 241
Photo-reliefs, 224
Photo-zincography, 243
Photometer, 254
Physical Effects of Light, 1
Pigment Press, 232
Plates, cleaning of, 39
Platinotype, 285
Poitevin, 232, 236, 244, 249, 267
Ponton, 218
Portable Plates, 283
Portrait, Choice of Dress for, 150
——— Influence of Weather on, 151
——— Influence of the Size of the Picture in, 152
——— Objectives, 19
——— Photography, 146
Portraits, 150
Positive, 29
Prisms, 61
Protuberances, 177
Pretsch, 221
Protection of Photographs, 44
Pyrogallic Acid, 35
Pyro-photography with Salts of Silver, 207

Refraction of Light, 81
Relief (High and Low) Printing, 229
Reliefs, 228
Rutherford, 182, 185, 186

Sachse, 16
Sand-blast Process, 252
Scamoni, 210, 224
Shades, 132
Schönbein, 34
Schools, 269
Scientific Photography, 289
Seebeck, 264
Silver, Salts, Effects of Light on, 106
——— Subbromide of, 108
——— Subchloride of, 108
——— Subiodide of, 108
——— Use of, in Photography, 115
Solar Camera, 93
Sun and Sun-spots, Taking of the, 181
Sunlight, Chemical Effect of, 76
——— Clearness of, 74
——— Reflected, 73
Spectra of Stars, 291
Spectrum, 61
——— Analysis, 62
——— Lines of, 62, 189
Steel Engraving, Photographic, 220
Standpoint, Effect of the, 142
Stereoscope, American, 100
Stereoscopic Landscapes, 159
Strengthening, 47

Talbot, Fox, 23, 220
——— R., 25, 30, 275
Talbot-type, 23
——— Paper Photographs, 23
Tent Photography, 157

Tessié de Mothay, 236
Thermometers registered by Photography, 195
Tilghmann, 252
Tones and Colours, 58
——— of Paper Pictures, 50
Topaz, its Sensitiveness to Light, 263
Transparent Pictures on Glass, 159

Undulations of Light, 56
Uranium Salts, 259

Van der Weyde, 286
Varnish, 44
Venus, Transit of, 192
Visite, Cartes de (see Cartes)

Wax, 4
Warren de la Rue, 170, 188
Wedgwood, 5
Wheatstone, 96
White of Egg (see Egg)
Willis, 239
Woodbury, 230

Yellow Light, Effect of, on Plants, 78
——————— on Salts, 42, 67

Zencker, 170, 267
Zincography, 243

THE END.

PRINTED BY WILLIAM CLOWES AND SONS, LIMITED, LONDON AND BECCLES.

A LIST OF

KEGAN PAUL, TRENCH & CO.'S

PUBLICATIONS.

7.88.

1, *Paternoster Square,*
London.

A LIST OF

KEGAN PAUL, TRENCH & CO.'S

PUBLICATIONS.

CONTENTS.

	PAGE		PAGE
General Literature. .	2	Military Works. .	33
Parchment Library . .	18	Poetry.	34
Pulpit Commentary . .	20	Novels and Tales .	39
International Scientific Series	29	Books for the Young .	41

GENERAL LITERATURE.

AINSWORTH, W. F.—A Personal Narrative of the Euphrates Expedition. With Map. 2 vols. Demy 8vo, 30*s.*

A. K. H. B.—From a Quiet Place. A Volume of Sermons. Crown 8vo, 5*s.*

ALEXANDER, William, D.D., Bishop of Derry.—The Great Question, and other Sermons. Crown 8vo, 6*s.*

ALLIES, T. W., M.A.—Per Crucem ad Lucem. The Result of a Life. 2 vols. Demy 8vo, 25*s.*

A Life's Decision. Crown 8vo, 7*s.* 6*d.*

AMHERST, Rev. W. J.—The History of Catholic Emancipation and the Progress of the Catholic Church in the British Isles (chiefly in England) from 1771-1820. 2 vols. Demy 8vo, 24*s.*

AMOS, Professor Sheldon.—The History and Principles of the Civil Law of Rome. An aid to the Study of Scientific and Comparative Jurisprudence. Demy 8vo, 16*s.*

Ancient and Modern Britons. A Retrospect. 2 vols. Demy 8vo, 24*s.*

Are Foreign Missions doing any Good? An Enquiry into their Social Effects. Crown 8vo, 1*s.*

ARISTOTLE.—The Nicomachean Ethics of Aristotle. Translated by F. H. Peters, M.A. Third Edition. Crown 8vo, 6*s.*

AUBERTIN, J. J.—A Flight to Mexico. With 7 full-page Illustrations and a Railway Map of Mexico. Crown 8vo, 7*s.* 6*d.*

Six Months in Cape Colony and Natal. With Illustrations and Map. Crown 8vo, 6*s.*

A Fight with Distances. Illustrations and Maps. Crown 8vo, 7*s.* 6*d.*

Aucassin and Nicolette. Edited in Old French and rendered in Modern English by F. W. BOURDILLON. Fcap 8vo, 7*s.* 6*d.*

AZARIAS, Brother.—Aristotle and the Christian Church. Small crown 8vo, 3*s.* 6*d.*

BADGER, George Percy, D.C.L.—An English-Arabic Lexicon. In which the equivalent for English Words and Idiomatic Sentences are rendered into literary and colloquial Arabic. Royal 4to, 80*s.*

BAGEHOT, Walter.—The English Constitution. Fourth Edition. Crown 8vo, 7*s.* 6*d.*

Lombard Street. A Description of the Money Market. Eighth Edition. Crown 8vo, 7*s.* 6*d.*

Essays on Parliamentary Reform. Crown 8vo, 5*s.*

Some Articles on the Depreciation of Silver, and Topics connected with it. Demy 8vo, 5*s.*

BAGOT, Alan, C.E.—Accidents in Mines: their Causes and Prevention. Crown 8vo, 6*s.*

The Principles of Colliery Ventilation. Second Edition, greatly enlarged. Crown 8vo, 5*s.*

The Principles of Civil Engineering as applied to Agriculture and Estate Management. Crown 8vo, 7*s.* 6*d.*

BALDWIN, Capt. J. H.—The Large and Small Game of Bengal and the North-Western Provinces of India. With 20 Illustrations. New and Cheaper Edition. Small 4to, 10*s.* 6*d.*

BALL, John, F.R.S.—Notes of a Naturalist in South America. With Map. Crown 8vo, 8*s.* 6*d.*

BALLIN, Ada S. and F. L.—A Hebrew Grammar. With Exercises selected from the Bible. Crown 8vo, 7*s.* 6*d.*

BASU, K. P., M.A.—Students' Mathematical Companion. Containing problems in Arithmetic, Algebra, Geometry, and Mensuration, for Students of the Indian Universities. Crown 8vo, 6*s.*

BAUR, Ferdinand, Dr. Ph.—A Philological Introduction to Greek and Latin for Students. Translated and adapted from the German, by C. KEGAN PAUL, M.A., and E. D. STONE, M.A. Third Edition. Crown 8vo, 6*s.*

BAYLY, Capt. George.—Sea Life Sixty Years Ago. A Record of Adventures which led up to the Discovery of the Relics of the long-missing Expedition commanded by the Comte de la Perouse. Crown 8vo, 3*s.* 6*d.*

BENSON, A. C.—William Laud, sometime Archbishop of Canterbury. A Study. With Portrait. Crown 8vo, 6*s.*

BLACKBURN, Mrs. Hugh.—Bible Beasts and Birds. 22 Illustrations of Scripture photographed from the Original. 4to, 42*s.*

BLOOMFIELD, The Lady.—Reminiscences of Court and Diplomatic Life. New and Cheaper Edition. With Frontispiece. Crown 8vo, 6*s.*

BLUNT, The Ven. Archdeacon.—The Divine Patriot, and other Sermons. Preached in Scarborough and in Cannes. New and Cheaper Edition. Crown 8vo, 4*s.* 6*d.*

BLUNT, Wilfrid S.—The Future of Islam. Crown 8vo, 6*s.*

Ideas about India. Crown 8vo. Cloth, 6*s.*

BOWEN, H. C., M.A.—Studies in English. For the use of Modern Schools. Ninth Thousand. Small crown 8vo, 1*s.* 6*d.*

English Grammar for Beginners. Fcap. 8vo, 1*s.*

Simple English Poems. English Literature for Junior Classes. In four parts. Parts I., II., and III., 6*d.* each. Part IV., 1*s.* Complete, 3*s.*

BRADLEY, F. H.—The Principles of Logic. Demy 8vo, 16*s.*

BRIDGETT, Rev. T. E.—History of the Holy Eucharist in Great Britain. 2 vols. Demy 8vo, 18*s.*

BROOKE, Rev. Stopford A.—The Fight of Faith. Sermons preached on various occasions. Fifth Edition. Crown 8vo, 7*s.* 6*d.*

The Spirit of the Christian Life. Third Edition. Crown 8vo, 5*s.*

Theology in the English Poets.—Cowper, Coleridge, Wordsworth, and Burns. Sixth Edition. Post 8vo, 5*s.*

Christ in Modern Life. Sixteenth Edition. Crown 8vo, 5*s*

Sermons. First Series. Thirteenth Edition. Crown 8vo, 5*s.*

Sermons. Second Series. Sixth Edition. Crown 8vo, 5*s.*

BROWN, Horatio F.—Life on the Lagoons. With 2 Illustrations and Map. Crown 8vo, 6*s.*

Venetian Studies. Crown 8vo, 7*s.* 6*d.*

BROWN, Rev. J. Baldwin.—**The Higher Life.** Its Reality, Experience, and Destiny. Sixth Edition. Crown 8vo, 5*s.*

Doctrine of Annihilation in the Light of the Gospel of Love. Five Discourses. Fourth Edition. Crown 8vo, 2*s.* 6*d.*

The Christian Policy of Life. A Book for Young Men of Business. Third Edition. Crown 8vo, 3*s.* 6*d.*

BURDETT, Henry C.—**Help in Sickness—Where to Go and What to Do.** Crown 8vo, 1*s.* 6*d.*

Helps to Health. The Habitation—The Nursery—The Schoolroom and—The Person. With a Chapter on Pleasure and Health Resorts. Crown 8vo, 1*s.* 6*d.*

BURKE, Oliver J.—**South Isles of Aran (County Galway).** Crown 8vo, 2*s.* 6*d.*

BURKE, The Late Very Rev. T. N.—**His Life.** By W. J. FITZPATRICK. 2 vols. With Portrait. Demy 8vo, 30*s.*

BURTON, Lady.—**The Inner Life of Syria, Palestine, and the Holy Land.** Post 8vo, 6*s.*

CANDLER, C.—**The Prevention of Consumption.** A Mode of Prevention founded on a New Theory of the Nature of the Tubercle-Bacillus. Demy 8vo, 10*s.* 6*d.*

CAPES, J. M.—**The Church of the Apostles:** an Historical Inquiry. Demy 8vo, 9*s.*

CARPENTER, W. B.—**The Principles of Mental Physiology.** With their Applications to the Training and Discipline of the Mind, and the Study of its Morbid Conditions. Illustrated. Sixth Edition. 8vo, 12*s.*

Nature and Man. With a Memorial Sketch by the Rev. J. ESTLIN CARPENTER. Portrait. Large crown 8vo, 8*s.* 6*d.*

Catholic Dictionary. Containing some Account of the Doctrine, Discipline, Rites, Ceremonies, Councils, and Religious Orders of the Catholic Church. By WILLIAM E. ADDIS and THOMAS ARNOLD, M.A. Third Edition. Demy 8vo, 21*s.*

Century Guild Hobby Horse. Vols. I. and II. Half parchment, 12*s.* 6*d.* each.

CHARLES, Rev. R. H.—**Forgiveness,** and other Sermons. Crown 8vo, 4*s.* 6*d.*

CHEYNE, Canon.—**The Prophecies of Isaiah.** Translated with Critical Notes and Dissertations. 2 vols. Fourth Edition. Demy 8vo, 25*s.*

Job and Solomon; or, the Wisdom of the Old Testament. Demy 8vo, 12*s.* 6*d.*

The Psalms; or, Book of The Praises of Israel. Translated with Commentary. Demy 8vo. 16*s.*

Churgress, The. By "THE PRIG." Fcap. 8vo, 3*s.* 6*d.*

CLAIRAUT.—**Elements of Geometry.** Translated by Dr. KAINES. With 145 Figures. Crown 8vo, 4*s.* 6*d.*

CLAPPERTON, Jane Hume.—**Scientific Meliorism and the Evolution of Happiness.** Large crown 8vo, 8*s.* 6*d.*

CLARKE, Rev. Henry James, A.K.C.—**The Fundamental Science.** Demy 8vo, 10*s.* 6*d.*

CLODD, Edward, F.R.A.S.—**The Childhood of the World:** a Simple Account of Man in Early Times. Eighth Edition. Crown 8vo, 3*s.*

A Special Edition for Schools. 1*s.*

The Childhood of Religions. Including a Simple Account of the Birth and Growth of Myths and Legends. Eighth Thousand. Crown 8vo, 5*s.*

A Special Edition for Schools. 1*s.* 6*d.*

Jesus of Nazareth. With a brief sketch of Jewish History to the Time of His Birth. Small crown 8vo, 6*s.*

COGHLAN, T. Cole, D.D.—**The Modern Pharisee and other Sermons.** Edited by the Very Rev. H. H. DICKINSON, D.D., Dean of Chapel Royal, Dublin. New and Cheaper Edition. Crown 8vo, 7*s.* 6*d.*

COLERIDGE, Sara.—**Memoir and Letters of Sara Coleridge.** Edited by her Daughter. With Index. Cheap Edition. With Portrait. 7*s.* 6*d.*

COLERIDGE, The Hon. Stephen.—**Demetrius.** Crown 8vo, 5*s.*

CONNELL, A. K.—**Discontent and Danger in India.** Small crown 8vo, 3*s.* 6*d.*

The Economic Revolution of India. Crown 8vo, 4*s.* 6*d.*

COOK, Keningale, LL.D.—**The Fathers of Jesus.** A Study of the Lineage of the Christian Doctrine and Traditions. 2 vols. Demy 8vo, 28*s.*

CORR, the late Rev. T. J., M.A.—**Favilla;** Tales, Essays, and Poems. Crown 8vo, 5*s.*

CORY, William.—**A Guide to Modern English History.** Part I.—MDCCCXV.-MDCCCXXX. Demy 8vo, 9*s.* Part II.—MDCCCXXX.-MDCCCXXXV., 15*s.*

COTTON, H. J. S.—**New India, or India in Transition.** Third Edition. Crown 8vo, 4*s.* 6*d.*; Cheap Edition, paper covers, 1*s.*

COWIE, Right Rev. W. G.—**Our Last Year in New Zealand.** 1887. Crown 8vo, 7*s.* 6*d.*

COX, Rev. Sir George W., M.A., Bart.—**The Mythology of the Aryan Nations.** New Edition. Demy 8vo, 16*s.*

COX, Rev. Sir George W., M.A., Bart.—continued.

Tales of Ancient Greece. New Edition. Small crown 8vo, 6*s.*

A Manual of Mythology in the form of Question and Answer. New Edition. Fcap. 8vo, 3*s.*

An Introduction to the Science of Comparative Mythology and Folk-Lore. Second Edition. Crown 8vo. 7*s.* 6*d.*

COX, Rev. Sir G. W., M.A., Bart., and JONES, Eustace Hinton.—Popular Romances of the Middle Ages. Third Edition, in 1 vol. Crown 8vo, 6*s.*

COX, Rev. Samuel, D.D.—A Commentary on the Book of Job. With a Translation. Second Edition. Demy 8vo, 15*s.*

Salvator Mundi; or, Is Christ the Saviour of all Men? Tenth Edition. Crown 8vo, 5*s.*

The Larger Hope. A Sequel to "Salvator Mundi." Second Edition. 16mo, 1*s.*

The Genesis of Evil, and other Sermons, mainly expository. Third Edition. Crown 8vo, 6*s.*

Balaam. An Exposition and a Study. Crown 8vo, 5*s.*

Miracles. An Argument and a Challenge. Crown 8vo, 2*s.* 6*d.*

CRAVEN, Mrs.—A Year's Meditations. Crown 8vo, 6*s.*

CRAWFURD, Oswald.—Portugal, Old and New. With Illustrations and Maps. New and Cheaper Edition. Crown 8vo, 6*s.*

CRUISE, Francis Richard, M.D.—Thomas à Kempis. Notes of a Visit to the Scenes in which his Life was spent. With Portraits and Illustrations. Demy 8vo, 12*s.*

Dante: The Banquet (Il Comito). Translated by KATHARINE HILLARD. Crown 8vo.

DARMESTETER, Arsene.—The Life of Words as the Symbols of Ideas. Crown 8vo, 4*s.* 6*d.*

DAVIDSON, Rev. Samuel, D.D., LL.D.—Canon of the Bible: Its Formation, History, and Fluctuations. Third and Revised Edition. Small crown 8vo, 5*s.*

The Doctrine of Last Things contained in the New Testament compared with the Notions of the Jews and the Statements of Church Creeds. Small crown 8vo, 3*s.* 6*d.*

DAWSON, Geo., M.A. Prayers, with a Discourse on Prayer. Edited by his Wife. First Series. Ninth Edition. Small Crown 8vo, 3*s.* 6*d.*

Prayers, with a Discourse on Prayer. Edited by GEORGE ST. CLAIR, F.G.S. Second Series. Small Crown 8vo, 3*s.* 6*d.*

Sermons on Disputed Points and Special Occasions. Edited by his Wife. Fourth Edition. Crown 8vo, 6*s.*

DAWSON, Geo., M.A.—continued.

Sermons on Daily Life and Duty. Edited by his Wife. Fifth Edition. Small Crown 8vo, 3*s.* 6*d.*

The Authentic Gospel, and other Sermons. Edited by GEORGE ST. CLAIR, F.G.S. Third Edition. Crown 8vo, 6*s.*

Every-day Counsels. Edited by GEORGE ST. CLAIR, F.G.S. Crown 8vo, 6*s.*

Biographical Lectures. Edited by GEORGE ST. CLAIR, F.G.S Third Edition. Large crown 8vo, 7*s.* 6*d.*

Shakespeare, and other Lectures. Edited by GEORGE ST. CLAIR, F.G.S. Large crown 8vo, 7*s.* 6*d.*

DE JONCOURT, Madame Marie.—Wholesome Cookery. Fourth Edition. Crown 8vo, cloth, 1*s.* 6*d*; paper covers, 1*s.*

DENT, H. C.—A Year in Brazil. With Notes on Religion, Meteorology, Natural History, etc. Maps and Illustrations. Demy 8vo, 18*s.*

DOWDEN, Edward, LL.D.—Shakspere: a Critical Study of his Mind and Art. Eighth Edition. Post 8vo, 12*s.*

Studies in Literature, 1789–1877. Fourth Edition. Large post 8vo, 6*s.*

Transcripts and Studies. Large post 8vo. 12*s.*

Dulce Domum. Fcap. 8vo, 5*s.*

DU MONCEL, Count.—The Telephone, the Microphone, and the Phonograph. With 74 Illustrations. Third Edition. Small crown 8vo, 5*s.*]

DUNN, H. Percy.—Infant Health. The Physiology and Hygiene of Early Life. Crown 8vo. 3*s.* 6*d.*

DURUY, Victor.—History of Rome and the Roman People. Edited by Prof. MAHAFFY. With nearly 3000 Illustrations. 4to. 6 vols. in 12 parts, 30*s.* each vol.

Education Library. Edited by Sir PHILIP MAGNUS:—

An Introduction to the History of Educational Theories. By OSCAR BROWNING, M.A. Second Edition. 3*s.* 6*d.*

Old Greek Education. By the Rev. Prof. MAHAFFY, M.A. Second Edition. 3*s.* 6*d.*

School Management. Including a general view of the work of Education, Organization and Discipline. By JOSEPH LANDON. Sixth Edition. 6*s.*

EDWARDES, Major-General Sir Herbert B.—Memorials of his Life and Letters. By his Wife. With Portrait and Illustrations. 2 vols. Demy 8vo, 36*s.*

ELSDALE, Henry.—**Studies in Tennyson's Idylls.** Crown 8vo, 5*s.*

Eighteenth Century Essays. Selected and Edited by AUSTIN DOBSON. Cheap Edition. Cloth 1*s.* 6*d.*

Emerson's (Ralph Waldo) Life. By OLIVER WENDELL HOLMES. English Copyright Edition. With Portrait. Crown 8vo, 6*s.*

Five o'clock Tea. Containing Receipts for Cakes, Savoury Sandwiches, etc. Fcap. 8vo, cloth, 1*s.* 6*d.*; paper covers, 1*s.*

FLINN, D. Edgar.—**Ireland: its Health-Resorts and Watering-Places.** With Frontispiece and Maps. Demy 8vo, 5*s.*

Forbes, Bishop: A Memoir. By the Rev. DONALD J. MACKAY. With Portrait and Map. Crown 8vo, 7*s.* 6*d.*

FORDYCE, J.—**The New Social Order.** Crown 8vo, 3*s.* 6*d.*

FOTHERINGHAM, James.—**Studies in the Poetry of Robert Browning.** Second Edition. Crown 8vo, 6*s.*

Franklin (Benjamin) as a Man of Letters. By J. B. MACMASTER. Crown 8vo, 5*s.*

FREWEN, MORETON.—**The Economic Crisis.** Crown 8vo, 4*s.* 6*d.*

From World to Cloister; or, My Novitiate. By BERNARD. Crown 8vo, 5*s.*

GARDINER, Samuel R., and J. BASS MULLINGER, M.A.—**Introduction to the Study of English History.** Second Edition. Large crown 8vo, 9*s.*

Genesis in Advance of Present Science. A Critical Investigation of Chapters I.-IX. By a Septuagenarian Beneficed Presbyter. Demy 8vo, 10*s.* 6*d.*

GEORGE, Henry.—**Progress and Poverty:** An Inquiry into the Causes of Industrial Depressions, and of Increase of Want with Increase of Wealth. The Remedy. Fifth Library Edition. Post 8vo, 7*s.* 6*d.* Cabinet Edition. Crown 8vo, 2*s.* 6*d.* Also a Cheap Edition. Limp cloth, 1*s.* 6*d.*; paper covers, 1*s.*

Protection, or Free Trade. An Examination of the Tariff Question, with especial regard to the Interests of Labour. Second Edition. Crown 8vo, 5*s.*

Social Problems. Fourth Thousand. Crown 8vo, 5*s.* Cheap Edition, paper covers, 1*s.*; cloth 1*s.* 6*d.*

GILBERT, Mrs.—**Autobiography, and other Memorials.** Edited by JOSIAH GILBERT. Fifth Edition. Crown 8vo, 7*s.* 6*d.*

GILLMORE, Parker.—**Days and Nights by the Desert.** Illustrated. Demy 8vo, 10*s.* 6*d.*

GLANVILL, Joseph.—**Scepsis Scientifica;** or, Confest Ignorance, the Way to Science; in an Essay of the Vanity of Dogmatizing and Confident Opinion. Edited, with Introductory Essay, by JOHN OWEN. Elzevir 8vo, printed on hand-made paper, 6*s.*

GLASS, H. A.—**The Story of the Psalters.** A History of the Metrical Versions from 1549 to 1885. Crown 8vo, 5*s.*

Glossary of Terms and Phrases. Edited by the Rev. H. PERCY SMITH and others. Second and Cheaper Edition. Medium 8vo, 7*s.* 6*d.*

GLOVER, F., M.A.—**Exempla Latina.** A First Construing Book, with Short Notes, Lexicon, and an Introduction to the Analysis of Sentences. Second Edition. Fcap. 8vo, 2*s.*

GOODENOUGH, Commodore J. G.—**Memoir of,** with Extracts from his Letters and Journals. Edited by his Widow. With Steel Engraved Portrait. Third Edition. Crown 8vo, 5*s.*

GORDON, Major-General C. G.—**His Journals at Kartoum.** Printed from the original MS. With Introduction and Notes by A. EGMONT HAKE. Portrait, 2 Maps, and 30 Illustrations. Two vols., demy 8vo, 21*s.* Also a Cheap Edition in 1 vol., 6*s.*

Gordon's (General) Last Journal. A Facsimile of the last Journal received in England from GENERAL GORDON. Reproduced by Photo-lithography. Imperial 4to, £3 3*s.*

Events in his Life. From the Day of his Birth to the Day of his Death. By Sir H. W. GORDON. With Maps and Illustrations. Second Edition. Demy 8vo, 7*s.* 6*d.*

GOSSE, Edmund.—**Seventeenth Century Studies.** A Contribution to the History of English Poetry. Demy 8vo, 10*s.* 6*d.*

GOULD, Rev. S. Baring, M.A.—**Germany, Present and Past.** New and Cheaper Edition. Large crown 8vo, 7*s.* 6*d.*

The Vicar of Morwenstow. A Life of Robert Stephen Hawker. Crown 8vo, 5*s.*

GOWAN, Major Walter E.—**A. Ivanoff's Russian Grammar.** (16th Edition.) Translated, enlarged, and arranged for use of Students of the Russian Language. Demy 8vo, 6*s.*

GOWER, Lord Ronald. **My Reminiscences.** MINIATURE EDITION, printed on hand-made paper, limp parchment antique, 10*s.* 6*d.*

Bric-à-Brac. Being some Photoprints illustrating art objects at Gower Lodge, Windsor. With descriptions. Super royal 8vo. 15*s.*; extra binding, 21*s.*

Last Days of Mary Antoinette. An Historical Sketch. With Portrait and Facsimiles. Fcap. 4to, 10*s.* 6*d.*

Notes of a Tour from Brindisi to Yokohama, 1883-1884. Fcap. 8vo, 2*s.* 6*d.*

GRAHAM, William, M.A.—**The Creed of Science,** Religious, Moral, and Social. Second Edition, Revised. Crown 8vo, 6*s.*

The Social Problem, in its Economic, Moral, and Political Aspects. Demy 8vo, 14*s.*

GRIMLEY, Rev. H. N., M.A.—Tremadoc Sermons, chiefly on the Spiritual Body, the Unseen World, and the Divine Humanity. Fourth Edition. Crown 8vo, 6*s.*

The Temple of Humanity, and other Sermons. Crown 8vo, 6*s.*

HADDON, Caroline.—The Larger Life, Studies in Hinton's Ethics. Crown 8vo, 5*s.*

HAECKEL, Prof. Ernst.—The History of Creation. Translation revised by Professor E. RAY LANKESTER, M.A., F.R.S. With Coloured Plates and Genealogical Trees of the various groups of both Plants and Animals. 2 vols. Third Edition. Post 8vo, 32*s.*

The History of the Evolution of Man. With numerous Illustrations. 2 vols. Post 8vo, 32*s.*

A Visit to Ceylon. Post 8vo, 7*s.* 6*d.*

Freedom in Science and Teaching. With a Prefatory Note by T. H. HUXLEY, F.R.S. Crown 8vo, 5*s.*

HALCOMBE, J. J.—Gospel Difficulties due to a Displaced Section of St. Luke. Second Edition. Crown 8vo, 6*s.*

Hamilton, Memoirs of Arthur, B.A., of Trinity College, Cambridge. Crown 8vo, 6*s.*

Handbook of Home Rule, being Articles on the Irish Question by Various Writers. Edited by JAMES BRYCE, M.P. Second Edition. Crown 8vo, 1*s.* sewed, or 1*s.* 6*d.* cloth.

HAWEIS, Rev. H. R., M.A.—Current Coin. Materialism—The Devil—Crime—Drunkenness—Pauperism—Emotion—Recreation—The Sabbath. Fifth Edition. Crown 8vo, 5*s.*

Arrows in the Air. Fifth Edition. Crown 8vo, 5*s.*

Speech in Season. Fifth Edition. Crown 8vo, 5*s.*

Thoughts for the Times. Fourteenth Edition. Crown 8vo, 5*s.*

Unsectarian Family Prayers. New Edition. Fcap. 8vo, 1*s.* 6*d.*

HAWTHORNE, Nathaniel.—Works. Complete in Twelve Volumes. Large post 8vo, 7*s.* 6*d.* each volume.

HEATH, Francis George.—Autumnal Leaves. Third and cheaper Edition. Large crown 8vo, 6*s.*

Sylvan Winter. With 70 Illustrations. Large crown 8vo, 14*s.*

HEIDENHAIN, Rudolph, M.D.—Hypnotism, or Animal Magnetism. With Preface by G. J. ROMANES. Second Edition. Small crown 8vo, 2*s.* 6*d.*

HINTON, J.—Life and Letters. With an Introduction by Sir W. W. GULL, Bart., and Portrait engraved on Steel by C. H. Jeens. Fifth Edition. Crown 8vo, 8*s.* 6*d.*

HINTON, J.—continued.

Philosophy and Religion. Selections from the Manuscripts of the late James Hinton. Edited by CAROLINE HADDON. Second Edition. Crown 8vo, 5*s.*

The Law Breaker, and The Coming of the Law. Edited by MARGARET HINTON. Crown 8vo, 6*s.*

The Mystery of Pain. New Edition. Fcap. 8vo, 1*s.*

Homer's Iliad. Greek text, with a Translation by J. G. CORDERY. 2 vols. Demy 8vo, 24*s.*

HOOPER, Mary.—Little Dinners: How to Serve them with Elegance and Economy. Twentieth Edition. Crown 8vo, 2*s.* 6*d.*

Cookery for Invalids, Persons of Delicate Digestion, and Children. Fifth Edition. Crown 8vo, 2*s.* 6*d.*

Every-day Meals. Being Economical and Wholesome Recipes for Breakfast, Luncheon, and Supper. Seventh Edition. Crown 8vo, 2*s.* 6*d.*

HOPKINS, Ellice.—Work amongst Working Men. Sixth Edition. Crown 8vo, 3*s.* 6*d.*

HORNADAY, W. T.—Two Years in a Jungle. With Illustrations. Demy 8vo, 21*s.*

HOSPITALIER, E.—The Modern Applications of Electricity. Translated and Enlarged by JULIUS MAIER, Ph.D. 2 vols. Second Edition, Revised, with many additions and numerous Illustrations. Demy 8vo, 25*s.*

HOWARD, Robert, M.A.—The Church of England and other Religious Communions. A course of Lectures delivered in the Parish Church of Clapham. Crown 8vo, 7*s.* 6*d.*

How to Make a Saint; or, The Process of Canonization in the Church of England. By "THE PRIG." Fcap 8vo, 3*s.* 6*d.*

HYNDMAN, H. M.—The Historical Basis of Socialism in England. Large crown 8vo, 8*s.* 6*d.*

IDDESLEIGH, Earl of.—The Pleasures, Dangers, and Uses of Desultory Reading. Fcap. 8vo, in Whatman paper cover, 1*s.*

IM THURN, Everard F.—Among the Indians of Guiana. Being Sketches, chiefly anthropologic, from the Interior of British Guiana. With 53 Illustrations and a Map. Demy 8vo, 18*s.*

Ixora: A Mystery. Crown 8vo, 6*s.*

Jaunt in a Junk: A Ten Days' Cruise in Indian Seas. Large crown 8vo, 7*s.* 6*d.*

JENKINS, E., and RAYMOND, J.—The Architect's Legal Handbook. Third Edition, revised. Crown 8vo, 6*s.*

JENKINS, Rev. Canon R. C.—**Heraldry: English and Foreign.** With a Dictionary of Heraldic Terms and 156 Illustrations. Small crown 8vo, 3*s.* 6*d.*

Jerome, St., Life. By M. J. MARTIN. Large crown 8vo, 6*s.*

JOEL, L.—**A Consul's Manual and Shipowner's and Shipmaster's Practical Guide in their Transactions Abroad.** With Definitions of Nautical, Mercantile, and Legal Terms; a Glossary of Mercantile Terms in English, French, German, Italian, and Spanish; Tables of the Money, Weights, and Measures of the Principal Commercial Nations and their Equivalents in British Standards; and Forms of Consular and Notarial Acts. Demy 8vo, 12*s.*

JOHNSTON, H. H., F.Z.S.—**The Kilima-njaro Expedition.** A Record of Scientific Exploration in Eastern Equatorial Africa, and a General Description of the Natural History, Languages, and Commerce of the Kilima-njaro District. With 6 Maps, and over 80 Illustrations by the Author. Demy 8vo, 21*s.*

JORDAN, Furneaux, F.R.C.S.—**Anatomy and Physiology in Character.** Crown 8vo, 5*s.*

KAUFMANN, Rev. M., M.A.—**Socialism:** its Nature, its Dangers, and its Remedies considered. Crown 8vo, 7*s.* 6*d.*

Utopias; or, Schemes of Social Improvement, from Sir Thomas More to Karl Marx. Crown 8vo, 5*s.*

Christian Socialism. Crown 8vo, 4*s.* 6*d.*

KAY, David, F.R.G.S.—**Education and Educators.** Crown 8vo. 7*s.* 6*d.*

Memory: what it is and how to improve it. Crown 8vo, 6*s.*

KAY, Joseph.—**Free Trade in Land.** Edited by his Widow. With Preface by the Right Hon. JOHN BRIGHT, M.P. Seventh Edition. Crown 8vo, 5*s.*

*** Also a cheaper edition, without the Appendix, but with a Review of Recent Changes in the Land Laws of England, by the RIGHT HON. G. OSBORNE MORGAN, Q.C., M.P. Cloth, 1*s.* 6*d.*; paper covers, 1*s.*

KELKE, W. H. H.—**An Epitome of English Grammar for the Use of Students.** Adapted to the London Matriculation Course and Similar Examinations. Crown 8vo, 4*s.* 6*d.*

KEMPIS, Thomas à.—**Of the Imitation of Christ.** Parchment Library Edition.—Parchment or cloth, 6*s.*; vellum, 7*s.* 6*d.* The Red Line Edition, fcap. 8vo, cloth extra, 2*s.* 6*d.* The Cabinet Edition, small 8vo, cloth limp, 1*s.*; cloth boards, 1*s.* 6*d.* The Miniature Edition, cloth limp, 32mo, 1*s.*; or with red lines, 1*s.* 6*d.*

*** **All the above Editions may be had in various extra bindings.**

KEMPIS, Thomas à—continued.

Notes of a Visit to the Scenes in which his Life was spent. With numerous Illustrations. By F. R. CRUISE, M.D. Demy 8vo, 12*s.*

KENDALL, Henry.—The Kinship of Men. An argument from Pedigrees, or Genealogy viewed as a Science. With Diagrams. Crown 8vo, 5*s.*

KENNARD, Rev. R. B.—A Manual of Confirmation. 18mo. Sewed, 3*d.*; cloth, 1*s.*

KIDD, Joseph, M.D.—The Laws of Therapeutics; or, the Science and Art of Medicine. Second Edition. Crown 8vo, 6*s.*

KINGSFORD, Anna, M.D.—The Perfect Way in Diet. A Treatise advocating a Return to the Natural and Ancient Food of our Race. Third Edition. Small crown 8vo, 2*s.*

KINGSLEY, Charles, M.A.—Letters and Memories of his Life. Edited by his Wife. With two Steel Engraved Portraits, and Vignettes on Wood. Sixteenth Cabinet Edition. 2 vols. Crown 8vo, 12*s.*

*** Also a People's Edition, in one volume. With Portrait. Crown 8vo, 6*s.*

All Saints' Day, and other Sermons. Edited by the Rev. W. HARRISON. Third Edition. Crown 8vo, 7*s.* 6*d.*

True Words for Brave Men. A Book for Soldiers' and Sailors' Libraries. Sixteenth Thousand. Crown 8vo, 2*s.* 6*d.*

KNOX, Alexander A.—The New Playground; or, Wanderings in Algeria. New and Cheaper Edition. Large crown 8vo, 6*s.*

Land Concentration and Irresponsibility of Political Power, as causing the Anomaly of a Widespread State of Want by the Side of the Vast Supplies of Nature. Crown 8vo, 5*s.*

LANDON, Joseph.—School Management; Including a General View of the Work of Education, Organization, and Discipline. Sixth Edition. Crown 8vo, 6*s.*

LAURIE, S. S.—The Rise and Early Constitution of Universities. With a Survey of Mediæval Education. Crown 8vo, 6*s.*

LEFEVRE, Right Hon. G. Shaw.—Peel and O'Connell. Demy 8vo, 10*s.* 6*d.*

Incidents of Coercion. A Journal of two visits to Loughrea. Crown 8vo.

Letters from an Unknown Friend. By the Author of "Charles Lowder." With a Preface by the Rev. W. H. CLEAVER. Fcap. 8vo, 1*s.*

Life of a Prig. By ONE. Third Edition. Fcap. 8vo, 3*s.* 6*d.*

LILLIE, Arthur, M.R.A.S.—The Popular Life of Buddha. Containing an Answer to the Hibbert Lectures of 1881. With Illustrations. Crown 8vo, 6*s.*

LILLIE, Arthur, M.R.A.S.—continued.

Buddhism in Christendom; or, Jesus the Essene. With Illustrations. Demy 8vo, 15*s.*

LOCHER, Carl.—**An Explanation of Organ Stops**, with Hints for Effective Combinations. Demy 8vo, 5*s.*

LONGFELLOW, H. Wadsworth.—**Life.** By his Brother, SAMUEL LONGFELLOW. With Portraits and Illustrations. 3 vols. Demy 8vo, 42*s.*

LONSDALE, Margaret.—**Sister Dora**: a Biography. With Portrait. Twenty-ninth Edition. Small crown 8vo, 2*s.* 6*d.*

George Eliot: Thoughts upon her Life, her Books, and Herself. Second Edition. Small crown 8vo, 1*s.* 6*d.*

LOUNSBURY, Thomas R.—**James Fenimore Cooper.** With Portrait. Crown 8vo, 5*s.*

LOWDER, Charles.—**A Biography.** By the Author of "St. Teresa." Twelfth Edition. Crown 8vo. With Portrait. 3*s.* 6*d.*

LÜCKES, Eva C. E.—**Lectures on General Nursing**, delivered to the Probationers of the London Hospital Training School for Nurses. Second Edition. Crown 8vo, 2*s.* 6*d.*

LYTTON, Edward Bulwer, Lord.—**Life, Letters and Literary Remains.** By his Son, the EARL OF LYTTON. With Portraits, Illustrations and Facsimiles. Demy 8vo. Vols. I. and II., 32*s.*

MACHIAVELLI, Niccolò. — **Life and Times.** By Prof. VILLARI. Translated by LINDA VILLARI. 4 vols. Large post 8vo, 48*s.*

Discourses on the First Decade of Titus Livius. Translated from the Italian by NINIAN HILL THOMSON, M.A. Large crown 8vo, 12*s.*

The Prince. Translated from the Italian by N. H. T. Small crown 8vo, printed on hand-made paper, bevelled boards, 6*s.*

MACNEILL, J. G. Swift.—**How the Union was carried.** Crown 8vo, cloth, 1*s.* 6*d.*; paper covers, 1*s.*

MAGNUS, Lady.—**About the Jews since Bible Times.** From the Babylonian Exile till the English Exodus. Small crown 8vo, 6*s.*

Maintenon, Madame de. By EMILY BOWLES. With Portrait, Large crown 8vo, 7*s.* 6*d.*

Many Voices. A volume of Extracts from the Religious Writers of Christendom from the First to the Sixteenth Century. With Biographical Sketches. Crown 8vo, cloth extra, red edges, 6*s.*

MARKHAM, Capt. Albert Hastings, R.N.—**The Great Frozen Sea**: A Personal Narrative of the Voyage of the *Alert* during the Arctic Expedition of 1875-6. With 6 full-page Illustrations, 2 Maps, and 27 Woodcuts. Sixth and Cheaper Edition. Crown 8vo, 6*s.*

MARTINEAU, Gertrude.—Outline Lessons on Morals. Small crown 8vo, 3*s.* 6*d.*

MASON, Charlotte M.—Home Education; a Course of Lectures to Ladies. Crown 8vo, 3*s.* 6*d.*

Matter and Energy: An Examination of the Fundamental Conceptions of Physical Force. By B. L. L. Small crown 8vo, 2*s.*

MATUCE, H. Ogram. A Wanderer. Crown 8vo, 5*s.*

MAUDSLEY, H., M.D.—Body and Will. Being an Essay concerning Will, in its Metaphysical, Physiological, and Pathological Aspects. 8vo, 12*s.*

Natural Causes and Supernatural Seemings. Second Edition. Crown 8vo, 6*s.*

McGRATH, Terence.—Pictures from Ireland. New and Cheaper Edition. Crown 8vo, 2*s.*

McKINNEY, S. B. G.—Science and Art of Religion. Crown 8vo, 8*s.* 6*d.*

MEREDITH, M.A.—Theotokos, the Example for Woman. Dedicated, by permission, to Lady Agnes Wood. Revised by the Venerable Archdeacon DENISON. 32mo, limp cloth, 1*s.* 6*d.*

MILLER, Edward.—The History and Doctrines of Irvingism; or, The so-called Catholic and Apostolic Church. 2 vols. Large post 8vo, 15*s.*

The Church in Relation to the State. Large crown 8vo, 4*s.*

MILLS, Herbert.—Poverty and the State; or, Work for the Unemployed. An Inquiry into the Causes and Extent of Enforced Idleness, with a Statement of a Remedy. Crown 8vo, 6*s.*

Mitchel, John, Life. By WILLIAM DILLON. 2 vols. 8vo. With Portrait. 21*s.*

MITCHELL, Lucy M.—A History of Ancient Sculpture. With numerous Illustrations, including 6 Plates in Phototype. Super-royal 8vo, 42*s.*

MOCKLER, E.—A Grammar of the Baloochee Language, as it is spoken in Makran (Ancient Gedrosia), in the Persia-Arabic and Roman characters. Fcap. 8vo, 5*s.*

MOHL, Julius and Mary.—Letters and Recollections of. By M. C. M. SIMPSON. With Portraits and Two Illustrations. Demy 8vo, 15*s.*

MOLESWORTH, Rev. W. Nassau, M.A.—History of the Church of England from 1660. Large crown 8vo, 7*s.* 6*d.*

MORELL, J. R.—Euclid Simplified in Method and Language. Being a Manual of Geometry. Compiled from the most important French Works, approved by the University of Paris and the Minister of Public Instruction. Fcap. 8vo, 2*s.* 6*d.*

MORISON, J. Cotter.—**The Service of Man:** an Essay towards the Religion of the Future. Crown 8vo, 5*s.*

MORSE, E. S., Ph.D.—**First Book of Zoology.** With numerous Illustrations. New and Cheaper Edition. Crown 8vo, 2*s.* 6*d.*

My Lawyer: A Concise Abridgment of the Laws of England. By a Barrister-at-Law. Crown 8vo, 6*s.* 6*d.*

NELSON, J. H., M.A.—**A Prospectus of the Scientific Study of the Hindû Law.** Demy 8vo, 9*s.*

Indian Usage and Judge-made Law in Madras. Demy 8vo, 12*s.*

NEWMAN, Cardinal.—**Characteristics from the Writings of.** Being Selections from his various Works. Arranged with the Author's personal Approval. Seventh Edition. With Portrait. Crown 8vo, 6*s.*

*** A Portrait of Cardinal Newman, mounted for framing, can be had, 2*s.* 6*d.*

NEWMAN, Francis William.—**Essays on Diet.** Small crown 8vo, cloth limp, 2*s.*

Miscellanies. Vol. II. Essays, Tracts, and Addresses, Moral and Religious. Demy 8vo, 12*s.*

Reminiscences of Two Exiles and Two Wars. Crown 8vo.

New Social Teachings. By POLITICUS. Small crown 8vo, 5*s.*

NICOLS, Arthur, F.G.S., F.R.G.S.—**Chapters from the Physical History of the Earth:** an Introduction to Geology and Palæontology. With numerous Illustrations. Crown 8vo, 5*s.*

NIHILL, Rev. H. D.—**The Sisters of St. Mary at the Cross: Sisters of the Poor and their Work.** Crown 8vo, 2*s.* 6*d.*

NOEL, The Hon. Roden.—**Essays on Poetry and Poets.** Demy 8vo, 12*s.*

NOPS, Marianne.—**Class Lessons on Euclid.** Part I. containing the First Two Books of the Elements. Crown 8vo, 2*s.* 6*d.*

Nuces: EXERCISES ON THE SYNTAX OF THE PUBLIC SCHOOL LATIN PRIMER. New Edition in Three Parts. Crown 8vo, each 1*s.*

*** The Three Parts can also be had bound together, 3*s.*

OATES, Frank, F.R.G.S.—**Matabele Land and the Victoria Falls.** A Naturalist's Wanderings in the Interior of South Africa. Edited by C. G. OATES, B.A. With numerous Illustrations and 4 Maps. Demy 8vo, 21*s.*

O'BRIEN, R. Barry.—**Irish Wrongs and English Remedies,** with other Essays. Crown 8vo, 5*s.*

OLIVER, Robert.—**Unnoticed Analogies.** A Talk on the Irish Question. Crown 8vo.

O'MEARA, Kathleen.—**Henri Perreyve and his Counsels to the Sick.** Small crown 8vo, 5*s.*

One and a Half in Norway. A Chronicle of Small Beer. By Either and Both. Small crown 8vo, 3*s.* 6*d.*

O'NEIL, the late Rev. Lord.—**Sermons.** With Memoir and Portrait. Crown 8vo, 6*s.*

Essays and Addresses. Crown 8vo, 5*s.*

OTTLEY, H. Bickersteth.—**The Great Dilemma.** Christ His Own Witness or His Own Accuser. Six Lectures. Second Edition. Crown 8vo, 3*s.* 6*d.*

Our Priests and their Tithes. By a Priest of the Province of Canterbury. Crown 8vo, 5*s.*

Our Public Schools—Eton, Harrow, Winchester, Rugby, Westminster, Marlborough, The Charterhouse. Crown 8vo, 6*s.*

PALMER, the late William.—**Notes of a Visit to Russia in 1840-1841.** Selected and arranged by JOHN H. CARDINAL NEWMAN, with Portrait. Crown 8vo, 8*s.* 6*d.*

Early Christian Symbolism. A Series of Compositions from Fresco Paintings, Glasses, and Sculptured Sarcophagi. Edited by the Rev. Provost NORTHCOTE, D.D., and the Rev. Canon BROWNLOW, M.A. With Coloured Plates, folio, 42*s.*, or with Plain Plates, folio, 25*s.*

Parchment Library. Choicely Printed on hand-made paper, limp parchment antique or cloth, 6*s.*; vellum, 7*s.* 6*d.* each volume.

Sartor Resartus. By THOMAS CARLYLE.

The Poetical Works of John Milton. 2 vols.

Chaucer's Canterbury Tales. Edited by A. W. POLLARD. 2 vols.

Letters and Journals of Jonathan Swift. Selected and edited, with a Commentary and Notes, by STANLEY LANE POOLE.

De Quincey's Confessions of an English Opium Eater. Reprinted from the First Edition. Edited by RICHARD GARNETT.

The Gospel according to Matthew, Mark, and Luke.

Selections from the Prose Writings of Jonathan Swift. With a Preface and Notes by STANLEY LANE-POOLE and Portrait.

English Sacred Lyrics.

Sir Joshua Reynolds's Discourses. Edited by EDMUND GOSSE.

Parchment Library—*continued.*

Selections from Milton's Prose Writings. Edited by ERNEST MYERS.

The Book of Psalms. Translated by the Rev. Canon T. K. CHEYNE, M.A., D.D.

The Vicar of Wakefield. With Preface and Notes by AUSTIN DOBSON.

English Comic Dramatists. Edited by OSWALD CRAWFURD.

English Lyrics.

The Sonnets of John Milton. Edited by MARK PATTISON. With Portrait after Vertue.

French Lyrics. Selected and Annotated by GEORGE SAINTSBURY. With a Miniature Frontispiece designed and etched by H. G. Glindoni.

Fables by Mr. John Gay. With Memoir by AUSTIN DOBSON, and an Etched Portrait from an unfinished Oil Sketch by Sir Godfrey Kneller.

Select Letters of Percy Bysshe Shelley. Edited, with an Introduction, by RICHARD GARNETT.

The Christian Year. Thoughts in Verse for the Sundays and Holy Days throughout the Year. With Miniature Portrait of the Rev. J. Keble, after a Drawing by G. Richmond, R.A.

Shakspere's Works. Complete in Twelve Volumes.

Eighteenth Century Essays. Selected and Edited by AUSTIN DOBSON. With a Miniature Frontispiece by R. Caldecott.

Q. Horati Flacci Opera. Edited by F. A. CORNISH, Assistant Master at Eton. With a Frontispiece after a design by L. Alma Tadema, etched by Leopold Lowenstam.

Edgar Allan Poe's Poems. With an Essay on his Poetry by ANDREW LANG, and a Frontispiece by Linley Sambourne.

Shakspere's Sonnets. Edited by EDWARD DOWDEN. With a Frontispiece etched by Leopold Lowenstam, after the Death Mask.

English Odes. Selected by EDMUND GOSSE. With Frontispiece on India paper by Hamo Thornycroft, A.R.A.

Of the Imitation of Christ. By THOMAS À KEMPIS. A revised Translation. With Frontispiece on India paper, from a Design by W. B. Richmond.

Poems: Selected from PERCY BYSSHE SHELLEY. Dedicated to Lady Shelley. With a Preface by RICHARD GARNETT and a Miniature Frontispiece.

PARSLOE, Joseph.—Our Railways. Sketches, Historical and Descriptive. With Practical Information as to Fares and Rates, etc., and a Chapter on Railway Reform. Crown 8vo, 6*s.*

PASCAL, Blaise.—The Thoughts of. Translated from the Text of Auguste Molinier, by C. KEGAN PAUL. Large crown 8vo, with Frontispiece, printed on hand-made paper, parchment antique, or cloth, 12*s.*; vellum, 15*s.* New Edition. Crown 8vo, 6*s.*

PATON, W. A.—Down the Islands. A Voyage to the Caribbees. With Illustration. Medium 8vo, 16*s.*

PAUL, C. Kegan.—Biographical Sketches. Printed on hand-made paper, bound in buckram. Second Edition. Crown 8vo, 7*s.* 6*d.*

PEARSON, Rev. S.—Week-day Living. A Book for Young Men and Women. Second Edition. Crown 8vo, 5*s.*

PENRICE, Major J.—Arabic and English Dictionary of the Koran. 4to, 21*s.*

PESCHEL, Dr. Oscar.—The Races of Man and their Geographical Distribution. Second Edition. Large crown 8vo, 9*s.*

PIDGEON, D.—An Engineer's Holiday; or, Notes of a Round Trip from Long. 0° to 0°. New and Cheaper Edition. Large crown 8vo, 7*s.* 6*d.*

Old World Questions and New World Answers. Second Edition. Large crown 8vo, 7*s.* 6*d.*

Plain Thoughts for Men. Eight Lectures delivered at Forester's Hall, Clerkenwell, during the London Mission, 1884. Crown 8vo, cloth, 1*s.* 6*d*; paper covers, 1*s.*

PLOWRIGHT, C. B.—The British Uredineæ and Ustilagineæ. With Illustrations. Demy 8vo, 10*s.* 6*d.*

PRICE, Prof. Bonamy.—Chapters on Practical Political Economy. Being the Substance of Lectures delivered before the University of Oxford. New and Cheaper Edition. Crown 8vo, 5*s.*

Prig's Bede: the Venerable Bede, Expurgated, Expounded, and Exposed. By "THE PRIG." Second Edition. Fcap. 8vo, 3*s.* 6*d.*

Pulpit Commentary, The. (*Old Testament Series.*) Edited by the Rev. J. S. EXELL, M.A., and the Very Rev. Dean H. D. M. SPENCE, M.A., D.D.

Genesis. By the Rev. T. WHITELAW, D.D. With Homilies by the Very Rev. J. F. MONTGOMERY, D.D., Rev. Prof. R. A. REDFORD, M.A., LL.B., Rev. F. HASTINGS, Rev. W. ROBERTS, M.A. An Introduction to the Study of the Old Testament by the Venerable Archdeacon FARRAR, D.D., F.R.S.; and Introductions to the Pentateuch by the Right Rev. H. COTTERILL, D.D., and Rev. T. WHITELAW, M.A. Eighth Edition. 1 vol., 15*s.*

Pulpit Commentary, The—*continued.*

Exodus. By the Rev. Canon RAWLINSON. With Homilies by Rev. J. ORR, D.D., Rev. D. YOUNG, B.A., Rev. C. A. GOODHART, Rev. J. URQUHART, and the Rev. H. T. ROBJOHNS. Fourth Edition. 2 vols., 9*s.* each.

Leviticus. By the Rev. Prebendary MEYRICK, M.A. With Introductions by the Rev. R. COLLINS, Rev. Professor A. CAVE, and Homilies by Rev. Prof. REDFORD, LL.B., Rev. J. A. MACDONALD, Rev. W. CLARKSON, B.A., Rev. S. R. ALDRIDGE, LL.B., and Rev. MCCHEYNE EDGAR. Fourth Edition. 15*s.*

Numbers. By the Rev. R. WINTERBOTHAM, LL.B. With Homilies by the Rev. Professor W. BINNIE, D.D., Rev. E. S. PROUT, M.A., Rev. D. YOUNG, Rev. J. WAITE, and an Introduction by the Rev. THOMAS WHITELAW, M.A. Fifth Edition. 15*s.*

Deuteronomy. By the Rev. W. L. ALEXANDER, D.D. With Homilies by Rev. C. CLEMANCE, D.D., Rev. J. ORR, D.D., Rev. R. M. EDGAR, M.A., Rev. D. DAVIES, M.A. Fourth edition. 15*s.*

Joshua. By Rev. J. J. LIAS, M.A. With Homilies by Rev. S. R. ALDRIDGE, LL.B., Rev. R. GLOVER, REV. E. DE PRESSENSÉ, D.D., Rev. J. WAITE, B.A., Rev. W. F. ADENEY, M.A.; and an Introduction by the Rev. A. PLUMMER, M.A. Fifth Edition. 12*s.* 6*d.*

Judges and Ruth. By the Bishop of BATH and WELLS, and Rev. J. MORISON, D.D. With Homilies by Rev. A. F. MUIR, M.A., Rev. W. F. ADENEY, M.A., Rev. W. M. STATHAM, and Rev. Professor J. THOMSON, M.A. Fifth Edition. 10*s.* 6*d.*

1 Samuel. By the Very Rev. R. P. SMITH, D.D. With Homilies by Rev. DONALD FRASER, D.D., Rev. Prof. CHAPMAN, and Rev. B. DALE. Sixth Edition. 15*s.*

1 Kings. By the Rev. JOSEPH HAMMOND, LL.B. With Homilies by the Rev. E. DE PRESSENSÉ, D.D., Rev. J. WAITE, B.A., Rev. A. ROWLAND, LL.B., Rev. J. A. MACDONALD, and Rev. J. URQUHART. Fifth Edition. 15*s.*

1 Chronicles. By the Rev. Prof. P. C. BARKER, M.A., LL.B. With Homilies by Rev. Prof. J. R. THOMSON, M.A., Rev. R. TUCK, B.A., Rev. W. CLARKSON, B.A., Rev. F. WHITFIELD, M.A., and Rev. RICHARD GLOVER. 15*s.*

Ezra, Nehemiah, and Esther. By Rev. Canon G. RAWLINSON, M.A. With Homilies by Rev. Prof. J. R. THOMSON, M.A., Rev. Prof. R. A. REDFORD, LL.B., M.A., Rev. W. S. LEWIS, M.A., Rev. J. A. MACDONALD, Rev. A. MACKENNAL, B.A., Rev. W. CLARKSON, B.A., Rev. F. HASTINGS, Rev. W. DINWIDDIE, LL.B., Rev. Prof. ROWLANDS, B.A., Rev. G. WOOD, B.A., Rev. Prof. P. C. BARKER, M.A., LL.B., and the Rev. J. S. EXELL, M.A. Sixth Edition. 1 vol., 12*s.* 6*d.*

Pulpit Commentary, The—*continued.*

Isaiah. By the Rev. Canon G. RAWLINSON, M.A. With Homilies by Rev. Prof. E. JOHNSON, M.A., Rev. W. CLARKSON, B.A., Rev. W. M. STATHAM, and Rev. R. TUCK, B.A. Second Edition. 2 vols., 15*s.* each.

Jeremiah. (Vol. I.) By the Rev. Canon T. K. CHEYNE, D.D. With Homilies by the Rev. W. F. ADENEY, M.A., Rev. A. F. MUIR, M.A., Rev. S. CONWAY, B.A., Rev. J. WAITE, B.A., and Rev. D. YOUNG, B.A. Third Edition. 15*s.*

Jeremiah (Vol. II.) and Lamentations. By Rev. Canon T. K. CHEYNE, D.D. With Homilies by Rev. Prof. J. R. THOMSON, M.A., Rev. W. F. ADENEY, M.A., Rev. A. F. MUIR, M.A., Rev. S. CONWAY, B.A., Rev. D. YOUNG, B.A. 15*s.*

Hosea and Joel. By the Rev. Prof. J. J. GIVEN, Ph.D., D.D. With Homilies by the Rev. Prof. J. R. THOMSON, M.A., Rev. A. ROWLAND, B.A., LL.B., Rev. C. JERDAN, M.A., LL.B., Rev. J. ORR, D.D., and Rev. D. THOMAS, D.D. 15*s.*

Pulpit Commentary, The. (*New Testament Series.*)

St. Mark. By Very Rev. E. BICKERSTETH, D.D., Dean of Lichfield. With Homilies by Rev. Prof. THOMSON, M.A., Rev. Prof. J. J. GIVEN, Ph.D., D.D., Rev. Prof. JOHNSON, M.A., Rev. A. ROWLAND, B.A., LL.B., Rev. A. MUIR, and Rev. R. GREEN. Fifth Edition. 2 vols., 10*s.* 6*d.* each.

St. John. By Rev. Prof. H. R. REYNOLDS, D.D. With Homilies by Rev. Prof. T. CROSKERY, D.D., Rev. Prof J. R. THOMSON, M.A., Rev. D. YOUNG, B.A., Rev. B. THOMAS, Rev. G. BROWN. Second Edition. 2 vols. 15*s.* each.

The Acts of the Apostles. By the Bishop of BATH and WELLS. With Homilies by Rev. Prof. P. C. BARKER, M.A., LL.B., Rev. Prof. E. JOHNSON, M.A., Rev. Prof. R. A. REDFORD, LL.B., Rev. R. TUCK, B.A., Rev. W. CLARKSON, B.A. Fourth Edition. 2 vols., 10*s.* 6*d.* each.

1 Corinthians. By the Ven. Archdeacon FARRAR, D.D. With Homilies by Rev. Ex-Chancellor LIPSCOMB, LL.D., Rev. DAVID THOMAS, D.D., Rev. D. FRASER, D.D., Rev. Prof. J. R. THOMSON, M.A., Rev. J. WAITE, B.A., Rev. R. TUCK, B.A., Rev. E. HURNDALL, M.A., and Rev. H. BREMNER, B.D. Fourth Edition. 15*s.*

2 Corinthians and Galatians. By the Ven. Archdeacon FARRAR, D.D., and Rev. Prebendary E. HUXTABLE. With Homilies by Rev. Ex-Chancellor LIPSCOMB, LL.D., Rev. DAVID THOMAS, D.D., Rev. DONALD FRASER, D.D., Rev. R. TUCK, B.A., Rev. E. HURNDALL, M.A., Rev. Prof. J. R. THOMSON, M.A., Rev. R. FINLAYSON, B.A., Rev. W. F. ADENEY, M.A., Rev. R. M. EDGAR, M.A., and Rev. T. CROSKERY, D.D. Second Edition. 21*s.*

Pulpit Commentary, The.—*continued.*

Ephesians, Philippians, and Colossians. By the Rev. Prof. W. G. BLAIKIE, D.D., Rev. B. C. CAFFIN, M.A., and Rev. G. G. FINDLAY, B.A. With Homilies by Rev. D. THOMAS, D.D., Rev. R. M. EDGAR, M.A., Rev. R. FINLAYSON, B.A., Rev. W. F. ADENEY, M.A., Rev. Prof. T. CROSKERY, D.D., Rev. E. S. PROUT, M.A., Rev. Canon VERNON HUTTON, and Rev. U. R. THOMAS, D.D. Second Edition. *21s.*

Thessalonians, Timothy, Titus, and Philemon. By the Bishop of Bath and Wells, Rev. Dr. GLOAG and Rev. Dr. EALES. With Homilies by the Rev. B. C. CAFFIN, M.A., Rev. R. FINLAYSON, B.A., Rev. Prof. T. CROSKERY, D.D., Rev. W. F. ADENEY, M.A., Rev. W. M. STATHAM, and Rev. D. THOMAS, D.D. *15s.*

Hebrews and James. By the Rev. J. BARMBY, D.D., and Rev Prebendary E. C. S. GIBSON, M.A. With Homiletics by the Rev. C. JERDAN, M.A., LL.B., and Rev. Prebendary E. C. S. GIBSON. And Homilies by the Rev. W. JONES, Rev. C. NEW, Rev. D. YOUNG, B.A., Rev. J. S. BRIGHT, Rev. T. F. LOCKYER, B.A., and Rev. C. JERDAN, M.A., LL.B. Second Edition. *15s.*

PUSEY, Dr.—**Sermons for the Church's Seasons from Advent to Trinity.** Selected from the Published Sermons of the late EDWARD BOUVERIE PUSEY, D.D. Crown 8vo, *5s.*

QUEKETT, Rev. W.—**My Sayings and Doings.** With Reminiscences of my Life. With Illustrations. Demy 8vo, *18s.*

RANKE, Leopold von.—**Universal History.** The oldest Historical Group of Nations and the Greeks. Edited by G. W. PROTHERO. Demy 8vo, *16s.*

RENDELL, J. M.—**Concise Handbook of the Island of Madeira.** With Plan of Funchal and Map of the Island. Fcap. 8vo, *1s. 6d.*

REVELL, W. F.—**Ethical Forecasts.** Crown 8vo, *3s. 6d.*

REYNOLDS, Rev. J. W.—**The Supernatural in Nature.** A Verification by Free Use of Science. Third Edition, Revised and Enlarged. Demy 8vo, *14s.*

The Mystery of Miracles. Third and Enlarged Edition. Crown 8vo, *6s.*

The Mystery of the Universe our Common Faith. Demy 8vo, *14s.*

The World to Come: Immortality a Physical Fact. Crown 8vo, *6s.*

RIBOT, Prof. Th.—**Heredity:** A Psychological Study of its Phenomena, its Laws, its Causes, and its Consequences. Second Edition, Large crown 8vo, *9s.*

RIVINGTON, Luke.—**Authority, or a Plain Reason for joining the Church of Rome.** Crown 8vo., 3*s.* 6*d.*

ROBERTSON, The late Rev. F. W., M.A.—**Life and Letters of.** Edited by the Rev. STOPFORD BROOKE, M.A.

I. Two vols., uniform with the Sermons. With Steel Portrait. Crown 8vo, 7*s.* 6*d.*

II. Library Edition, in Demy 8vo, with Portrait. 12*s.*

III. A Popular Edition, in 1 vol. Crown 8vo, 6*s.*

Sermons. Four Series. Small crown 8vo, 3*s.* 6*d.* each.

The Human Race, and other Sermons. Preached at Cheltenham, Oxford, and Brighton. New and Cheaper Edition. Small crown 8vo, 3*s.* 6*d.*

Notes on Genesis. New and Cheaper Edition. Small crown 8vo, 3*s.* 6*d.*

Expository Lectures on St. Paul's Epistles to the Corinthians. A New Edition. Small crown 8vo, 5*s.*

Lectures and Addresses, with other Literary Remains. A New Edition. Small crown 8vo, 5*s.*

An Analysis of Tennyson's "In Memoriam." (Dedicated by Permission to the Poet-Laureate.) Fcap. 8vo, 2*s.*

The Education of the Human Race. Translated from the German of GOTTHOLD EPHRAIM LESSING. Fcap. 8vo, 2*s.* 6*d.*

The above Works can also be had, bound in half-morocco.

*** A Portrait of the late Rev. F. W. Robertson, mounted for framing, can be had, 2*s.* 6*d.*

ROGERS, William.—**Reminiscences.** Compiled by R. H. HADDEN. With Portrait. Crown 8vo, 6*s.*

ROMANES, G. J.—**Mental Evolution in Animals.** With a Posthumous Essay on Instinct by CHARLES DARWIN, F.R.S. Demy 8vo, 12*s.*

ROSMINI SERBATI, Antonio.—**Life.** By the REV. W. LOCKHART. Second Edition. 2 vols. With Portraits. Crown 8vo, 12*s.*

ROSS, Janet.—**Italian Sketches.** With 14 full-page Illustrations. Crown 8vo, 7*s.* 6*d.*

RULE, Martin, M.A.—**The Life and Times of St. Anselm, Archbishop of Canterbury and Primate of the Britains.** 2 vols. Demy 8vo, 32*s.*

SAVERY, C. E.—**The Church of England; an Historical Sketch.** Crown 8vo.

SAYCE, Rev. Archibald Henry.—**Introduction to the Science of Language.** 2 vols. Second Edition. Large post 8vo, 21*s.*

SCOONES, W. Baptiste.—**Four Centuries of English Letters:** A Selection of 350 Letters by 150 Writers, from the Period of the Paston Letters to the Present Time. Third Edition. Large crown 8vo, 6*s.*

SEYMOUR, W. Digby, Q.C.,—Home Rule and State Supremacy. Crown 8vo, 3*s* 6*d*.

Shakspere's Works. The Avon Edition, 12 vols., fcap. 8vo, cloth, 18*s*.; in cloth box, 21*s*.; bound in 6 vols., cloth, 15*s*.

Shakspere's Works, an Index to. By EVANGELINE O'CONNOR. Crown 8vo, 5*s*.

SHELLEY, Percy Bysshe.—Life. By EDWARD DOWDEN, LL.D. 2 vols. With Portraits. Demy 8vo, 36*s*.

SHILLITO, Rev. Joseph.—Womanhood: its Duties, Temptations and Privileges. A Book for Young Women. Third Edition. Crown 8vo, 3*s*. 6*d*.

Shooting, Practical Hints on. Being a Treatise on the Shot Gun and its Management. By "20 Bore." With 55 Illustrations. Demy 8vo, 12*s*.

Sister Augustine, Superior of the Sisters of Charity at the St. Johannis Hospital at Bonn. Authorized Translation by HANS THARAU, from the German "Memorials of AMALIE VON LASAULX." Cheap Edition. Large crown 8vo, 4*s*. 6*d*.

SKINNER, James.—A Memoir. By the Author of "Charles Lowder." With a Preface by the Rev. Canon CARTER, and Portrait. Large crown, 7*s*. 6*d*.

*** Also a cheap Edition. With Portrait. Fourth Edition. Crown 8vo, 3*s*. 6*d*.

SMEATON, D. Mackenzie.—The Loyal Karens of Burma. Crown 8vo, 4*s*. 6*d*.

SMITH, Edward, M.D., LL.B., F.R.S.—Tubercular Consumption in its Early and Remediable Stages. Second Edition. Crown 8vo, 6*s*.

SMITH, L, A.—The Music of the Waters: Sailor's Chanties and Working Songs of the Sea. Demy 8vo.

Spanish Mystics. By the Editor of "Many Voices." Crown 8vo, 5*s*.

Specimens of English Prose Style from Malory to Macaulay. Selected and Annotated, with an Introductory Essay, by GEORGE SAINTSBURY. Large crown 8vo, printed on hand-made paper, parchment antique or cloth, 12*s*.; vellum, 15*s*.

Stray Papers on Education, and Scenes from School Life. By B. H. Second Edition. Small crown 8vo, 3*s*. 6*d*.

STREATFEILD, Rev. G. S., M.A.—Lincolnshire and the Danes. Large crown 8vo, 7*s*. 6*d*.

STRECKER-WISLICENUS.—Organic Chemistry. Translated and Edited, with Extensive Additions, by W. R. HODGKINSON, Ph.D., and A. J. GREENAWAY, F.I.C. Second and cheaper Edition. Demy 8vo, 12*s*. 6*d*.

Suakin, 1885; being a Sketch of the Campaign of this year. By an Officer who was there. Second Edition. Crown 8vo, 2*s.* 6*d.*

SULLY, James, M.A.—Pessimism: a History and a Criticism. Second Edition. Demy 8vo, 14*s.*

SWANWICK, Anna.—An Utopian Dream, and how it may be Realized. Fcap. 8vo, 1*s.*

SWEDENBORG, Eman.—De Cultu et Amore Dei ubi Agitur de Telluris ortu, Paradiso et Vivario, tum de Primogeniti Seu Adami Nativitate Infantia, et Amore. Crown 8vo, 6*s.*

On the Worship and Love of God. Treating of the Birth of the Earth, Paradise, and the Abode of Living Creatures. Translated from the original Latin. Crown 8vo, 7*s.* 6*d.*

Prodromus Philosophiæ Ratiocinantis de Infinito, et Causa Finali Creationis: deque Mechanismo Operationis Animæ et Corporis. Edidit THOMAS MURRAY GORMAN, M.A. Crown 8vo, 7*s.* 6*d.*

TACITUS.—The Agricola. A Translation. Small crown 8vo, 2*s.* 6*d.*

TARRING, C. J.—A Practical Elementary Turkish Grammar. Crown 8vo, 6*s.*

TAYLOR, Hugh.—The Morality of Nations. A Study in the Evolution of Ethics. Crown 8vo, 6*s.*

TAYLOR, Rev. Canon Isaac, LL.D.—The Alphabet. An Account of the Origin and Development of Letters. With numerous Tables and Facsimiles. 2 vols. Demy 8vo, 36*s.*

Leaves from an Egyptian Note-book. Crown 8vo.

TAYLOR, Jeremy.—The Marriage Ring. With Preface, Notes, and Appendices. Edited by FRANCIS BURDETT MONEY COUTTS. Small crown 8vo, 2*s.* 6*d.*

TAYLOR, Reynell, C.B., C.S.I. A Biography. By E. GAMBIER PARRY. With Portait and Map. Demy 8vo, 14*s.*

TAYLOR, Sedley.—Profit Sharing between Capital and Labour. To which is added a Memorandum on the Industrial Partnership at the Whitwood Collieries, by ARCHIBALD and HENRY BRIGGS, with remarks by SEDLEY TAYLOR. Crown 8vo, 2*s.* 6*d.*

THOM, J. Hamilton.—Laws of Life after the Mind of Christ. Two Series. Crown 8vo, 7*s.* 6*d.* each.

THOMPSON, Sir H.—Diet in Relation to Age and Activity. Fcap. 8vo, cloth, 1*s.* 6*d.*; paper covers, 1*s.*

TIDMAN, Paul F.—Money and Labour. 1*s.* 6*d.*

TODHUNTER, Dr. J.—A Study of Shelley. Crown 8vo, 7*s.*

TOLSTOI, Count Leo.—**Christ's Christianity.** Translated from the Russian. Large crown 8vo, 7*s.* 6*d.*

TRANT, William.—**Trade Unions: Their Origin, Objects, and Efficacy.** Small crown 8vo, 1*s.* 6*d.*; paper covers, 1*s.*

TRENCH, The late R. C., Archbishop.—**Letters and Memorials.** By the Author of "Charles Lowder." With two Portraits. 2 vols. 8vo, 21*s.*

Notes on the Parables of Our Lord. Fourteenth Edition. 8vo, 12*s.* Cheap Edition, 7*s.* 6*d.*

Notes on the Miracles of Our Lord. Twelfth Edition. 8vo, 12*s.* Cheap Edition, 7*s.* 6*d.*

Studies in the Gospels. Fifth Edition, Revised. 8vo, 10*s.* 6*d.*

Brief Thoughts and Meditations on Some Passages in Holy Scripture. Third Edition. Crown 8vo, 3*s.* 6*d.*

Synonyms of the New Testament. Tenth Edition, Enlarged. 8vo, 12*s.*

Sermons New and Old. Crown 8vo, 6*s.*

Westminster and other Sermons. Crown 8vo, 6*s.*

On the Authorized Version of the New Testament. Second Edition. 8vo, 7*s.*

Commentary on the Epistles to the Seven Churches in Asia. Fourth Edition, Revised. 8vo, 8*s.* 6*d.*

The Sermon on the Mount. An Exposition drawn from the Writings of St. Augustine, with an Essay on his Merits as an Interpreter of Holy Scripture. Fourth Edition, Enlarged. 8vo, 10*s.* 6*d.*

Shipwrecks of Faith. Three Sermons preached before the University of Cambridge in May, 1867. Fcap. 8vo, 2*s.* 6*d.*

Lectures on Mediæval Church History. Being the Substance of Lectures delivered at Queen's College, London. Second Edition. 8vo, 12*s.*

English, Past and Present. Thirteenth Edition, Revised and Improved. Fcap. 8vo, 5*s.*

On the Study of Words. Twentieth Edition, Revised. Fcap. 8vo, 5*s.*

Select Glossary of English Words Used Formerly in Senses Different from the Present. Sixth Edition, Revised and Enlarged. Fcap. 8vo, 5*s.*

Proverbs and Their Lessons. Seventh Edition, Enlarged. Fcap. 8vo, 4*s.*

Poems. Collected and Arranged anew. Ninth Edition. Fcap. 8vo, 7*s* 6*d.*

TRENCH, The late R. C., Archbishop.—continued.

Poems. Library Edition. 2 vols. Small crown 8vo, 10*s.*

Sacred Latin Poetry. Chiefly Lyrical, Selected and Arranged for Use. Third Edition, Corrected and Improved. Fcap. 8vo, 7*s.*

A Household Book of English Poetry. Selected and Arranged, with Notes. Fourth Edition, Revised. Extra fcap. 8vo, 5*s.* 6*d.*

An Essay on the Life and Genius of Calderon. With Translations from his "Life's a Dream" and "Great Theatre of the World." Second Edition, Revised and Improved. Extra fcap. 8vo, 5*s.* 6*d.*

Gustavus Adolphus in Germany, and other Lectures on the Thirty Years' War. Third Edition, Enlarged. Fcap. 8vo, 4*s.*

Plutarch: his Life, his Lives, and his Morals. Second Edition, Enlarged. Fcap. 8vo, 3*s.* 6*d.*

Remains of the late Mrs. Richard Trench. Being Selections from her Journals, Letters, and other Papers. New and Cheaper Issue. With Portrait. 8vo, 6*s.*

TUTHILL, C. A. H.—Origin and Development of Christian Dogma. Crown 8vo.

TWINING, Louisa.—Workhouse Visiting and Management during Twenty-Five Years. Small crown 8vo, 2*s.*

Two Centuries of Irish History. By various Writers. Edited by Prof. J. BRYCE. Demy 8vo.

VAL d'EREMAO, Rev. J. P.—The Serpent of Eden. A Philological and Critical Essay. Crown 8vo, 4*s.* 6*d.*

VICARY, J. Fulford.—Saga Time. With Illustrations. Crown 8vo, 7*s.* 6*d.*

VOLCKXSOM, E. W. v.—Catechism of Elementary Modern Chemistry. Small crown 8vo, 3*s.*

WALPOLE, Chas. George.—A Short History of Ireland from the Earliest Times to the Union with Great Britain. With 5 Maps and Appendices. Third Edition. Crown 8vo, 6*s.*

Words of Jesus Christ taken from the Gospels. Small crown 8vo, 2*s.* 6*d.*

WARD, Wilfrid.—The Wish to Believe. A Discussion Concerning the Temper of Mind in which a reasonable Man should undertake Religious Inquiry. Small crown 8vo, 5*s.*

WARD, William George, Ph.D.—Essays on the Philosophy of Theism. Edited, with an Introduction, by WILFRID WARD. 2 vols. Demy 8vo, 21*s.*

WARTER, J. W.—An Old Shropshire Oak. 2 vols. Demy 8vo, 28*s.*

WEDMORE, Frederick.—The Masters of Genre Painting. With Sixteen Illustrations. Post 8vo, 7*s.* 6*d.*

WHITMAN, Sidney.—Conventional Cant: its Results and Remedy. Crown 8vo, 6*s.*

WHITNEY, Prof. William Dwight.—Essentials of English Grammar, for the Use of Schools. Second Edition. Crown 8vo, 3*s.* 6*d.*

WHITWORTH, George Clifford.—An Anglo-Indian Dictionary: a Glossary of Indian Terms used in English, and of such English or other Non-Indian Terms as have obtained special meanings in India. Demy 8vo, cloth, 12*s.*

WILSON, Mrs. R. F.—The Christian Brothers. Their Origin and Work. With a Sketch of the Life of their Founder, the Ven. JEAN BAPTISTE, de la Salle. Crown 8vo, 6*s.*

WOLTMANN, Dr. Alfred, and WOERMANN, Dr. Karl.—History of Painting. With numerous Illustrations. Medium 8vo. Vol. I. Painting in Antiquity and the Middle Ages. 28*s.*; bevelled boards, gilt leaves, 30*s.* Vol. II. The Painting of the Renascence. 42*s.*; bevelled boards, gilt leaves, 45*s.*

YOUMANS, Edward L., M.D.—A Class Book of Chemistry, on the Basis of the New System. With 200 Illustrations. Crown 8vo, 5*s.*

YOUMANS, Eliza A.—First Book of Botany. Designed to Cultivate the Observing Powers of Children. With 300 Engravings. New and Cheaper Edition. Crown 8vo, 2*s.* 6*d.*

THE INTERNATIONAL SCIENTIFIC SERIES.

I. Forms of Water in Clouds and Rivers, Ice and Glaciers. By J. Tyndall, LL.D., F.R.S. With 25 Illustrations. Ninth Edition. 5*s.*

II. Physics and Politics; or, Thoughts on the Application of the Principles of "Natural Selection" and "Inheritance" to Political Society. By Walter Bagehot. Eighth Edition. 5*s.*

III. Foods. By Edward Smith, M.D., LL.B., F.R.S. With numerous Illustrations. Ninth Edition. 5*s.*

IV. Mind and Body: the Theories of their Relation. By Alexander Bain, LL.D. With Four Illustrations. Eighth Edition. 5*s.*

V. The Study of Sociology. By Herbert Spencer. Thirteenth Edition. 5*s.*

VI. The Conservation of Energy. By Balfour Stewart, M.A., LL.D., F.R.S. With 14 Illustrations. Seventh Edition. 5*s*.

VII. Animal Locomotion; or Walking, Swimming, and Flying. By J. B. Pettigrew, M.D., F.R.S., etc. With 130 Illustrations. Third Edition. 5*s*.

VIII. Responsibility in Mental Disease. By Henry Maudsley, M.D. Fourth Edition. 5*s*.

IX. The New Chemistry. By Professor J. P. Cooke. With 31 Illustrations. Ninth Edition. 5*s*.

X. The Science of Law. By Professor Sheldon Amos. Sixth Edition. 5*s*.

XI. Animal Mechanism: a Treatise on Terrestrial and Aerial Locomotion. By Professor E. J. Marey. With 117 Illustrations. Third Edition. 5*s*.

XII. The Doctrine of Descent and Darwinism. By Professor Oscar Schmidt. With 26 Illustrations. Seventh Edition. 5*s*.

XIII. The History of the Conflict between Religion and Science. By J. W. Draper, M.D., LL.D. Twentieth Edition. 5*s*.

XIV. Fungi: their Nature, Influences, and Uses. By M. C. Cooke, M.A., LL.D. Edited by the Rev. M. J. Berkeley, M.A., F.L.S. With numerous Illustrations. Fourth Edition. 5*s*.

XV. The Chemistry of Light and Photography. By Dr. Hermann Vogel. With 100 Illustrations. Fifth Edition. 5*s*.

XVI. The Life and Growth of Language. By Professor William Dwight Whitney. Fifth Edition. 5*s*.

XVII. Money and the Mechanism of Exchange. By W. Stanley Jevons, M.A., F.R.S. Eighth Edition. 5*s*.

XVIII. The Nature of Light. With a General Account of Physical Optics. By Dr. Eugene Lommel. With 188 Illustrations and a Table of Spectra in Chromo-lithography. Fourth Edition. 5*s*.

XIX. Animal Parasites and Messmates. By P. J. Van Beneden. With 83 Illustrations. Third Edition. 5*s*.

XX. On Fermentation. By Professor Schützenberger. With 28 Illustrations. Fourth Edition. 5*s*.

XXI. The Five Senses of Man. By Professor Bernstein. With 91 Illustrations. Fifth Edition. 5*s*.

XXII. The Theory of Sound in its Relation to Music. By Professor Pietro Blaserna. With numerous Illustrations. Third Edition. 5*s*.

XXIII. Studies in Spectrum Analysis. By J. Norman Lockyer, F.R.S. With six photographic Illustrations of Spectra, and numerous engravings on Wood. Fourth Edition. 6*s*. 6*d*.

XXIV. **A History of the Growth of the Steam Engine.** By Professor R. H. Thurston. With numerous Illustrations. Fourth Edition. 5*s*.

XXV. **Education as a Science.** By Alexander Bain, LL.D. Sixth Edition. 5*s*.

XXVI. **The Human Species.** By Professor A. de Quatrefages. Fourth Edition. 5*s*.

XXVII. **Modern Chromatics.** With Applications to Art and Industry. By Ogden N. Rood. With 130 original Illustrations. Second Edition. 5*s*.

XXVIII. **The Crayfish:** an Introduction to the Study of Zoology. By Professor T. H. Huxley. With 82 Illustrations. Fourth Edition. 5*s*.

XXIX. **The Brain as an Organ of Mind.** By H. Charlton Bastian, M.D. With numerous Illustrations. Third Edition. 5*s*.

XXX. **The Atomic Theory.** By Prof. Wurtz. Translated by E. Cleminshaw, F.C.S. Fifth Edition. 5*s*.

XXXI. **The Natural Conditions of Existence as they affect Animal Life.** By Karl Semper. With 2 Maps and 106 Woodcuts. Third Edition. 5*s*.

XXXII. **General Physiology of Muscles and Nerves.** By Prof. J. Rosenthal. Third Edition. With 75 Illustrations. 5*s*.

XXXIII. **Sight:** an Exposition of the Principles of Monocular and Binocular Vision. By Joseph le Conte, LL.D. Second Edition. With 132 Illustrations. 5*s*.

XXXIV. **Illusions:** a Psychological Study. By James Sully. Third Edition. 5*s*.

XXXV. **Volcanoes: what they are and what they teach.** By Professor J. W. Judd, F.R.S. With 96 Illustrations on Wood. Fourth Edition. 5*s*.

XXXVI. **Suicide:** an Essay on Comparative Moral Statistics. By Prof. H. Morselli. Second Edition. With Diagrams. 5*s*.

XXXVII. **The Brain and its Functions.** By J. Luys. With Illustrations. Second Edition. 5*s*.

XXXVIII. **Myth and Science:** an Essay. By Tito Vignoli. Third Edition. With Supplementary Note. 5*s*.

XXXIX. **The Sun.** By Professor Young. With Illustrations. Third Edition. 5*s*.

XL. **Ants, Bees, and Wasps:** a Record of Observations on the Habits of the Social Hymenoptera. By Sir John Lubbock, Bart., M.P. With 5 Chromo-lithographic Illustrations. Eighth Edition. 5*s*.

XLI. Animal Intelligence. By G. J. Romanes, LL.D., F.R.S. Fourth Edition. 5*s*.

XLII. The Concepts and Theories of Modern Physics. By J. B. Stallo. Third Edition. 5*s*.

XLIII. Diseases of Memory; An Essay in the Positive Psychology. By Prof. Th. Ribot. Third Edition. 5*s*.

XLIV. Man before Metals. By N. Joly, with 148 Illustrations. Fourth Edition. 5*s*.

XLV. The Science of Politics. By Prof. Sheldon Amos. Third Edition. 5*s*.

XLVI. Elementary Meteorology. By Robert H. Scott. Fourth Edition. With Numerous Illustrations. 5*s*.

XLVII. The Organs of Speech and their Application in the Formation of Articulate Sounds. By Georg Hermann Von Meyer. With 47 Woodcuts. 5*s*.

XLVIII. Fallacies. A View of Logic from the Practical Side. By Alfred Sidgwick. Second Edition. 5*s*.

XLIX. Origin of Cultivated Plants. By Alphonse de Candolle. Second Edition. 5*s*.

L. Jelly-Fish, Star-Fish, and Sea-Urchins. Being a Research on Primitive Nervous Systems. By G. J. Romanes. With Illustrations. 5*s*.

LI. The Common Sense of the Exact Sciences. By the late William Kingdon Clifford. Second Edition. With 100 Figures. 5*s*.

LII. Physical Expression: Its Modes and Principles. By Francis Warner, M.D., F.R.C.P., Hunterian Professor of Comparative Anatomy and Physiology, R.C.S.E. With 50 Illustrations. 5*s*.

LIII. Anthropoid Apes. By Robert Hartmann. With 63 Illustrations. 5*s*.

LIV. The Mammalia in their Relation to Primeval Times. By Oscar Schmidt. With 51 Woodcuts. 5*s*.

LV. Comparative Literature. By H. Macaulay Posnett, LL.D. 5*s*.

LVI. Earthquakes and other Earth Movements. By Prof. John Milne. With 38 Figures. Second Edition. 5*s*.

LVII. Microbes, Ferments, and Moulds. By E. L. Trouessart. With 107 Illustrations. 5*s*.

LVIII. Geographical and Geological Distribution of Animals. By Professor A. Heilprin. With Frontispiece. 5*s*.

LIX. Weather. A Popular Exposition of the Nature of Weather Changes from Day to Day. By the Hon. Ralph Abercromby. Second Edition. With 96 Illustrations. 5*s*.

LX. **Animal Magnetism.** By Alfred Binet and Charles Féré. 5*s.*

LXI. **Manual of British Discomycetes,** with descriptions of all the Species of Fungi hitherto found in Britain included in the Family, and Illustrations of the Genera. By William Phillips, F.L.S. 5*s.*

LXII. **International Law.** With Materials for a Code of International Law. By Professor Leone Levi. 5*s.*

LXIII. **The Geological History of Plants.** By Sir J. William Dawson. With 80 Figures. 5*s.*

LXIV. **The Origin of Floral Structures through Insect and other Agencies.** By Rev. Prof. G. Henslow. With 88 Illustrations. 5*s.*

LXV. **On the Senses, Instincts, and Intelligence of Animals.** With special Reference to Insects. By Sir John Lubbock, Bart., M.P. 100 Illustrations. 5*s.*

MILITARY WORKS.

BRACKENBURY, Col. C. B., R.A.—**Military Handbooks for Regimental Officers.**

I. **Military Sketching and Reconnaissance.** By Col. F. J. Hutchison and Major H. G. MacGregor. Fifth Edition. With 16 Plates. Small crown 8vo, 4*s.*

II. **The Elements of Modern Tactics Practically applied to English Formations.** By Lieut.-Col. Wilkinson Shaw. Sixth Edition. With 25 Plates and Maps. Small crown 8vo, 9*s.*

III. **Field Artillery.** Its Equipment, Organization and Tactics. By Major Sisson C. Pratt, R.A. With 12 Plates. Third Edition. Small crown 8vo, 6*s.*

IV. **The Elements of Military Administration.** First Part: Permanent System of Administration. By Major J. W. Buxton. Small crown 8vo, 7*s.* 6*d.*

V. **Military Law:** Its Procedure and Practice. By Major Sisson C. Pratt, R.A. Third Edition. Revised. Small crown 8vo, 4*s.* 6*d.*

VI. **Cavalry in Modern War.** By Major-General F. Chenevix Trench. Small crown 8vo, 6*s.*

VII. **Field Works.** Their Technical Construction and Tactical Application. By the Editor, Col. C. B. Brackenbury, R.A. Small crown 8vo.

BROOKE, Major, C. K.—**A System of Field Training.** Small crown 8vo, cloth limp, 2*s.*

Campaign of Fredericksburg, November—December, 1862. A Study for Officers of Volunteers. By a Line Officer. With 5 Maps and Plans. Second Edition. Crown 8vo, 5*s.*

CLERY, C. Francis, Col.—**Minor Tactics.** With 26 Maps and Plans. Seventh Edition, Revised. Crown 8vo, 9*s.*

COLVILE, Lieut.-Col. C. F.—**Military Tribunals.** Sewed, 2*s.* 6*d.*

CRAUFURD, Capt. H. J.—**Suggestions for the Military Training of a Company of Infantry.** Crown 8vo, 1*s.* 6*d.*

HAMILTON, Capt. Ian, A.D.C.—**The Fighting of the Future.** 1*s.*

HARRISON, Col. R.—**The Officer's Memorandum Book for Peace and War.** Fourth Edition, Revised throughout. Oblong 32mo, red basil, with pencil, 3*s.* 6*d.*

Notes on Cavalry Tactics, Organisation, etc. By a Cavalry Officer. With Diagrams. Demy 8vo, 12*s.*

PARR, Col. H. Hallam, C.M.G.—**The Dress, Horses, and Equipment of Infantry and Staff Officers.** Crown 8vo, 1*s.*

Further Training and Equipment of Mounted Infantry. Crown 8vo, 1*s.*

SCHAW, Col. H.—**The Defence and Attack of Positions and Localities.** Third Edition, Revised and Corrected. Crown 8vo, 3*s.* 6*d.*

STONE, Capt. F. Gleadowe, R.A.—**Tactical Studies from the Franco-German War of 1870-71.** With 22 Lithographic Sketches and Maps. Demy 8vo, 10*s.* 6*d.*

WILKINSON, H. Spenser, Capt. 20th Lancashire R.V.—**Citizen Soldiers.** Essays towards the Improvement of the Volunteer Force. Crown 8vo, 2*s.* 6*d.*

POETRY.

ADAM OF ST. VICTOR.—**The Liturgical Poetry of Adam of St. Victor.** From the text of GAUTIER. With Translations into English in the Original Metres, and Short Explanatory Notes, by DIGBY S. WRANGHAM, M.A. 3 vols. Crown 8vo, printed on hand-made paper, boards, 21*s.*

ALEXANDER, William, D.D., Bishop of Derry.—**St. Augustine's Holiday,** and other Poems. Crown 8vo, 6*s.*

AUCHMUTY, A. C.—**Poems of English Heroism:** From Brunanburh to Lucknow; from Athelstan to Albert. Small crown 8vo, 1*s.* 6*d.*

BARNES, William.—**Poems of Rural Life, in the Dorset Dialect.** New Edition, complete in one vol. Crown 8vo, 6*s.*

BAYNES, Rev. Canon H. R.—**Home Songs for Quiet Hours.** Fourth and Cheaper Edition. Fcap. 8vo, cloth, 2*s.* 6*d.*

BEVINGTON, L. S.—**Key Notes.** Small crown 8vo, 5*s.*

BLUNT, Wilfrid Scawen.—**The Wind and the Whirlwind.** Demy 8vo, 1*s.* 6*d.*

The Love Sonnets of Proteus. Fifth Edition, 18mo. Cloth extra, gilt top, 5*s.*

Book of Verse, A. By J. R. W. Small crown 8vo, 2*s.* 6*d.*

BOWEN, H. C., M.A.—**Simple English Poems.** English Literature for Junior Classes. In Four Parts. Parts I., II., and III., 6*d.* each, and Part IV., 1*s.* Complete, 3*s.*

BRYANT, W. C.—**Poems.** Cheap Edition, with Frontispiece. Small crown 8vo, 3*s.* 6*d.*

Calderon's Dramas: the Wonder-Working Magician—Life is a Dream—the Purgatory of St. Patrick. Translated by DENIS FLORENCE MACCARTHY. Post 8vo, 10*s.*

Camoens' Lusiads.—Portuguese Text, with Translation by J. J. AUBERTIN. Second Edition. 2 vols. Crown 8vo, 12*s.*

CAMPBELL, Lewis.—**Sophocles.** The Seven Plays in English Verse. Crown 8vo, 7*s.* 6*d.*

CHRISTIE, Albany J.—**The End of Man.** Fourth Edition. Fcap. 8vo, 2*s.* 6*d.*

COXHEAD, Ethel.—**Birds and Babies.** With 33 Illustrations. Imp. 16mo, 1*s.*

Dante's Divina Commedia. Translated in the *Terza Rima* of Original, by F. K. H. HASELFOOT. Demy 8vo, 16*s.*

DENNIS, J.—**English Sonnets.** Collected and Arranged by. Small crown 8vo, 2*s.* 6*d.*

DE VERE, Aubrey.—**Poetical Works.**

I. THE SEARCH AFTER PROSERPINE, etc. 6*s.*
II. THE LEGENDS OF ST. PATRICK, etc. 6*s.*
III. ALEXANDER THE GREAT, etc. 6*s.*

The Foray of Queen Meave, and other Legends of Ireland's Heroic Age. Small crown 8vo, 5*s.*

Legends of the Saxon Saints. Small crown 8vo, 6*s.*

Legends and Records of the Church and the Empire. Small crown 8vo, 6*s.*

DOBSON, Austin.—**Old World Idylls** and other Verses. Eighth Edition. Elzevir 8vo, gilt top, 6*s.*

At the Sign of the Lyre. Fifth Edition. Elzevir 8vo, gilt top, 6*s.*

Dorica. By E. D. S. Small crown 8vo, 5*s.*

DOWDEN, Edward, LL.D.—**Shakspere's Sonnets.** With Introduction and Notes. Large post 8vo, 7*s.* 6*d.*

DUTT, Toru.—**A Sheaf Gleaned in French Fields.** New Edition. Demy 8vo, 10*s.* 6*d.*

Ancient Ballads and Legends of Hindustan. With an Introductory Memoir by EDMUND GOSSE. Second Edition, 18mo. Cloth extra, gilt top, 5*s.*

ELLIOTT, Ebenezer, The Corn Law Rhymer.—**Poems.** Edited by his son, the Rev. EDWIN ELLIOTT, of St. John's, Antigua. 2 vols. Crown 8vo, 18*s.*

English Verse. Edited by W. J. LINTON and R. H. STODDARD. 5 vols. Crown 8vo, cloth, 5*s.* each.

I. CHAUCER TO BURNS.
II. TRANSLATIONS.
III. LYRICS OF THE NINETEENTH CENTURY.
IV. DRAMATIC SCENES AND CHARACTERS.
V. BALLADS AND ROMANCES.

GOSSE, Edmund.—**New Poems.** Crown 8vo, 7*s.* 6*d.*

Firdausi in Exile, and other Poems. Second Edition. Elzevir 8vo, gilt top, 6*s.*

GURNEY, Rev. Alfred.—**The Vision of the Eucharist,** and other Poems. Crown 8vo, 5*s.*

A Christmas Faggot. Small crown 8vo, 5*s.*

HAMILTON, Ian.—**The Ballad of Hadji,** and other Poems. With Frontispiece and Vignettes. Elzevir 8vo, 3*s.* 6*d.*

HARRISON, Clifford.—**In Hours of Leisure.** Second Edition. Crown 8vo, 5*s.*

HEYWOOD, J. C.—**Herodias,** a Dramatic Poem. New Edition, Revised. Small crown 8vo, 5*s.*

Antonius. A Dramatic Poem. New Edition, Revised. Small crown 8vo, 5*s.*

Salome. A Dramatic Poem. Small crown 8vo, 5*s.*

HICKEY, E. H.—**A Sculptor,** and other Poems. Small crown 8vo, 5*s.*

KEATS, John.—**Poetical Works.** Edited by W. T. ARNOLD. Large crown 8vo, choicely printed on hand-made paper, with Portrait in *eau-forte.* Parchment or cloth, 12*s.*; vellum, 15*s.* New Edition, crown 8vo, cloth, 3*s.* 6*d.*

KING, Mrs. Hamilton.—**The Disciples.** Ninth Edition. Small crown 8vo, 5*s.*; Elzevir Edition, cloth extra, 6*s.*

A Book of Dreams. Third Edition. Crown 8vo, 3*s.* 6*d.*

The Sermon in the Hospital (From "The Dimples"). Fcap. 8vo, 1*s.* Cheap Edition for distribution 3*d.*, or 20*s.* per 100.

LANG, A.—**XXXII. Ballades in Blue China.** Elzevir 8vo, 5*s.*

Rhymes à la Mode. With Frontispiece by E. A. Abbey. Second Edition. Elzevir 8vo, cloth extra, gilt top, 5*s.*

LAWSON, Right Hon. Mr. Justice.—**Hymni Usitati Latine Redditi**: with other Verses. Small 8vo, parchment, 5*s.*

Living English Poets MDCCCLXXXII. With Frontispiece by Walter Crane. Second Edition. Large crown 8vo. Printed on hand-made paper. Parchment or cloth, 12*s.*; vellum, 15*s.*

LOCKER, F.—**London Lyrics.** Tenth Edition. With Portrait, Elzevir 8vo. Cloth extra, gilt top, 5*s.*

Love in Idleness. A Volume of Poems. With an Etching by W. B. Scott. Small crown 8vo, 5*s.*

MAGNUSSON, Eirikr, M.A., and PALMER, E. H., M.A.—**Johan Ludvig Runeberg's Lyrical Songs, Idylls, and Epigrams.** Fcap. 8vo, 5*s.*

Matin Songs. Small crown 8vo, 2*s.*

MEREDITH, Owen [The Earl of Lytton].—**Lucile.** New Edition. With 32 Illustrations. 16mo, 3*s.* 6*d.* Cloth extra, gilt edges, 4*s.* 6*d.*

MORRIS, Lewis.—**Poetical Works of.** New and Cheaper Editions, with Portrait. Complete in 3 vols., 5*s.* each.

Vol. I. contains "Songs of Two Worlds." Twelfth Edition.
Vol. II. contains "The Epic of Hades." Twenty-second Edition.
Vol. III. contains "Gwen" and "The Ode of Life." Seventh Edition.
Vol. IV. contains "Songs Unsung" and "Gycia." Fifth Edition.

Songs of Britain. Third Edition. Fcap. 8vo, 5*s.*

The Epic of Hades. With 16 Autotype Illustrations, after the Drawings of the late George R. Chapman. 4to, cloth extra, gilt leaves, 21*s.*

The Epic of Hades. Presentation Edition. 4to, cloth extra, gilt leaves, 10*s.* 6*d.*

The Lewis Morris Birthday Book. Edited by S. S. COPEMAN, with Frontispiece after a Design by the late George R. Chapman. 32mo, cloth extra, gilt edges, 2*s.*; cloth limp, 1*s.* 6*d.*

MORSHEAD, E. D. A.—**The House of Atreus.** Being the Agamemnon, Libation-Bearers, and Furies of Æschylus. Translated into English Verse. Crown 8vo, 7*s.*

MORSHEAD, E. D. A.—continued.

The Suppliant Maidens of Æschylus. Crown 8vo, 3*s.* 6*d.*

MULHOLLAND, Rosa.—Vagrant Verses. Small crown 8vo, 5*s.*

NADEN, Constance C. W.—A Modern Apostle, and other Poems. Small crown 8vo, 5*s.*

NOEL, The Hon. Roden.—A Little Child's Monument. Third Edition. Small crown 8vo, 3*s.* 6*d.*

The House of Ravensburg. New Edition. Small crown 8vo, 6*s.*

The Red Flag, and other Poems. New Edition. Small crown 8vo, 6*s.*

Songs of the Heights and Deeps. Crown 8vo, 6*s.*

O'HAGAN, John.—The Song of Roland. Translated into English Verse. New and Cheaper Edition. Crown 8vo, 5*s.*

PFEIFFER, Emily.—The Rhyme of the Lady of the Rock, and How it Grew. Second Edition. Small crown 8vo, 3*s.* 6*d.*

Gerard's Monument, and other Poems. Second Edition. Crown 8vo, 6*s.*

Under the Aspens: Lyrical and Dramatic. With Portrait. Crown 8vo, 6*s.*

Rare Poems of the 16th and 17th Centuries. Edited by W. J. LINTON. Crown 8vo, 5*s.*

RHOADES, James.—The Georgics of Virgil. Translated into English Verse. Small crown 8vo, 5*s.*

Poems. Small crown 8vo, 4*s.* 6*d.*

Dux Redux. A Forest Tangle. Small crown 8vo, 3*s.* 6*d.*

ROBINSON, A. Mary F.—A Handful of Honeysuckle. Fcap. 8vo, 3*s.* 6*d.*

The Crowned Hippolytus. Translated from Euripides. With New Poems. Small crown 8vo, 5*s.*

SCOTT, Fredk. George.—The Soul's Quest. Small crown 8vo.

SHARP, Isaac.—Saul of Tarsus, and other Poems. Small crown 8vo, 2*s.* 6*d.*

SMITH, J. W. Gilbart.—The Loves of Vandyck. A Tale of Genoa. Small crown 8vo, 2*s.* 6*d.*

The Log o' the "Norseman." Small crown 8vo, 5*s.*

Serbelloni. Small crown 8vo, 5*s.*

Sophocles: The Seven Plays in English Verse. Translated by LEWIS CAMPBELL. Crown 8vo, 7*s.* 6*d.*

SYMONDS, John Addington.—**Vagabunduli Libellus.** Crown 8vo, 6*s.*

Tasso's Jerusalem Delivered. Translated by Sir JOHN KINGSTON JAMES, Bart. Two Volumes. Printed on hand-made paper, parchment, bevelled boards. Large crown 8vo, 21*s.*

TAYLOR, Sir H.—**Works.** Complete in Five Volumes. Crown 8vo, 30*s.*

Philip Van Artevelde. Fcap. 8vo, 3*s.* 6*d.*

The Virgin Widow, etc. Fcap. 8vo, 3*s.* 6*d.*

TODHUNTER, Dr. J.—**Laurella,** and other Poems. Crown 8vo, 6*s.* 6*d.*

Forest Songs. Small crown 8vo, 3*s.* 6*d.*

The True Tragedy of Rienzi: a Drama. 3*s.* 6*d.*

Alcestis: a Dramatic Poem. Extra fcap. 8vo, 5*s.*

Helena in Troas. Small crown 8vo, 2*s.* 6*d.*

The Banshee, and other Poems. Small crown 8vo, 3*s.* 6*d.*

TYNAN, Katherine.—**Louise de la Valliere,** and other Poems. Small crown 8vo, 3*s.* 6*d.*

Shamrocks. Small crown 8vo, 5*s.*

TYRER, C. E.—**Fifty Sonnets.** Small crown 8vo, 1*s.* 6*d.*

Victorian Hymns; English Sacred Songs of Fifty Years. Dedicated to the Queen. Large post 8vo, 10*s.* 6*d.*

WILLIS, E. Cooper, Q.C.—**Tales and Legends in Verse.** Small crown 8vo, 3*s.* 6*d.*

Wordsworth Birthday Book, The. Edited by ADELAIDE and VIOLET WORDSWORTH. 32mo, limp cloth, 1*s.* 6*d.*; cloth extra, 2*s.*

NOVELS AND TALES.

BANKS, Mrs. G. L.—**God's Providence House.** Crown 8vo, 6*s.*

CHICHELE, Mary.—**Doing and Undoing.** A Story. Crown 8vo. 4*s.* 6*d.*

CRAWFURD, Oswald.—**Sylvia Arden.** With Frontispiece. Crown 8vo, 6*s.*

GARDINER, Linda.—**His Heritage.** With Frontispiece. Crown 8vo, 6*s.*

GRAY, Maxwell.—**The Silence of Dean Maitland.** Fifteenth thousand. With Frontispiece. Crown 8vo, 6*s.*

GREY, Rowland.—**In Sunny Switzerland.** A Tale of Six Weeks. Second Edition. Small crown 8vo, 5*s.*

GREY, Rowland.—continued.

Lindenblumen and other Stories. Small crown 8vo, 5*s.*

By Virtue of his Office. Crown 8vo, 6*s.*

HUNTER, Hay.—**The Crime of Christmas Day.** A Tale of the Latin Quarter. By the Author of "My Ducats and my Daughter." 1*s.*

HUNTER, Hay, and WHYTE, Walter.—**My Ducats and My Daughter.** With Frontispiece. Crown 8vo, 6*s.*

INGELOW, Jean.—**Off the Skelligs:** a Novel. With Frontispiece. Crown 8vo, 6*s.*

JENKINS, Edward.—**A Secret of Two Lives.** Crown 8vo, 2*s.* 6*d.*

KIELLAND, Alexander L.—**Garman and Worse.** A Norwegian Novel. Authorized Translation, by W. W. Kettlewell. Crown 8vo, 6*s.*

LANG, Andrew.—**In the Wrong Paradise,** and other Stories. Crown 8vo, 6*s.*

MACDONALD, G.—**Donal Grant.** A Novel. With Frontispiece. Crown 8vo, 6*s.*

Home Again. With Frontispiece. Crown 8vo, 6*s.*

Castle Warlock. A Novel. With Frontispiece. Crown 8vo, 6*s.*

Malcolm. With Portrait of the Author engraved on Steel. Crown 8vo, 6*s.*

The Marquis of Lossie. With Frontispiece. Crown 8vo, 6*s.*

St. George and St. Michael. With Frontispiece. Crown 8vo, 6*s.*

What's Mine's Mine. With Frontispiece. Crown 8vo, 6*s.*

Annals of a Quiet Neighbourhood. With Frontispiece. Crown 8vo, 6*s.*

The Seaboard Parish: a Sequel to "Annals of a Quiet Neighbourhood." With Frontispiece. Crown 8vo, 6*s.*

Wilfred Cumbermede. An Autobiographical Story. With Frontispiece. Crown 8vo, 6*s.*

Thomas Wingfold, Curate. With Frontispiece. Crown 8vo, 6*s.*

Paul Faber, Surgeon. With Frontispiece. Crown 8vo, 6*s.*

The Elect Lady. With Frontispiece. Crown 8vo, 6*s.*

MALET, Lucas.—**Colonel Enderby's Wife.** A Novel. With Frontispiece. Crown 8vo, 6*s.*

A Counsel of Perfection. With Frontispiece. Crown 8vo, 6*s.*

MULHOLLAND, Rosa.—**Marcella Grace.** An Irish Novel. Crown 8vo. 6*s.*

OGLE, Anna C.—**A Lost Love.** Small crown 8vo, 2*s.* 6*d.*

PALGRAVE, W. Gifford.—**Hermann Agha:** an Eastern Narrative. Crown 8vo, 6*s.*

Romance of the Recusants. By the Author of "Life of a Prig." Crown 8vo, 5*s.*

SEVERNE, Florence.—**The Pillar House.** With Frontispiece. Crown 8vo, 6*s.*

SHAW, Flora L.—**Castle Blair:** a Story of Youthful Days. Crown 8vo, 3*s.* 6*d.*

STRETTON, Hesba.—**Through a Needle's Eye:** a Story. With Frontispiece. Crown 8vo, 6*s.*

TAYLOR, Col. Meadows, C.S.I., M.R.I.A.—**Seeta:** a Novel. With Frontispiece. Crown 8vo, 6*s.*

Tippoo Sultaun: a Tale of the Mysore War. With Frontispiece. Crown 8vo, 6*s.*

Ralph Darnell. With Frontispiece. Crown 8vo, 6*s.*

A Noble Queen. With Frontispiece. Crown 8vo, 6*s.*

The Confessions of a Thug. With Frontispiece. Crown 8vo, 6*s.*

Tara: a Mahratta Tale. With Frontispiece. Crown 8vo, 6*s.*

Within Sound of the Sea. With Frontispiece. Crown 8vo, 6*s.*

BOOKS FOR THE YOUNG.

Brave Men's Footsteps. A Book of Example and Anecdote for Young People. By the Editor of "Men who have Risen." With 4 Illustrations by C. Doyle. Ninth Edition. Crown 8vo, 2*s.* 6*d.*

COXHEAD, Ethel.—**Birds and Babies.** With 33 Illustrations. Second Edition. Imp. 16mo, cloth, 1*s.*

DAVIES, G. Christopher.—**Rambles and Adventures of our School Field Club.** With 4 Illustrations. New and Cheaper Edition. Crown 8vo, 3*s.* 6*d.*

EDMONDS, Herbert.—**Well Spent Lives:** a Series of Modern Biographies. New and Cheaper Edition. Crown 8vo, 3*s.* 6*d.*

EVANS, Mark.—**The Story of our Father's Love,** told to Children. Sixth and Cheaper Edition of Theology for Children. With 4 Illustrations. Fcap. 8vo, 1*s.* 6*d.*

MAC KENNA, S. J.—**Plucky Fellows.** A Book for Boys. With 6 Illustrations. Fifth Edition. Crown 8vo, 3*s.* 6*d.*

MALET, Lucas.—**Little Peter.** A Christmas Morality for Children of any Age. With numerous Illustrations. Fourth thousand. 5*s.*

REANEY, Mrs. G. S.—**Waking and Working**; or, From Girlhood to Womanhood. New and Cheaper Edition. With a Frontispiece. Crown 8vo, 3*s.* 6*d.*

Blessing and Blessed: a Sketch of Girl Life. New and Cheaper Edition. Crown 8vo, 3*s.* 6*d.*

Rose Gurney's Discovery. A Story for Girls. Dedicated to their Mothers. Crown 8vo, 3*s.* 6*d.*

English Girls: Their Place and Power. With Preface by the Rev. R. W. Dale. Fifth Edition. Fcap. 8vo, 2*s.* 6*d.*

Just Anyone, and other Stories. Three Illustrations. Royal 16mo, 1*s.* 6*d.*

Sunbeam Willie, and other Stories. Three Illustrations. Royal 16mo, 1*s.* 6*d.*

Sunshine Jenny, and other Stories. Three Illustrations. Royal 16mo, 1*s.* 6*d.*

STORR, Francis, and TURNER, Hawes.—**Canterbury Chimes**; or, Chaucer Tales re-told to Children. With 6 Illustrations from the Ellesmere Manuscript. Third Edition. Fcap. 8vo, 3*s.* 6*d.*

STRETTON, Hesba.—**David Lloyd's Last Will.** With 4 Illustrations. New Edition. Royal 16mo, 2*s.* 6*d.*

WHITAKER, Florence.—**Christy's Inheritance.** A London Story, Illustrated. Royal 16mo, 1*s.* 6*d.*

PRINTED BY WILLIAM CLOWES AND SONS, LIMITED, LONDON AND BECCLES.

MESSRS.

KEGAN PAUL, TRENCH & CO.'S

EDITIONS OF

SHAKSPERE'S WORKS.

THE PARCHMENT LIBRARY EDITION.

THE AVON EDITION.

The Text of these Editions is mainly that of Delius. Wherever a variant reading is adopted, some good and recognized Shaksperian Critic has been followed. In no case is a new rendering of the text proposed; nor has it been thought necessary to distract the reader's attention by notes or comments.

1, PATERNOSTER SQUARE.

[P. T. O.

SHAKSPERE'S WORKS.

THE PARCHMENT LIBRARY EDITION.

In 12 volumes Elzevir 8vo., choicely printed on hand-made paper, and bound in parchment or cloth, price £3 12*s.*, or in vellum, price £4 10*s.*

The set of 12 volumes may also be had in a strong cloth box, price £3 17*s.*, or with an oak hanging shelf, £3 18*s.*



SOME PRESS NOTICES.

". . . There is, perhaps, no edition in which the works of Shakspere can be read in such luxury of type and quiet distinction of form as this, and we warmly recommend it."—*Pall Mall Gazette.*

"For elegance of form and beauty of typography, no edition of Shakspere hitherto published has excelled the 'Parchment Library Edition.' . . . They are in the strictest sense pocket volumes, yet the type is bold, and, being on fine white hand-made paper, can hardly tax the weakest of sight. The print is judiciously confined to the text, notes being more appropriate to library editions. The whole will be comprised in the cream-coloured parchment which gives the name to the series."—*Daily News.*

"The Parchment Library Edition of Shakspere needs no further praise."—*Saturday Review.*

Just published. Price 5*s.*

AN INDEX TO THE WORKS OF SHAKSPERE.

Applicable to all editions of Shakspere, and giving reference, by topics, to notable passages and significant expressions; brief histories of the plays; geographical names and historic incidents; mention of all characters and sketches of important ones; together with explanations of allusions and obscure and obsolete words and phrases.

By EVANGELINE M. O'CONNOR.

LONDON: KEGAN PAUL, TRENCH & CO., 1, PATERNOSTER SQUARE.

SHAKSPERE'S WORKS.

THE AVON EDITION.

Printed on thin opaque paper, and forming 12 handy volumes, cloth, 18*s*., or bound in 6 volumes, 15*s*.

The set of 12 volumes may also be had in a cloth box, price 21*s*., or bound in Roan, Persian, Crushed Persian Levant, Calf, or Morocco, and enclosed in an attractive leather box at prices from 31*s*. 6*d*. upwards.



SOME PRESS NOTICES.

"This edition will be useful to those who want a good text, well and clearly printed, in convenient little volumes that will slip easily into an overcoat pocket or a travelling-bag."—*St. James's Gazette.*

"We know no prettier edition of Shakspere for the price."—*Academy.*

"It is refreshing to meet with an edition of Shakspere of convenient size and low price, without either notes or introductions of any sort to distract the attention of the reader."—*Saturday Review.*

"It is exquisite. Each volume is handy, is beautifully printed, and in every way lends itself to the taste of the cultivated student of Shakspere."—*Scotsman.*

LONDON: KEGAN PAUL, TRENCH & CO., 1, PATERNOSTER SQUARE.

SHAKSPERE'S WORKS.

SPECIMEN OF TYPE.

Salar. My wind, cooling my broth,
Would blow me to an ague, when I thought
What harm a wind too great might do at sea.
I should not see the sandy hour-glass run
But I should think of shallows and of flats,
And see my wealthy Andrew, dock'd in sand,
Vailing her high-top lower than her ribs
To kiss her burial. Should I go to church
And see the holy edifice of stone,
And not bethink me straight of dangerous rocks,
Which touching but my gentle vessel's side,
Would scatter all her spices on the stream,
Enrobe the roaring waters with my silks,
And, in a word, but even now worth this,
And now worth nothing? Shall I have the thought
To think on this, and shall I lack the thought
That such a thing bechanc'd would make me sad?
But tell not me: I know Antonio
Is sad to think upon his merchandise.

Ant. Believe me, no: I thank my fortune for it,
My ventures are not in one bottom trusted,
Nor to one place; nor is my whole estate
Upon the fortune of this present year:
Therefore my merchandise makes me not sad.

Salar. Why, then you are in love.

Ant. Fie, fie!

Salar. Not in love neither? Then let us say you are sad,
Because you are not merry; and 'twere as easy
For you to laugh, and leap, and say you are merry,
Because you are not sad. Now, by two-headed Janus,
Nature hath fram'd strange fellows in her time:
Some that will evermore peep through their eyes
And laugh like parrots at a bag-piper;
And other of such vinegar aspect

LONDON: KEGAN PAUL, TRENCH & CO., 1, PATERNOSTER SQUARE.

85-B8802

CONS.
SPECIAL
NH
510
V87
1888

85-B
8802

THE GETTY CENTER
LIBRARY

THE

INTERNATIONAL

SCIENTIFIC SERIES